

Correlations Between COVID-19 and Dengue

Paula Bergero^a, Laura P. Schaposnik^{*,b}, Grace Wang^c
(^{*}) *Corresponding author: schapos@uic.edu*

A dramatic increase in the number of outbreaks of Dengue has recently been reported, and climate change is likely to extend the geographical spread of the disease. In this context, this paper shows how a neural network approach can incorporate Dengue and COVID-19 data as well as external factors (such as social behaviour or climate variables), to develop predictive models that could improve our knowledge and provide useful tools for health policy makers. Through the use of neural networks with different social and natural parameters, in this paper we define a *Correlation Model* through which we show that the number of cases of COVID-19 and Dengue have very similar trends. We then illustrate the relevance of our model by extending it to a Long short-term memory model (LSTM) that incorporates both diseases, and using this to estimate Dengue infections via COVID-19 data in countries that lack sufficient Dengue data.

Keywords: COVID-19, Dengue, neural network

I. INTRODUCTION

Since its emergence, COVID-19 has been studied in correlation with many other infectious diseases, most notably influenza, meningitis, and measles [Ber21]. Caused by a coronavirus known as SARS-CoV-2, COVID-19 has become a worldwide pandemic that has, as of April of 2022, over 500 million confirmed cases and over six million deaths have been reported globally by WHO. Although a large amount of research has been done both on Dengue as well as on COVID-19, not much work has been done on their correlation, and thus this shall be the focus of the present paper. In particular, building on [BG21], we study such correlation worldwide using machine learning techniques, and explore different directions in which the results we deduce could be used by policy makers in the future, especially since the syndemic and possible simultaneous transmission presents a significant challenge to public health efforts in those areas [RSI⁺20].

Prominent in Latin American and Asian countries, Dengue is a viral disease that is transmitted by mosquitoes, especially those of species *Aedes aegypti* (Aa) [Org20]. Dengue is a highly seasonal, multi-annual disease, most prevalent before and after rainy seasons. Individuals who recover from Dengue have long-term immunity against that specific serotype (homotypic), and they also have short-term immunity against Dengue of a different serotype (heterotypic) [MW11]. Moreover, Dengue is widely considered to be the most important mosquito-borne viral disease and is very wide spread, covering mostly tropical and sub-tropical areas, between the January isotherm and the July isotherm of 10 degrees Celsius. Temperature, rainfall, and population density were all factors shown to be associated with the number of Dengue infections, which explains the regions where it is most prevalent [MQWS13].

Recently, infections of Dengue and COVID-19 have begun to be considered together, particularly in South America. Despite the year 2020 being an epidemiological complex year with the pandemic of COVID-19, the fatality rate from Dengue was recorded as 0.04%, the lowest in the past decade [Org20]. Interestingly, however, there seems to be a persistence of higher than ex-

pected number of Dengue cases in endemic areas, occurring simultaneously with intense COVID transmission. Although it has been brought up in September of 2021 that there may be cross-immunity between the two diseases [SCL⁺20], a population-based cohort study in December of 2021 found that individuals with prior dengue actually had an increased risk of clinically apparent COVID-19 [NRJ⁺21]. Thus, there is likely not any cross-immunity between the two diseases.

We shall organize our paper in the following way: after introducing some background in Section II, we define different external variables that we then use in a neural network model for Brazil in Section IV. In particular, we consider holidays in Subsection IV A and climate factors such as temperature and humidity in Subsection IV B. By adding in these factors, we

- are able to **create a model that predicts and correlates COVID-19 to**
 - holidays;
 - climate, and
 - Dengue.

After introducing and describing our novel model, we show its utility by applying it to other nations or regions in Section V. In particular, we use our model to study the data from Peru and Colombia and

- show the **model's predictive qualities** by using COVID-19 data to predict Dengue in countries that lack sufficient Dengue data.

Other factors such as Latent Heat Flux and peaks correlations are also considered in Section VIII. Finally, since our Machine Learning model focused solely on external variables, we take a more time-series based approach and

- introduce a **Long short-term memory model (LSTM)** in Section VII, obtaining a more comprehensive look at predicting future values for both diseases than does the standard neural network.

The results and observations drawn from our work are summarized in Section VIII C, where future directions of research are also outlined.

II. BACKGROUND

Machine Learning has been incredibly useful in countless topics, and COVID-19 is no exception. Ever since the beginning of the pandemic, researchers have been using machine learning to predict future outbreaks or possible correlations with other factors. In the present paper we are specifically looking at the correlation of COVID-19 with Dengue. Hence, we shall dedicate this section to introducing the background needed in Machine Learning, neural networks and LSTM models.

A. Machine Learning and COVID-19

Because Machine Learning is such a powerful tool in making predictions and finding correlations, researchers have been using it in studies about COVID-19 since the beginning of the pandemic. As early as April of 2020, in fact, researchers were finding that specific models, such as MLP (Multi-layered perceptron) and ANFIS (adaptive network-based fuzzy inference system) – both artificial neural networks – had promising results for estimating the severity of the pandemic. In the beginning of 2020, researchers also tested several models to estimate time-series data, finding that whilst the logistic model outperformed the others, these fitted models were hard to generalize after a 30-day period [AMG+20]. More recently, Machine Learning begun to be used to classify different types of COVID-19 since it can also test different aspects, such as the severity of someone’s COVID-19 symptoms. In particular, researchers have suggested a hybrid machine learning/deep learning model that predicts COVID-19 severity from CT images [CFM+22].

Our work on the correlation between Dengue and COVID-19 will be done firstly by using a neural network to study data that was collected of COVID-19 and Dengue. By incorporating parameters that are possibly related to these two infectious diseases such as holiday seasons, temperature, or rainfall, we are able to draw strong correlations that then serve to build a predictive model. These models then shall generate loss curves and prediction graphs to find out what factors are the most prominent in these disease cases. A standard neural network has input layers, output layers, and one or more hidden layers as shown in Figure 1.




FIG. 1: An example of a neural network with i hidden layers, 1 input layer and 12 output layers.

The learning structure used here has one input layer, four output layers using the relu activation function, and an output layer using the linear activation function. The predicted infection number is given by the output node with the greatest activation. The neural network was trained using a training set of size 10 epochs and testing using a cross- validations set of size approximately 150 epochs. To understand the model we consider its loss function using the Mean Absolute Error function in Section IV, which was calculated by averaging the absolute distances between the predicted and actual values. Data for Dengue fever has been collected from the [Pan-American Health Organization Dataset on Dengue](#), and data for COVID-19 has been collected from the World Health Organization [dashboard on COVID-19](#).

B. LSTM Models

The correlation between Dengue and COVID-19 will also be studied through a Recurrent Neural Network (RNN), in an effort to predict future values of the number of infections based on past observed data. Specifically, we shall consider a LSTM model (Long short-term memory), which is particularly useful especially in cases where there may be time lags, and which is often used in analyzing stock prices and the like. In the setting of our paper, we use the LSTM model to generate a model for each disease based solely on its past observed values and then we incorporate the time series values for the other disease as well as other external factors.

The LSTM model is more complicated than a standard neural network in that it can process sequences of data and not solely datapoints. Because these recurrent types of neural networks have “loops” (hence, recurrent) around them, the information is able to persist, something that standard neural networks cannot necessarily do. Essentially, a LSTM model contains a cell, input gate, and output gate as shown in Figure 2. But it also consists of a forget gate, something that traditional neural networks do not have. The input gate inserts new information into the cell, and the output gate passes along the new, updated information. The forget gate, on the other hand, forgets useless information, which is especially important because LSTM is used for long-term processing. In our LSTM model, we have an input layer, a single hidden layer, and an output layer.




FIG. 2: An example of an LSTM model.




FIG. 3: Dengue and COVID-19 cases plotted for Brazil (left), Peru (middle), Colombia (right).

III. CORRELATIONS VIA DATASETS

In order to understand the data sets from the [Pan-American Health Organization Dataset on Dengue](#) and the World Health Organization [dashboard on COVID-19](#) which we will consider in this paper, we shall build some correlation plots to gauge the data at hand.

We shall begin our work with the largest country in South America, and the most prominent with respect to COVID-19 and Dengue, which is Brazil. Since the number of COVID-19 cases is relatively large, one may take the base 10 logarithms of all the data to understand the sets better: a graph of the base 10 logarithm for new COVID-19 cases per week vs the base 10 logarithm for new Dengue cases per week can be seen in [Figure 3](#) (Left) above.

Along this paper we shall only use data from epidemiological weeks 30 to 100, which corresponds to the count beginning in January 2020. This is done since outside of that range the datasets are too irregular, and thus including those values would not be representative of the actual trend. Through [Figure 3](#) one can deduce some initial properties of the correlation between Dengue and COVID-19 in South America. In the correlation graph for Brazil in [Figure 3](#) (Left), one can see that the two diseases have a roughly positive correlation. A similar study of the datasets for Peru and Colombia are presented in [Figure 3](#) (Middle) and (Right) respectively.

It is interesting to note that the graph for Peru is very random, whereas the graph for Colombia shows slightly negative correlation, suggesting that the notion that the correlation between the diseases could differ by country. Returning the attention to Brazil, we shall consider a graph from the years 2020-2022 for Dengue and COVID-19 infections in Brazil, where the horizontal axis is the epidemiological week, counted from the beginning of 2020, and the vertical axis represents the number of cases in millions as shown in [Figure 4](#). One can then compare the number of COVID-19 cases (red) and the number of Dengue cases (blue), as shown in [Figure 4](#) (Left), noting that between week 60 and week 80, the peak of COVID-19 generally coincides with the peak of Dengue, a period that corresponds to the year 2021. After week 100 the number of COVID-19 cases spikes up, likely due to the recent increases of Omicron. In [Figure 4](#) (Left) the data has not been normalized, and thus one can see the number of COVID-19 cases being much greater than the number of Dengue cases.

Since the number of COVID-19 cases is of a greater magnitude than the number of Dengue cases, it becomes difficult to see a definite trend. It is thus useful to consider the base 10 log of the number of COVID-19 and Dengue cases as shown in [Figure 4](#) (Right) to note that the peaks of Dengue generally coincide with the peaks of COVID-19.




FIG. 4: Plot of data from the [Pan-American Health Organization Dataset on Dengue](#) and the World Health Organization [dashboard on COVID-19](#) (left) and its log plot (right).

Through Figure 4 (Right) in the previous page, one can see that from approximately from week 30 to week 100 the increase or decrease of cases for COVID-19 and Dengue are correlated. In particular, one can see that in the beginning of year 2020, there was a much greater number of Dengue infections than COVID-19 cases, since the pandemic had not emerged yet. After week 100, or roughly the beginning of year 2022, the Omicron variant resulted in the number of COVID-19 cases increasing dramatically. Interestingly, both the number of COVID-19 and Dengue experience a drop around weeks 50 and 100 (during 2021). Whilst this may be due to the fact that the period coincides with the wintertime and the end of the year, this may be counterintuitive because one would think that infectious diseases would spike during holiday times.

A similar study to the one done above can be performed for the dataset of Perú, leading to Figure 5 which shows the data against the epidemiological weeks for Perú, where the number of cases for each disease seem to follow the same general trend.




FIG. 5: Weekly correlations between COVID-19 and Dengue for Perú.

In order to understand other parameters which might be influencing the cases of both COVID-19 and Dengue, we shall consider the particular influence of humidity and temperature. Following the style from the previous analysis, we can draw the explicit correlations between the various parameters and the number of cases of either COVID-19 or Dengue. In particular Figure 6 below shows the correlation between COVID-19/Dengue and Temperature/Humidity, where the black dots represent the points for COVID-19, and the red dots represent the points for Dengue. By analyzing the graphs one can deduce that temperature would be a better predictor than humidity for the number of cases.

IV. A CORRELATION MODEL

In order to study the correlation between COVID-19 and Dengue in further detail, we shall build a neural network, *the Correlation Model*, for our model (see Section II for background). Our model has an input layer consisting of the various parameters we add, four hidden layers within the network, and an output layer.

As with the previous section, we shall begin our study with the dataset from Brazil. The Correlation Model will generate a prediction for the number of COVID-19 cases, once additional variables are taken into consideration. We have built the first version of the model to include:

- the number of Dengue infections,
- the boolean variable of whether the week contains a “holiday”, and
- quantitative climate factors (temperature, humidity, and rainfall).

In what follows we shall describe the role each variable plays within the correlation study, and how we are able to incorporate such variables into our Correlation Model.




FIG. 6: Humidity Correlations (Left) and Temperature Correlations (Right) for Perú’s dataset.

A. Impact of Holidays

The impact of public holidays on epidemic spreads has long been studied, from generic epidemic standpoints [Eam14] to directly related to the latest COVID-19 epidemic [CCY+20]. It is thus natural to consider how holidays influence the correlation between COVID-19 and Dengue, and to study this question we shall consider the Brazilian dataset and a parameter which tracks whether or not a week contains an important Brazilian holiday. The list of holidays used can be found in Appendix A, and our parameter has a value of 1 during the weeks that contain the holidays in 2020, 2021, and 2022, and 0 otherwise. We firstly study the loss curve for this model, plotted in Figure 7, where the blue line represents the training loss and the red line represents the validation loss. As in usual neural networks, the data has been split randomly into a training set and a cross-validation set, with our epoch size of 150 and the loss function based on the Mean Absolute Error.





FIG. 7: A graph of the loss curve when the holiday data is first added.



Since one of the most useful things that the Keras model can do is predict new values, we used `model.predict()` to do so within our setting. Specifically, our Correlation Model then predicts the number of cases for COVID-19 leading to the visualization in Figure 8 (Left), where the blue line is the predicted value for any given week using the prediction algorithm, and the red line is the actual value in the dataset.

Notice that the vertical axis runs from 4.8 to 5.6. Recall that we have taken the base-10 logarithm of the weekly cases for COVID-19 and Dengue as a means of normalization and for the number of cases to be of the same approximate magnitude. In Figure 8 (Left), the prediction has the same general trend as the actual data and can therefore indicate where the approximate peaks and valleys will be. Yet, the prediction has a smaller amplitude than the actual data, and thus the prediction would seem to diminish the variance of the initial data. To account for this, we can define a new variable C to be the *Contraction ratio*: the ratio of the average distance from the mean for the actual data to the average distance from the mean for the predictions. We shall see the importance of this variable in the upcoming sections as well as in the conclusion.

In order to test our model, one repeats the process for the prediction done before and generates a new test graph shown in Figure 8 (Right), which presents the study on the cross-validation set, not the training set. In this case, the blue line represents the prediction model on the validation set, and the red line is the actual data in the validation set. Since not as many weeks were included in the test set in Figure 8 (Right), the relationship between the two curves is less apparent than that of Figure 8 (Left). However, one can still see that the prediction and the actual data for the validation set have the same approximate trend, and that like in the training set, the prediction values do not vary as much as the actual data values.




FIG. 8: A graph of the actual data and the predicted data for holidays on the training set (Left) and the test set (Right).

B. Impact of Humidity and Temperature

Research has shown that climate [CPK+21] and in particular increasing temperatures influence COVID-19 transmission [Not21], as well as for other viruses [LMSP07]. Therefore, in what follows we shall add climate factors such as temperature or humidity to our model. A characteristic of Dengue is that it is most prevalent around rainy seasons, and thus one should expect higher value of humidity would correspond to a greater number of Dengue cases and we shall look into this correlation below.

The dataset obtained on Brazilian climate contains daily maximum and minimum temperature and humidity for major Brazilian cities, so in order to fit it to our model, we can take the average of the temperature and humidity over each epidemiological week. In addition to the factors of temperature and humidity, we shall weight the data based on population, so that the greater the population, the more heavily it is weighted. To perform our study we consider the two biggest cities in Northern and Southern Brazil, which are Salvador and Sao Paulo, respectively. The weighted data according to the populations of Northern and Southern Brazil, is given by approximately 43% and 57%, respectively, leading to the loss curve model shown in Figure 9.





FIG. 9: The loss curve for only climate factors.



Unlike the study done in Figure 7, one can observe that the loss is generally greater, and thus the model generates less precise results, leading to the conclusion that climate factors are not as correlated with COVID-19 cases as holiday factors are. Moreover, a graph of the predicted data based on our neural network model on the training set can be obtained, as shown in Figure 11 (Left) below. In particular, one can see that the model predicts the actual numbers for COVID-19 rather well, as the two graphs have approximately the same amplitude and the same mean. Finally, one can repeat this for the test set, and find that, similar to before, the model in Figure 11 (Right) predicts the general trend of ups and downs fairly well for the test set.

Having studied our Correlation Model with climate parameters and holiday parameters separately, we shall now consider both sets of parameters together, leading to the comparison chart featured in Figure 10 which describes the loss curve for both climate and holidays:




FIG. 10: The loss curve for both climate and holidays. Data on the number of reported cases is from Pan-American Health Organization Dataset on Dengue and the World Health Organization dashboard on COVID-19. Data on Brazilian climate is from <https://www.visualcrossing.com/weather-history/brazil>.




FIG. 11: Actual data and predicted data for only climate on the training set (Left) and the test set (Right).




FIG. 12: Actual data and the predicted data for Brazil when both holiday and climate factors are considered on the training set (Left) and the test set (Right).

Once the parameters for temperature and humidity are added, the loss curve of [Figure 10](#) decreases more gradually. In contrast, the loss curve from [Figure 7](#) decreased very rapidly. The actual training data and the values predicted by the Keras model are then plotted in [Figure 12](#). In particular, in [Figure 12](#) (Left) the prediction has the same general peaks and valleys as the actual data. However, whilst the prediction seems to have roughly the same amplitude as the data, the prediction is shifted down approximately 0.2 on the logarithmic scale. In [Figure 8](#) (Left), the prediction had roughly the same mean value and a smaller amplitude. The model predictions with the actual test data are plotted in [Figure 12](#) (Right): compared with [Figure 8](#) (right), the predictions in better seem to correlate with the trend of the actual data. This graph resembles [Figure 12](#) (Left) in that the blue line has the same approximate trend as the red line, but the predictions has a smaller numerical values.

V. THE EFFICACY OF THE CORRELATION MODEL

We shall dedicate this section to the study of how well our Correlation Model can serve to understand data from other South American countries. For this, the model shall be re-trained for datasets from Peru and Colombia. Then, we shall perform a reverse study, flipping the parameters in order to predict the number of Dengue cases on countries that do not have Dengue data readily available such as Cambodia and Kenya, countries from Southeast Asia and Africa that have significant Dengue.

A. South American Nations

Now that we have the model tested on Brazil, we can use it on other nations as well to see if the model predictions match up with the actual data. The procedure shall be repeated for Peru and Colombia, which are both countries where both Dengue and COVID-19 are very prevalent and frequent.

1. The Correlation Model on Perú

According to the [Pan-American Health Organization Dataset on Dengue](#), Peru had 49,274 cases of Dengue Fever in 2021 and has had 20,491 cases of Dengue during January-June 2022, setting Peru as the second country with the highest Dengue cases in South America, just after Brazil. Therefore, it would be meaningful to see what correlates with the number of Dengue or COVID-19 cases in this country. In order to study the influence of holidays within the dataset from Perú, we replicated our Brazilian study but with the new set of national holidays, a list of which has been included in [Appendix A](#).

Because both Peru and Brazil are South American countries, they celebrate very similar national holidays allowing us to do further comparisons of the datasets. Furthermore, for our climate variables we consider the data from [Visual Crossing](#) to obtain data on humidity, temperature, and precipitation. Since Lima is the capital and largest city, with around one-third of the nations' population, we have chosen it for our climate data, allowing us to derive the loss curve and prediction curve for Peru shown in [Figure 13](#) and [Figure 16](#) below.




FIG. 13: Loss curve of the neural network model for Perú




FIG. 14: A graph of the actual data and the predicted data for Perú, for when both holiday and climate factors are considered on the training set (Left) and the test set (Right).

2. The Correlation Model on Colombia

We shall finally replicate our method for Colombia's dataset. In this case, however, because of incomplete data for Dengue from approximately week 30 to week 60, we shall only focus on the period between week 60 to week 100, and consider the national holidays, a list of which has been included in Appendix A.




FIG. 15: Loss curve for Colombia.

Following a similar approach as in the previous sec-




FIG. 16: A graph of the actual data and the predicted data for Colombia, for when both holiday and climate factors are considered on the training set (Left) and the test set (Right).

tions, we derive the loss curve for Colombia's Correlation Model as shown in Figure 15. In order to add the variables corresponding to climate factors, we consider the data from Visual Crossing to obtain data on humidity and temperature across the nation. Since Bogotá is the both Colombia's capital and largest city, we chose it to be a representative for our climate data in order to do a parallel study to the one done for Lima in the previous section. Then, by using our Correlation Model both on the training set and on the test set, we are able to evaluate its accuracy in predicting infection cases across Colombia as shown in Figure 16.

It should be noted that for Brazil, Peru and Colombia, the abrupt drop in cases between weeks 52 y 104 could be due to the low reporting rate associated with the new year's celebrations, which has been seen when studying other diseases [SRP⁺16]. Within our setting, we attempted to mitigate such effect by taking weekly averages when performing our studies. Finally, it is also important to note that Dengue data has sometimes been thought to have been underreported, and in particular to have been undermined by the beginning of the COVID-19 pandemic [LBP⁺21], and this is why it is sometimes useful to leave the first weeks of the data unused.

VI. USING THE MODEL TO PREDICT INFECTIONS IN AFRICA OR SOUTHEAST ASIA


Having developed our Correlation Model and trained it with the datasets from several South American countries, we can use the model to predict the number of Dengue cases for countries in Africa or Southeast Asia, especially since those regions also have a high number of Dengue cases. In particular, whilst not much data can be found on recent Dengue cases for those countries, it is known that the regions of Southeastern Asia have a significant amount of cases of Dengue fever, which creates a heavy economic burden on those countries [SUH13]. Thus, by *reversing* the Correlation Model to use COVID-19 as a parameter to predict Dengue cases over time, one can obtain very useful information for future policy making.

1. Predicting Dengue cases in Cambodia

We shall first consider Dengue in Cambodia, a South-eastern Asia country. In a recent update as of April of 2022, there have been a total of 457 cases, including one death, which remains much lower than the normal range of cases from 2015 to 2021 [Org22]. In our model, we shall use South American countries for the training set, and then Cambodia for the test set.

It should be noted that many of the holidays celebrated in Cambodia are quite different from those celebrated in South American countries, and thus we have included the new corresponding list in Appendix A. In addition, we shall also include a climate variable built through the data for Cambodia found in Visual Crossing. Following the same style as before, we shall take Phnom Penh, the capital and largest city in Cambodia as our city of study. Finally, it should be noted that instead of using the log of the number of cases, we shall perform our study by considering the parameter

$$\log \left(\frac{\text{Number of COVID-19 or Dengue cases}}{\text{Country Population in millions}} \right)$$



This kind normalization, dividing by the nation's population, gives a better idea of the prevalence of that disease. By taking Peru as the country for the training set, one obtains the following prediction of the number of Dengue cases in Cambodia with respect to time shown in Figure 18 (Left). Moreover, by adding Brazil into the training set, one can confirm similar trends with the previous figure, and around the same times of year, as shown in Figure 18 (Right).

It becomes interesting to compare the above analysis with the average trend of Dengue fever in Cambodia from 2015-2020, from WHO's April 2022 Update of Dengue in the Western Pacific [Org22]. In particular, one should note the similarities in trend, even though the peaks seen in Figure Figure 18 (Right) and Figure 17, which correspond to different times of the year.




Figure 1: Dengue cases reported weekly in 2022 vs Mean and Mean+2SD during 2015-2020, *excluding 2019 in Cambodia
Source: National Dengue Surveillance System (NDSP/CNM/MOH)

FIG. 17: World Health Organization's Graph of Dengue in Cambodia from 2015-2020

In what follows we shall perform a similar study using Kenya's data set, and include an analysis of such study in the last section of the paper.




FIG. 18: Predicting Cambodia's Dengue cases using Peru as the training set (Left), and using both Peru and Brazil's data as training set (Right).




FIG. 19: A scaled look at COVID-19 numbers over the past two years.

2. Predicting Dengue cases in Kenya

In what follows we shall continue showing the utility of our model by considering the data sets for Kenya, one of the countries in Eastern Africa with a significant amount of Dengue cases. By applying our Correlation Model trained with South American countries on Kenya, one can predict infection peaks at roughly epidemiological weeks 60 and 110 and valleys at epidemiological weeks 50 and 100 as shown in Figure 20.




FIG. 20: Predicting Kenya's Dengue cases using Peru and Brazil as the training set.

Having seen how many external variables, such as celebration of holidays or temperature or humidity, affect the prevalence of COVID-19 or Dengue, in what follows, we shall expand on our Correlation Model and build a Recurrent Neural Network and perform a time series analysis (see Section II B for background on LSTM models).

In what follows, it is useful to have in mind the number of COVID-19 infections from the beginning of 2020 up until the beginning of 2022 as given in Figure 19, with data used from 0 – 1.

VII. RECURRENT NEURAL NETWORK AND TIME SERIES ANALYSIS

We shall dedicate this section to expand our Correlation Model to build upon a Recurrent Neural Network. To train this new model, we shall use Perú's dataset, since it has the most complete data for Dengue and thus provides an ideal starting point. Moreover, it should be noted that the number of epochs that one chooses for the model has a large impact on the model: the smaller the number of epochs, the more the model is likely to under-fit; Equivalently, the larger the number of epochs, the more the model tends to over-fit. In what follows we shall will assign the first 80% of the data, roughly until October 2021, for the training set and the remaining 20% for the test set, and use MinMaxScaler, so that the calculations are done with all the data from 0 to 1.

Through the data of Figure 19, we can inverse of our original rescaled model first, and then consider the base 10 logarithm for all of the values, to obtain a prediction of COVID-19 infections using a time series analysis for Peru as shown in Figure 21 below.




FIG. 21: Predicting COVID-19 infections using time series.

It should be noted that the horizontal scale is measured in days, and thus from our model one expects the number of COVID-19 cases to decrease gradually after the spike in January of 2022, which is reasonable considering that Omicron caused a large increase in the number of cases.




FIG. 22: Predictions of infections using a time series analysis and LSTM model for Dengue (Left), COVID-19 (middle), and for predicting Dengue infections using an LSTM model that incorporates both diseases (Right).

A similar study can then be done for the prediction of Dengue and COVID using LSTM, which we shall illustrate in Figure 22 above. In the case of Dengue, one can see in 22 (Left) that with enough epochs the prediction fits the true data quite well.

The case of Dengue infections has been considered in Figure 22 (Middle), where the blue spike downwards is actually probably due to a missing value of sorts and may not be an actual zero. Considering this, the model gets most of the general trends pretty accurately. After the beginning of 2022, this model predicts that the number of Dengue infections will initially rise and then fall, which we can compare with Figure 22 (Left), in which we have incorporated both epidemics. Essentially, there are two models here; one using past values for both diseases to predict COVID-19, and the other using past observed values for both to predict Dengue. These are updated simultaneously while the program is running. Again, we have used MinMaxScaler to scale the numbers from 0 to 1, then inverse scaled them back and took the logarithm of all value to make the details more clear.

VIII. CONCLUSION AND APPLICATIONS

In this paper we have built a neural network Correlation Model as well as a recurrent Correlation model for a neural network to take advantage of the correlation between Dengue and COVID-19 to deduce predictions on future infections of both diseases. Such correlations drawn should also present interesting lines of research for other viruses which present correlations. Moreover, there are many directions in which our models could further be expended. Since it is outside the scope of this paper to perform those extensions here, we shall instead give a brief summary of the directions we believe would be very fruitful to explore in upcoming work.

In particular, we shall consider Latent Heat Flux and whether it could be a better correlator than other climate factors, such as humidity, temperature, or precipitation. Finally, we shall also propose a notion of peak indices which could be the ideal setting when finding correlations between viral epidemics. Finally, we shall conclude this note by summarizing our methods and highlighting our findings.

A. Latent Heat Flux

From our model building analysis, it would seem that the time series of transmissions of COVID-19 and Dengue could be better correlated to the latent heat flux (LHF), which is the amount of energy moving between the air and the land due to evaporation or condensation. In particular, the research of heat and mass transfers has been identified as a possible area that could lead to progress in reducing COVID-19 [TCC+21]. A sufficient dataset on latent heat flux could not be found because the datasets that are available online stopped at the early-2010's and were not daily or weekly, but there are many environmental factors correlated with LHF or just COVID-19 and Dengue which could be taken into consideration. Instead. Some of the ones we believe could be best suited for finding correlations are the following:

- Sea Surface Temperature [WKP07] – unfortunately, no data on this either;
- Temperature change;
- Humidity – the higher the humidity, the higher the latent heat flux tends to be;
- Wind speed – the greater the wind speed, the lower the latent heat flux usually is;
- Atmospheric pollution impacts [TCC+21] – for this, use the Visibility data from the Visual Crossing dataset.

From the above, one can add the new parameters of

- maximum temperature,
- minimum temperature,
- wind speed, and
- visibility

for the study of Perú's dataset (since that was the country that had the most complete data) leading to the graph of the loss curve and the prediction models shown in Figure 23 shown in the following page.




FIG. 23: (Left) Loss curve (Center) Training predictions (Right) Test predictions

B. Peak Index Predictions

It should be very useful to understand correlations between viral epidemics through some sort of *peak index*, which can be defined in a general sense as the week index of where the largest number of COVID-19 or Dengue cases occur. In particular, the following two perspectives could be incorporated to our Correlation Model to expand on our work:

- **A relative index.** We define an epidemiological week to be a peak if it has a greater number of cases than both the week before and after it. We define a function $\rho(t)$ to be the function that represents whether EW t is a peak. Thus,

$$\begin{aligned} \rho(t) &= 1 \text{ if } Nc[t] \geq \alpha Nc[t-1] \text{ and } Nc[t] \geq \alpha Nc[t+1] \\ &= 0 \text{ otherwise} \end{aligned}$$

- **An absolute index.** We define a function $\rho(t)$ to be the function that represents whether EW t is a peak. Formally, this is given by

$$\begin{aligned} \rho(t) &= 1 \text{ if } Nc \geq \alpha \cdot P \\ &= 0 \text{ otherwise,} \end{aligned}$$

where Nc represents the number of new infections for a particular disease and P represents the total population for a particular country, and α is a coefficient that differs among various diseases. For example, for COVID-19, this could be if the new cases is at least $\frac{1}{10,000}$ of the country's population. For Dengue, this could be if the number of new cases is at least $\frac{1}{1,000,000}$ of the country's population (since there are currently far less cases for Dengue than for COVID-19)

C. Final remarks

By considering datasets from different South American countries on COVID-19 and Dengue cases, we have been able to build a Correlation Model which allows us to study COVID-19 and Dengue cases in areas of the world where data is not fully available. In particular our study, we have been able to observe the following.

- When considering the importance of holidays as a parameter, the prediction curve has approximately the same mean as the actual data and yet has a smaller amplitude, and it seems as if the prediction essentially diminished the variance of the initial data as seen in Figure 8 (Left).
- When parameters for temperature and humidity are added, the loss curve seems to decrease more gradually as shown in Figure 10. In contrast, the loss curve from Figure 7 decreased very rapidly.
- By only adding in climate factors into the neural network results in a gradually descending loss curve, but with very big amplitude as shown in Figure 7. Combining this with holiday factors seems to take care of this issue.
- When considering combined holiday and climate factors, the prediction seems to have roughly the same amplitude as the data, but the prediction is shifted down approximately 0.2 on the logarithmic scale as shown in Figure 8 (Left). However, interestingly the prediction had roughly the same mean value and a smaller amplitude.
- The sequence length is also a highly important factor that may change the prediction: indeed, when changing the 14-day sequence length to 35-days, the prediction for COVID-19 is to decrease (like before) and then rise slowly.

Finally, it would be interesting to see the effects of the COVID-19 lockdown on Dengue [CLL⁺22]. Many say that because the lockdown occurred so close to the peak of the mosquito season, the transmission of Dengue increased [LHP⁺21], as the lockdown affected *Aedes* mosquito surveillance and vector control procedures [DRRGCA⁺20]. In this setting, then mosquito larvae populations would have increased, and thus the number of people infected with Dengue would increase because they lived in close proximity with mosquitos. It should be noted that the number of Dengue cases could have been severely underestimated, simply due to the fact that health resources were being focused on COVID-19 instead or that people who were infected with Dengue were unwilling to get a formal diagnosis due to the lockdown [BBC⁺22].

Acknowledgments. Grace Wang and Laura P. Schaposnik would like to express their deep gratitude to the MIT PRIMES Program for this wonderful opportunity to conduct research, and to Fidel A. Schaposnik for introducing them to the work of Paula Bergero which led to this collaboration.

Contributions of authors. All authors contributed equally to the planning of the paper. Much of the work was done by Grace Wang under the supervision of Laura P. Schaposnik through PRIMES-MIT program 2022.

Funding. PB is member of the Scientific Career of Consejo Nacional de Investigaciones Científicas y Técnicas of Argentina (CONICET). The work of LPS is partially supported by a Simons Fellowship, NSF CAREER Award DMS 1749013 and NSF FRG Award 2152107.

Affiliations.

- (a) Universidad Nacional de La Plata & CCT, Argentina.
- (b) University of Illinois, Chicago, USA.
- (c) PRIMES-MIT, USA.

-
- [AMG⁺20] S. F. Ardabili, A. Mosavi, P. Ghamisi, F. Ferdinand, A. R. Varkonyi-Koczy, U. Reuter, T. Rabczuk, and P. M. Atkinson, “Covid-19 outbreak prediction with machine learning,” *medRxiv* (2020) .
- [BBC⁺22] F. Borre, J. I. Borri, Y. Z. Cohen, M. Gasparoto, and T. B. Gurung, “Impact of the covid-19 pandemic on infectious diseases in brazil: A case study on dengue infections,” *Epidemiologia* **3** no. 1, (2022) 97–115.
- [Ber21] G. Berberian, “Dengue at the beginning of the COVID-19 pandemic in Argentina,” *Arch Argent Pediatr* (04, 2021) .
- [BG21] P. Bergero and N. Guisoni, “Mathematical modelling of dengue-COVID-19 coinfection: a first approximation,” *Revista Argentina De Dalud Publica* **13** (05, 2021) .
- [CCY⁺20] S. Chen, Q. Chen, W. Yang, L. Xue, Y. Liu, J. Yang, C. Wang, and T. Bärnighausen, “Buying time for an effective epidemic response: the impact of a public holiday for outbreak control on covid-19 epidemic spread,” *Engineering* **6** no. 10, (2020) 1108–1114.
- [CFM⁺22] M. Chierigato, F. Frangiamore, M. Morassi, C. Baresi, S. Nici, C. Bassetti, C. Bna, and M. Galelli, “A hybrid machine learning/deep learning COVID-19 severity predictive model from CT images and clinical data,” *Scientific Reports* (03, 2022) .
- [CLL⁺22] Chen, Li, Lourenco, et al., “Measuring the effects of COVID-19-related disruption on dengue transmission in southeast Asia and Latin America: a statistical modelling study,” *The Lancet* (3, 2022) .
- [CPK⁺21] S. Chen, K. Prettnner, M. Kuhn, P. Geldsetzer, C. Wang, T. Bärnighausen, and D. E. Bloom, “Climate and the spread of covid-19,” *Scientific Reports* **11** no. 1, (2021) 1–6.
- [DRRGCA⁺20] A. Daniel Reegan, M. Rajiv Gandhi, A. Cruz Asharaja, C. Devi, and S. Perumal Shanthakumar, “Covid-19 lockdown: impact assessment on aedes larval indices, breeding habitats, effects on vector control programme and prevention of dengue outbreaks,” *Heliyon* **6** no. 10, (10, 2020) e05181.
- [Eam14] K. Eames, “The influence of school holiday timing on epidemic impact,” *Epidemiology & Infection* **142** no. 9, (2014) 1963–1971.
- [LBP⁺21] X. Lu, H. Bambrick, P. Pongsumpun, P. W. Dhe-wantara, D. T. T. Toan, and W. Hu, “Dengue outbreaks in the covid-19 era: Alarm raised for asia,” *PLoS neglected tropical diseases* **15** no. 10, (2021) e0009778.
- [LHP⁺21] X. Lu et al. “Dengue Outbreaks in the COVID-19 era: Alarm raised for Asia,” *PLoS Neglected Tropical Diseases* (10, 2021) .
- [LMSPO7] A. C. Lowen, S. Mubareka, J. Steel, and P. Palese, “Influenza virus transmission is dependent on relative humidity and temperature,” *PLoS pathogens* **3** no. 10, (2007) e151.
- [MQWS13] N. E. A. Murray, M. B. Quam, and A. Wilder-Smith, “Epidemiology of dengue: past, present and future prospects,” *PubMed Central* (08, 2013) .
- [MW11] B. R. Murphy and S. S. Whitehead, “Immune response to dengue virus and prospects for a vaccine,” *Annual Review of Immunology* (2011) .
- [Not21] A. Notari, “Temperature dependence of covid-19 transmission,” *Science of The Total Environment* **763** (2021) 144390.
- [NRJ⁺21] V. C. Nicolete, P. T. Rodrigues, I. C. Johansen, R. M. Corder, J. Tonini, M. A. Cardoso, J. G. de Jesus, I. M. Claro, N. R. Faria, E. C. Sabino, M. C. Castro, and M. U. Ferreira, “Interacting Epidemics in Amazonian Brazil: Prior Dengue Infection Associated With Increased Coronavirus Disease 2019 (COVID-19) Risk in a Population-Based Cohort Study,” *Clin Infect Dis.* (12, 2021) .
- [Org20] P. A. H. Organization, “Epidemiological Update: Dengue in the context of COVID-19,” (12, 2020) .
- [Org22] W. H. Organization, “Update on the Dengue situation in the Western Pacific Region,” (04, 2022) .
- [RSI⁺20] T. Rahman, A. Sobur, S. Islam, A. Toniolo, and K. N. H. Nazir, “Is the covid-19 pandemic masking dengue epidemic in bangladesh?,” *Journal of advanced veterinary and animal research* **7** no. 2, (2020) 218–219.
- [SCL⁺20] Silvestre, Costa, Lopes, Barbosa, Botelho, Albuquerque, Souza, Coelho, J. de Oliveira, Barantini, Neves, Nadruz, Maguire, and Fernandes-Silva, “Previous Dengue Infection and Mortality in Coronavirus Disease 2019 (COVID-19),” *Clinical Infectious Diseases* **73** no. 5, (12, 2020) e1219–e1221.
- [SRP⁺16] M. M. Silva, M. S. Rodrigues, I. A. Paploski, M. Kikuti, A. M. Kasper, J. S. Cruz, T. L. Queiroz, A. S. Tavares, P. M. Santana, J. M. Araújo, et al., “Accuracy of dengue reporting by national surveillance system, brazil,” *Emerging infectious diseases* **22** no. 2, (2016) 336.
- [SUH13] D. S. Shepard, E. A. Undurraga, and Y. A. Halasa, “Economic and Disease Burden of Dengue in Southeast Asia,” *PLoS Neglected Tropical Diseases* (02, 2013) .
- [TCC⁺21] M. Trancossi, C. Carli, G. Cannistraro, J. Pascoa, and S. Sharma, “Could thermodynamics and heat and mass transfer research produce a fundamental step advance toward and significant reduction of SARS-COV-2 spread?,” *International Journal of Heat and Mass Transfer* (05, 2021) .
- [WKP07] R. Wu, B. Kirtman, and K. Pegion, “Surface Latent Heat Flux and Relationships with SST in CFS,” *Geophysical Research Letters* (09, 2007) .

Appendix A: Holidays Used

Brazil Holidays:

- New Year's Day (January 1)
- Shrove Tuesday (March 1)
- Good Friday and Easter (around April 12, 2020 and April 4, 2020)
- Tiradentes Day (April 21)
- Labour Day (May 1)
- Feast of Corpus Christi (June 16)
- Independence Day (September 7)
- Our Lady of Aparecida's day (October 12)
- All Souls Day (November 2)
- Republic Day (November 15)
- Christmas Day (December 25)
- Brazilian Carnival – February 21 - 26 (in 2020) and February 12 - 17 (in 2021)

Peru Holidays:

- New Year's Day (January 1)
- Good Friday and Easter Sunday (April 2 and April 4 in 2021)
- Labour Day (May 1)
- Saint Peter and Saint Paul (June 29)
- Independence Day (July 28-29)
- Santa Rosa de Lima (August 30)
- Battle of Angamos (October 8)
- All Saints' Day (November 1)
- Immaculate Conception Day (December 8)
- Christmas Day (December 25)

Colombia Holidays:

- New Year's Day (January 1)
- Epiphany (January 10)
- St. Joseph's Day (March 21)
- Maundy Thursday and Good Friday (April 14 and April 15 in 2021)
- Labour Day (May 1)
- Ascension Day Holiday (May 30)
- Corpus Christi Holiday (June 20)
- Sacred Heart (June 27)
- Saints Peter and Paul's Day (July 4)
- Declaration of Independence (July 20)
- Battle of Boyaca (August 7)
- Assumption Day (August 15)
- Day of the Races (October 17)
- All Saints' Day Holiday (November 7)
- Independence of Cartagena (November 14)
- Immaculate Conception Day (December 8)
- Christmas Day (December 25)

Cambodia Holidays:

- New Year's Day (January 1)
- Victory over Genocide Day (January 7)
- International Women's Day (March 8)
- Khmer New Year (April 14-16 in 2021 and August 17-21 in 2020, as a replacement holiday)
- Visak Bochea Day (April 26)
- Royal Plowing Ceremony (April 30)
- International Labour Day (May 1)
- King's Birthday (May 14)
- King's Mother's Birthday (June 18)
- Constitutional Day (September 24)
- Ancestors' Day (October 5-7)
- Commemoration Day of King's Father (October 15)
- King's Coronation Day (October 29)
- Independence Day (November 9)
- Water Festival Ceremony (November 18-20)

Kenya Holidays:

- New Year's Day (January 1)
- Good Friday and Easter Monday (April 15 and April 18, respectively)
- President Kibaki State Funeral (April 19)
- Labour Day (May 2)
- Idd-ul-Fitr (May 3)
- Madaraka Day (June 1)
- Idd-ul-Azha (July 10)
- Utamaduni Day (October 10)
- Mashujaa Day (October 20)
- Jamhuri Day (December 12)
- Christmas Day and Boxing Day (December 25 and December 26, respectively)