

On the Vertex Position Number of Graphs

Maya G.S. Thankachy^a, Elias John Thomas^b, Ullas Chandran S. V.^a, James Tuite^c, Gabriele Di Stefano^d, Grahame Erskine^c

^a*Department of Mathematics, Mahatma Gandhi College, University of Kerala, Thiruvananthapuram-695004, Kerala, India*

^b*Department of Mathematics, Mar Ivanios College, University of Kerala, Thiruvananthapuram-695015, Kerala, India*

^c*Department of Mathematics and Statistics, Open University, Walton Hall, Milton Keynes, UK*

^d*Department of Information Engineering, Computer Science and Mathematics, University of L'Aquila, Italy*

Abstract

In this paper we generalise the notion of visibility from a point in an integer lattice to the setting of graph theory. For a vertex x of a connected graph G , we say that a set $S \subseteq V(G)$ is an x -position set if for any $y \in S$ the shortest x, y -paths in G contain no point of $S \setminus \{y\}$. We investigate the largest and smallest orders of maximum x -position sets in graphs, determining these numbers for common classes of graphs and giving bounds in terms of the girth, vertex degrees, diameter and radius. Finally we discuss the complexity of finding maximum vertex position sets in graphs.

Keywords: geodesic, vertex position set, vertex position number, general position

2000 MSC: 05C12, 05C69

1. Introduction

All graphs considered in this paper are finite, undirected and simple. For a graph G we will denote the subgraph induced by a subset $S \subseteq V(G)$ by

Email addresses: mayagstthankachy@gmail.com (Maya G.S. Thankachy), eliasjohnkalarickal@gmail.com (Elias John Thomas), svuc.math@gmail.com (Ullas Chandran S. V.), james.t.tuite@open.ac.uk (James Tuite), gabriele.distefano@univaq.it (Gabriele Di Stefano), grahame.erskine@open.ac.uk (Grahame Erskine)

$G[S]$. The *distance* $d(u, v)$ between two vertices u and v in a connected graph G is the length of a shortest u, v -path in G ; any such path is called a *geodesic*. The distance is a metric on the vertex set V . The diameter $\text{diam}(G)$ of a connected graph G is the length of any longest geodesic. For any vertex u of G , the *eccentricity* of u is $e(u) = \max\{d(u, v) : v \in V\}$. A vertex v of G such that $d(u, v) = e(u)$ is called an *eccentric vertex* of u . The neighborhood of a vertex v is the set $N(v)$ consisting of all vertices u which are adjacent with v . A vertex v is *simplicial* if the subgraph induced by its neighborhood $N(v)$ is complete; we will denote the number of simplicial vertices of a graph G by $s(G)$ and the set of all simplicial vertices of G by $\text{Ext}(G)$. A set of vertices in a graph is *independent* if no two vertices in the set are adjacent; the independence number $\alpha(G)$ is the number of vertices in a largest independent set of G . A graph is a *block graph* if every maximal 2-connected component is a clique. For basic graph theoretic terminology not defined here we refer to [4, 6].

Visibility and illumination problems are among the most attractive and interesting research topics in combinatorics, geometry and number theory [3]. Such problems have been studied intensively in the context of the integer lattice; a set Λ of points of the lattice is *visible* from a point x if for any $y \in \Lambda$ the line segment from x to y contains no other points of Λ . A well-known result from elementary analytic number theory first proved by Sylvester [19] states that the density of the set of points in the integer lattice that are visible from the origin is $\frac{6}{\pi^2}$ [2]. In particular, in Chapter III of [14], it is shown how to place a set of points with positive integer coordinates (i, j) , $j \leq i$, in such a way that each point is visible from the origin $(0, 0)$, by also maximising the number of points with the same abscissa. This construction has interesting relations with the Farey series and Euler's totient function ϕ . Other interesting visibility problems in integer lattices can be found in [9, 13].

In recent years the algorithmic component of visibility problems has attracted great attention under the name *art gallery* or *watchman* problems, which lie in the intersection of combinatorial and computational geometry [18]. Art gallery problems, theorems and algorithms are so named after the celebrated 48 years old problem posed by V. Klee. In 1973 he asked the following question: 'What is the minimum number of guards sufficient to cover the interior of an n -wall gallery?'. This problem was solved by Chvátal and subsequently by Fisk. By creating idealised situations such as obstacles, guards, etc., the theory succeeds in abstracting the algorithmic essence of many visibility problems.

Taking our inspiration from the result of Sylvester [19], in this paper we consider a generalisation of ‘local visibility problems’ to the context of the general position problem in graph theory. The general position problem originated in Dudeney’s no-three-in-line problem [8] and the general position subset selection problem [10, 17] from discrete geometry. These problems were generalised to graphs independently in [5] and [15]. A set S of vertices of a graph G is in *general position* if for any $u, v \in S$ any u, v -geodesic does not intersect $S \setminus \{u, v\}$. The *general position number* $gp(G)$ of G is the number of vertices in a largest general position set in G . We refer the reader to [1, 16, 20] for more information on the general position problem.

In a recent paper Di Stefano [7] introduced the concept of a *mutual visibility set* in a graph; a set S of points in a graph G are *mutually visible* if for any $u, v \in S$ there exists a shortest u, v -path in G that does not pass through $S \setminus \{u, v\}$; the *mutual visibility number* $\mu(G)$ of G is the number of vertices in a largest mutual visibility set in G . In [7] the mutual visibility number of some classes of graphs are determined and it is shown that the problem of finding a largest mutual visibility set is NP-complete for general graphs.

We now study a ‘local’ version of these problems using a parameter that we call the *vertex position number* of a graph. The plan of this paper is as follows. In Section 2 we provide some bounds on the vertex position numbers of a graph. In Section 3 the vertex position numbers of some common classes of graphs are determined. We characterise the graphs with very large or small vertex position numbers in Section 4. Finally in Section 5 we consider the computational complexity of finding the vertex position number of a graph.

2. Vertex position sets in graphs

In this section we derive bounds for the vertex position numbers of a graph in terms of the minimum and maximum degrees, radius and diameter. First we formally define the vertex position numbers.

Definition 2.1. *For any graph G and a fixed vertex $x \in V(G)$, a set $S_x \subseteq V(G)$ is an x -position set if for any $y \in S_x$ no vertex of $S_x \setminus \{y\}$ lies on any x, y -geodesic in G . The x -position number of G is defined to be the maximum cardinality of an x -position set and is denoted by $p_x(G)$ or simply p_x . An x -position set of cardinality $p_x(G)$ is called a p_x -set. The maximum value of $p_x(G)$ among all vertices x of G is called the upper vertex position number $vp(G)$ (or simply the vertex position number) of G . Similarly, the minimum*




Figure 2.1

value of $p_x(G)$ among all vertices of G is called the minimum vertex position number $\text{vp}^-(G)$ of G .

To illustrate these concepts, consider the graph G in Figure 2.1. We give the x -position numbers of G for representative vertices in Table 1, together with a (not necessarily unique) x -position set. We see from the table that $\text{vp}^-(G) = 4$ and $\text{vp}(G) = 11$.

Vertex	p_x -set	$p_x(G)$
x	$\{c_1, c_2, c_3, c_4\}$	4
c_1	$\{x, c_2, c_3, c_4, b_1, b_2, b_3, b_4\}$	8
b_1	$\{c_1, c_2, c_3, c_4, b_2, b_3, b_4, a_1, a_2, a_3, a_4\}$	11
a_1	$\{a_2, a_3, a_4, b_1, b_2, b_3, b_4\}$	7

Table 1

Unless stated otherwise (for example in Theorem 2.13) we assume all graphs to be connected. However, Definition 2.1 also applies to disconnected graphs; if x belongs to a component C of a disconnected graph G , then any vertex y from another component D of G can be included in an x -position set, as there is no x, y -path in G . Hence in this case $p_x(G) = (n - |C|) + p_x(C)$.

For any vertex $x \in V(G)$ the set $\{x\}$ is an x -position set; however, by the convention in Definition 2.1, if G is connected, then x is not contained in any x -position set of order ≥ 2 . Hence for any connected graph G with order $n \geq 2$ we have $1 \leq p_x(G) \leq n - 1$ for any $x \in V(G)$ and, more generally, a (not necessarily connected) graph G has $\text{vp}(G) = n$ if and only if G has

an isolated vertex. These bounds are sharp: for any path P_n of length ≥ 1 we have $p_x(P_n) = 1$ for either terminal vertex, whilst for $n \geq 2$ we have $p_x(K_n) = n - 1$ for every vertex of a complete graph K_n . In this section we derive several bounds for the vertex position numbers in terms of various graph parameters. First we compare the vertex position number with the general position number.

Lemma 2.2. *The vertex position number and general position number of a graph are related by $\text{vp}(G) \geq \text{gp}(G) - 1$.*

Proof. Let S be a gp-set of G with $|S| = \text{gp}(G)$. Choose a vertex $x \in S$. Then $S \setminus \{x\}$ is an x -position set, implying that $\text{vp}(G) \geq p_x(G) \geq \text{gp}(G) - 1$. ■

The bound in Lemma 2.2 is met by the complete graph K_n . However, we now give an example to show that the numbers $\text{vp}^-(G)$, $\text{gp}(G)$ and $\text{vp}(G)$ can be arbitrarily far apart. For $r \geq 2$ we define the vertex set of the graph $G(r)$ to be $\{u_{i,j} : 1 \leq i \leq 7, 1 \leq j \leq r\} \cup \{x\}$. Let $H(r)$ be the graph on the same vertex set as $G(r)$ with adjacencies defined as follows:

- $x \sim u_{1,j}$ for $1 \leq j \leq r$,
- $u_{i,j} \sim u_{i,j'}$, $1 \leq i \leq 7$, $1 \leq j, j' \leq r$ and $j \neq j'$, and
- $u_{i,j} \sim u_{i+1,j'}$ for $1 \leq i \leq 6$ and $1 \leq j, j' \leq r$.

Now define $G(r)$ to be the graph formed by deleting all edges to the vertices $u_{3,1}$, $u_{4,1}$ and $u_{5,1}$ except for the path $u_{2,1}, u_{3,1}, u_{4,1}, u_{5,1}, u_{6,1}$. See Figure 2.2 for an example. The minimum vertex position number of this graph is r (attained at the vertex x) and the vertex position number is $6r - 4$ (attained at the vertex $u_{4,1}$).

Lemma 2.3. *For $r \geq 3$, we have $\text{vp}^-(G(r)) = r$, $\text{gp}(G(r)) = 2r$, $\text{vp}(G(r)) = 6r - 4$.*

This raises the question of how far apart the numbers $\text{vp}^-(G)$ and $\text{vp}(G)$ can be.

Problem 2.4. *Is the ratio $\frac{\text{vp}(G)}{\text{vp}^-(G)}$ bounded for connected graphs?*

We now bound the vertex position numbers in terms of the vertex degrees.




Figure 2.2: A graph with $vp^- = r$ (green vertex) and $vp = 6r - 4$ (blue vertex). A largest vp -set of the blue vertex is shown in red.

Lemma 2.5. *Let G have minimum degree δ and maximum degree Δ . Then $vp^-(G) \geq \delta$ and $vp(G) \geq \Delta$.*

Proof. It follows from Definition 2.1 that for any vertex x of G the neighbourhood $N(x)$ is an x -position set of G . Therefore for all vertices $x \in V(G)$ we have $p_x(G) \geq d(x)$. This implies that all p_x -sets have order at least δ and there exists a p_x -set with order at least Δ . ■

We now generalise this result to sets of vertices at given distance from a fixed vertex; this leads to bounds on $p_x(G)$ in terms of the order n of G and the eccentricity $e(x)$ of the vertex x .

Lemma 2.6. *For any vertex x of G with eccentricity $e(x)$ the vertex position number satisfies $p_x(G) \geq \frac{n-1}{e(x)}$. Thus $vp^-(G) \geq \frac{n-1}{\text{diam}(G)}$ and $vp(G) \geq \frac{n-1}{\text{rad}(G)}$.*

Proof. For $1 \leq t \leq e(x)$, let V_t be the set of vertices at distance exactly t from x in G . Each of the sets V_t is an x -position set and one of them must have order at least $\frac{n-1}{e(x)}$, so that $p_x(G) \geq \frac{n-1}{e(x)}$. Since $\text{rad}(G) \leq e(x) \leq \text{diam}(G)$ for all $x \in V(G)$ the result follows. ■

This bound immediately characterises the graphs with vertex position number one.

Corollary 2.7. *A graph G satisfies $\text{vp}^-(G) = 1$ if and only if G is a path. The only connected graphs with $\text{vp}(G) = 1$ are K_1 and K_2 .*

Proof. If x is the terminal vertex of a path P_n , then $p_x(P_n) = 1$. Conversely, if $\text{vp}^-(G) = 1$, then by Lemma 2.6 we must have $\text{diam}(G) = n - 1$, which implies that G is a path. By Lemma 2.5 any graph G with $\text{vp}(G) = 1$ must have maximum degree $\Delta \leq 1$, which proves the latter statement. ■

The argument of Lemma 2.6 also easily yields the vertex position number of the join of two graphs.

Corollary 2.8. *If G_i has order n_i and maximum degree Δ_i for $i = 1, 2$, then the vertex position number of the join is*

$$\text{vp}(G \vee H) = \max\{n_1 + \Delta_2, n_2 + \Delta_1\}.$$

Proof. The diameter of G is two. For any vertex x in G_1 the set $V(G_2) \cup N_{G_1}(x)$ is an x -position set by Lemma 2.6 with order $n_2 + \Delta_1$, with a similar result for vertices y in G_2 . Suppose without loss of generality that the largest vertex position set is attained at a vertex $x \in V(G_1)$. Then we can assume that a p_x -set contains a vertex of G_2 , for otherwise $\text{vp}(G \vee H) = p_x(G \vee H) \leq n_1 < p_y(G \vee H)$ for any $y \in V(G_2)$, a contradiction. As a maximum p_x -set S_x contains a vertex of G_2 , S_x cannot contain any vertex of $V(G_1) \setminus (\{x\} \cup N_{G_1}(x))$, so that $p_x(G \vee H) \leq n_2 + \Delta_1$. The result follows. ■

Theorem 2.9. *For any connected graph G we have $\text{vp}^-(G) \geq \lceil \frac{\Delta+1}{3} \rceil$. If G is bipartite, then $\text{vp}^-(G) \geq \lceil \frac{\Delta}{2} \rceil$.*

Proof. Let G be a connected graph with maximum degree Δ and let x be a vertex of G with this degree. Let y be any vertex of G . If $y = x$, we have $p_y(G) \geq \Delta$, so suppose that $y \neq x$ and let $r \geq 0$ be the length of the shortest path from y to $N(x)$. Then it can be seen that the distance from y to any vertex of $\{x\} \cup N(x)$ is one of $r, r + 1$ or $r + 2$. It follows that one of the level sets of G in the distance partition with respect to y must have order at least $\frac{\Delta+1}{3}$. Hence $p_y(G) \geq \frac{\Delta+1}{3}$ and our proof is complete. If G is bipartite, then $N(x)$ is an independent set and the distance from y to any vertex of $N(x)$ is either r or $r + 2$, so we can improve the bound to $\text{vp}^-(G) \geq \frac{\Delta}{2}$ in this case. The constructions in Figures 2.3 show that both of these bounds are tight (in both cases x is a vertex with maximum degree and $p_y(G) = \text{vp}^-(G)$). ■




Figure 2.3: A graph with $\text{vp}^-(G) = \lceil \frac{\Delta+1}{3} \rceil$ (left) and a bipartite graph with $\text{vp}^-(G) = \frac{\Delta}{2}$ (right), with p_y -sets in red.

Now we give an upper bound for the vertex position number in terms of vertex eccentricity.

Lemma 2.10. *For any vertex x of G with eccentricity $e(x)$, the x -vertex position number of G is bounded above by $p_x(G) \leq n - e(x)$. Thus $\text{vp}(G) \leq n - \text{rad}(G)$ and $\text{vp}^-(G) \leq n - \text{diam}(G)$.*

Proof. Fix a vertex x of G with eccentricity $e(x)$. Let y be an eccentric vertex of x , i.e. $d(x, y) = e(x)$. Let $x = u_0, u_1, \dots, u_{e(x)} = y$ be an x, y -geodesic in G and S_x be an x -position set of G with order $p_x(G)$. Suppose that $u_i, u_j \in S_x$ for some i, j with $0 \leq i < j \leq e(x)$. But then u_i lies on an x, u_j -geodesic, contradicting the fact that S_x is an x -position set. Hence any x -position set contains at most one vertex from the set $\{x, u_1, u_2, \dots, u_{e(x)}\}$. Thus $p_x(G) = |S_x| \leq n - 1 - e(x) + 1 = n - e(x)$. Thus $\text{vp}(G) \leq n - \text{rad}(G)$ and $\text{vp}^-(G) \leq n - \text{diam}(G)$. ■

The following theorem improves the upper bound for $\text{vp}(G)$ in Lemma 2.10.

Theorem 2.11. *For any graph G with $\text{rad}(G) \geq 3$ we have $\text{vp}(G) \leq n - \text{rad}(G) - 1$.*

Proof. Suppose that G has radius $\text{rad}(G) \geq 3$ and meets the upper bound in Lemma 2.10. Then the largest value of the vertex position number is achieved by a central vertex, call it u . Let S_u be any u -position set of order $n - \text{rad}(G)$. By the argument of Lemma 2.10 there is a path P from u to one of its eccentric vertices such that P contains just one vertex of S_u and all vertices of $V(G) \setminus V(P)$ belong to S_u . As the shortest path from u to any




Figure 2.4: The boundary $\partial(x)$ (shown in red) is a p_x -set

vertex $x \in V(G) \setminus V(P)$ cannot pass through another vertex of $V(G) \setminus V(P)$, the shortest path from u to x consists of a section of P followed by an edge from P to x . Hence each vertex of $V(G) \setminus V(P)$ has an edge to P ; however, this contradicts our supposition that u is a central vertex. ■

A vertex v in a connected graph G is a *boundary vertex* of a vertex u if $d(u, w) \leq d(u, v)$ for each neighbour w of v . The set of all boundary vertices of u is denoted by $\partial(u)$.

Proposition 2.12. *For any connected graph G and any vertex $x \in V(G)$, the boundary $\partial(x)$ is an x -position set of G .*

Proof. Assume to the contrary that $\partial(x)$ is not an x -position set; hence there must be a geodesic $x = u_0, u_1, \dots, u_i = z, u_{i+1}, \dots, u_k = y$ such that $z, y \in \partial(x)$ and $z \neq y$. This shows that $d(x, u_{i+1}) > d(x, z)$, contradicting the fact that z is a boundary vertex of x . Hence $\partial(x)$ is an x -position set. ■

It follows from Proposition 2.12 that for any $x \in V(G)$ the set $\text{Ext}(G) \setminus \{x\}$ is an x -position set. The bound in Proposition 2.12 is tight for the vertex x in the graph in Figure 2.4, but this is not true in general. In fact for any $s \geq t$ if we take a vertex x in the partite set of order $t + 1$ in the complete bipartite graph $K_{s,t+1}$ then $|\partial(x)| = t$ but $p_x(K_{s,t+1}) = s$.

Finally we present a Nordhaus-Gaddum relation for the vertex position number.

Theorem 2.13. *For any graph G we have $n - 1 \leq \text{vp}(G) + \text{vp}(\overline{G}) \leq 2n - 1$. Both bounds are tight.*

Proof. Notice that one of G and \overline{G} could be disconnected. Let x be any vertex of a graph G with degree $d(x)$. In the complement \overline{G} the vertex x has

degree $d'(x) = n - 1 - d(x)$. By Lemma 2.5 we thus have

$$\text{vp}(G) + \text{vp}(\overline{G}) \geq p_x(G) + p_x(\overline{G}) \geq d(x) + n - 1 - d(x) = n - 1. \quad (1)$$

To show that equality holds, consider the cycle C_n for $n \geq 5$. If $n = 5$ the result is simple, as $\overline{C_5} \cong C_5$, so take $n \geq 6$. Label the vertices of the cycle x_0, x_1, \dots, x_{n-1} , where $x_0 \sim x_{n-1}$ and $x_i \sim x_{i+1}$ for $0 \leq i \leq n - 2$. As will be shown in Corollary 4.2, we have $\text{vp}(C_n) = 2$. Consider the vertex x_0 (as $\overline{C_n}$ is vertex-transitive the choice is arbitrary) and let S be a largest x_0 -position set. The degree of x_0 is $d(x) = n - 3$, so that by Lemma 2.5 we have $\text{vp}(\overline{C_n}) \geq n - 3$. Suppose that a vertex x_i , $3 \leq i \leq n - 3$, belongs to S ; then as x_0, x_i, x_1 and x_0, x_i, x_{n-1} are shortest paths we must have $x_1, x_{n-1} \notin S$, so that $|S| \leq n - 3$. Furthermore S cannot contain both vertices x_{n-2} and x_1 and likewise cannot contain both x_2 and x_{n-1} , so in any case $|S| \leq n - 3$. Thus $\text{vp}(\overline{C_n}) = n - 3$ and we have $\text{vp}(C_n) + \text{vp}(\overline{C_n}) = n - 1$.

Applying this argument to a vertex of maximum degree Δ and a vertex with minimum degree δ gives the stronger bound $\text{vp}(G) + \text{vp}(\overline{G}) \geq n - 1 + \Delta - \delta$, so we see that we have equality in Equation 1 if and only if G is regular and both G and \overline{G} have vertex position number equal to their maximum degree.

Trivially for $n \geq 2$ we have $\text{vp}(G) \leq n$, with equality if and only if G has an isolated vertex. Not both of G and \overline{G} can have an isolated vertex, for if G has an isolated vertex, then \overline{G} contains a universal vertex. Therefore we do not have equality in both $\text{vp}(G) \leq n$ and $\text{vp}(\overline{G}) \leq n$, so it follows that $\text{vp}(G) + \text{vp}(\overline{G}) \leq 2n - 1$. Equality holds if and only if G contains an isolated vertex or a universal vertex. ■

3. Vertex position numbers of certain classes of graphs

In this section, we determine the x -position number of certain standard classes of graphs.

Lemma 3.1. *Let x be a vertex of a connected graph G and $S_x \subseteq V(G)$ be an x -position set of G . If C_1, C_2, \dots, C_k are the components of $G[S_x]$, then there exist r_1, r_2, \dots, r_k such that $d(x, y) = r_i$ for all $y \in C_i$.*

Proof. Suppose that there is a component C of $G[S_x]$ and $y, y' \in V(C)$ such that $d(x, y) \neq d(x, y')$. Then, considering a shortest path from y to y' in $G[C]$, we see that there is a pair $z, z' \in V(C)$ such that $z \sim z'$ and $d(x, z) =$

$d(x, z) + 1$. However, this implies that an x, z -geodesic followed by the edge $z \sim z'$ is a shortest x, z' -path that passes through z , a contradiction. ■

Theorem 3.2. *If G is a bipartite graph, then $\text{vp}(G) \leq \alpha(G)$.*

Proof. Let S_x be an x -position set of G and suppose for a contradiction that S_x is not an independent set. Then there are $y, z \in S_x$ such that $y \sim z$ in G . By Lemma 3.1 we have $d(x, y) = d(x, z) = r$ for some $r \geq 1$. A shortest x, y -path, a shortest x, z -path and the edge $y \sim z$ together constitute an odd circuit, implying the existence of an odd cycle; since G is bipartite, this is impossible and it follows that $p_x(G) \leq \alpha(G)$. ■

Theorem 3.3. *For $r \geq 2$, let K_{n_1, n_2, \dots, n_r} be the complete multipartite graph with partite sets V_1, V_2, \dots, V_r , where $n_i = |V_i|$ and $n_1 \geq n_2 \geq \dots \geq n_r$. Set $n = \sum_{i=1}^r n_i$. Then if the vertex x lies in V_i , the x -position number is given by*

$$p_x(K_{n_1, n_2, \dots, n_r}) = \max\{n - n_i, n_i - 1\}.$$

Thus $\text{vp}(K_{n_1, n_2, \dots, n_r}) = n - n_r$.

Proof. Let $x \in V_i$ and let S be a maximum x -position set of the graph. Set $V = \bigcup_{i=1}^r V_i$. Suppose that S contains a vertex $y \in V_i \setminus \{x\}$; for any vertex $z \in V \setminus V_i$ the path x, z, y is a geodesic, so that in this case $S \cap (V \setminus V_i) = \emptyset$. Thus either $S \subseteq V \setminus V_i$ or $S \subseteq V_i \setminus \{x\}$. Conversely, both of these sets are x -position sets by the argument of Lemma 2.6, which yields the claimed bounds. ■

Theorem 3.3 shows that equality holds in the bound of Theorem 3.2 for all complete bipartite graphs.

Lemma 3.4. *Let G be a connected graph of order n . Then for each $x \in V(G)$ there is a maximum x -position set without cutvertices.*

Proof. Suppose that there is a maximum x -position set M containing a cutvertex $v \neq x$ of G . Let C_1, C_2, \dots, C_k be the components of $G \setminus \{v\}$, where $k \geq 2$. Without loss of generality we may assume that $x \in V(C_1)$. Then it follows that $M \cap V(C_i) = \emptyset$ for all $i = 2, 3, \dots, k$. Let u_i be any vertex in C_i for all $i = 2, 3, \dots, k$. If $k \geq 3$, then the set $M' = (M \setminus \{v\}) \cup \{u_2, u_3, \dots, u_k\}$ is an x -position set with order greater than M , a contradiction to the maximality of M . Hence $k = 2$. Let u be a farthest vertex from v in C_2 . Then u is not a cutvertex in G . Moreover, $M' = (M \setminus \{v\}) \cup \{u\}$ is a maximum x -position set containing fewer cutvertices than M ; this implies the existence of a maximum x -position set without cutvertices in G . ■

Theorem 3.5. *For any block graph G ,*

$$p_x(G) = \begin{cases} s(G) - 1, & \text{if } x \text{ is a simplicial vertex,} \\ s(G), & \text{otherwise.} \end{cases}$$

Proof. First suppose that x is a simplicial vertex. Then it is clear that $s(G) \setminus \{x\}$ is an x -position set in G . Hence $p_x(G) \geq s(G) - 1$. On the other hand, in a block graph each vertex is either a cutvertex or a simplicial vertex. By the above lemma, G contains a maximum x -position set without cutvertices. Hence the result follows. ■

Corollary 3.6. *For any tree T with ℓ leaves we have*

$$p_x(T) = \begin{cases} \ell - 1, & \text{if } x \text{ is a leaf,} \\ \ell, & \text{otherwise.} \end{cases}$$

Corollary 3.6 implies the following bound for the vertex position numbers in terms of the girth of the graph.

Theorem 3.7. *If a graph G has girth g and minimum degree $\delta \geq 2$ and there are N vertices at distance less than or equal to $\lfloor \frac{g-1}{2} \rfloor - 1$ from a vertex u , then $p_u(G) \leq n - N$.*

Proof. Set $r = \lfloor \frac{g-1}{2} \rfloor$. Fix a vertex u of G and consider the subgraph G' induced by the vertices at distance at most r from u . G' is isomorphic to a tree, possibly with some edges added between the vertices at distance r from u . It follows from Corollary 3.6 that the largest number of vertices from G' that can belong to a u -position set is the number of vertices at distance exactly r from u ; hence there are at least N vertices missing from any u -position set and $p_u(G) \leq n - N$. ■

Theorem 3.7 is tight for the Petersen and Hoffman-Singleton graphs by Lemma 2.6. Finally, we note that Lemma 2.5 gives the vertex position number of sufficiently large Kneser graphs. The Kneser graph $K(n, k)$ is the graph with vertex set equal to all k -subsets of $\{1, 2, \dots, n\}$ with an edge between any two such subsets if and only if they are disjoint.

Theorem 3.8. *For sufficiently large n we have $\text{vp}(K(n, k)) = \binom{n-k}{k}$.*




Figure 3.1: A largest x -position set (red vertices) in the Petersen graph

Proof. For $n \geq 3k$ the Kneser graph $K(n, k)$ has diameter two. Note that $K(n, k)$ is vertex-transitive, so $\text{vp}(K(n, k)) = \text{vp}^-(K(n, k))$ and we can without loss of generality consider the vertex $\{1, 2, \dots, k\}$; let S be a largest $\{1, 2, \dots, k\}$ -position set. Lemma 2.5 gives $|S| = \text{vp}(K(n, k)) \geq \binom{n-k}{k}$. Suppose that S contains a vertex at distance two from $\{1, 2, \dots, k\}$, say $\{1, 2, \dots, i, j_{i+1}, j_{i+2}, \dots, j_k\}$, where

$$\{1, 2, \dots, k\} \cap \{1, 2, \dots, i, j_{i+1}, j_{i+2}, \dots, j_k\} = \{1, 2, \dots, i\}.$$

As $\{1, 2, \dots, k\}$ and $\{1, 2, \dots, i, j_{i+1}, j_{i+2}, \dots, j_k\}$ have exactly $\binom{n-2k+i}{k}$ common neighbours, we would have $|S| \leq \binom{n}{k} - \binom{n-2k+i}{k}$, which is a polynomial of degree $k-1$, whereas the vertex degree is a polynomial function of n with degree k . Thus for sufficiently large n compared to k the bound in Lemma 2.5 is best possible. ■

Interestingly Theorem 3.8 implies that for large n the vertex position number of $K(n, k)$ is significantly larger than the general position number, as given in [11]. For small n Lemma 2.5 is not optimal; for example, as previously noted for the Petersen graph P (isomorphic to $K(5, 2)$) the second neighbourhood of a vertex is a largest vertex position set and $\text{vp}(P) = \text{gp}(P) = 6$.

4. Characterisation results

We now make use of the bounds derived in Section 2 to characterise graphs with very large or very small vertex position numbers.

Corollary 4.1. *A connected graph G with order n satisfies $\text{vp}(G) = n - 1$ if and only if G contains a universal vertex, whilst $\text{vp}^-(G) = n - 1$ if and only if G is a complete graph.*

Proof. By Lemma 2.5 any universal vertex u has vertex position number $p_u(G) = n - 1$. Conversely, by Lemma 2.10 any vertex u with $p_u(G) = n - 1$ has eccentricity one and hence is universal. If $\text{vp}^-(G) = n - 1$, it follows that G is complete. ■

Corollary 4.2. *A connected graph G satisfies $\text{vp}^-(G) = \text{vp}(G) = 2$ if and only if G is a cycle. Similarly $\text{vp}(G) = 2$ only for cycles and paths of length ≥ 2 .*

Proof. Let C_n be a cycle for some $n \geq 3$. As C_n is 2-regular, by Lemma 2.5 we have $\text{vp}^-(C_n) \geq 2$. We now show that $\text{vp}(C_n) \leq 2$. Let x be any vertex of C_n and suppose that there exists an x -position set S_x of C_n of order ≥ 3 ; we can assume that $x \notin S_x$. Let A be the set of antipodal vertices of x , i.e. the vertices of C_n at distance $\lfloor \frac{n}{2} \rfloor$ from x . We have $|A| = 1$ if n is even and $|A| = 2$ if n is odd. Let P_1 and P_2 be the two shortest paths from x to A . Then one of P_1 and P_2 (say P_2) contains distinct vertices $u, v \in S_x$. Hence either u is on the v, x -geodesic or v is on the u, x -geodesic, a contradiction. Hence $|S_x| \leq 2$ and, since x is an arbitrary vertex of C_n , we have $\text{vp}^-(C_n) = \text{vp}(C_n) = 2$.

Conversely, suppose that $\text{vp}(G) = 2$; it follows from Lemma 2.5 that G has maximum degree $\Delta = 2$, so that G is either a path or a cycle. As $\text{vp}^-(P_\ell) = 1$ for paths by Corollary 2.7, it follows that if $\text{vp}^-(G) = 2$, then G is a cycle. ■

Now we characterise some graphs with very large vertex position number.

Lemma 4.3. *A vertex u of a connected graph G with order n has $p_u(G) = n - 2$ if and only if either i) u has degree $d(u) = n - 2$, or ii) u has a neighbour v such that v is a cutvertex of G and $\{u, v\}$ dominates G , in which case the unique largest p_u -set of G is $S_u = V(G) \setminus \{u, v\}$.*

Proof. Let G be a graph with order n and let $u \in V(G)$ satisfy $p_u(G) = n - 2$, with S_u a largest u -position set. If u is a universal vertex, then by Corollary 4.1 we would have $p_u(G) = n - 1$, so u has degree $d(u) \leq n - 2$. Hence by Lemma 2.10 u has eccentricity two. If $d(u) = n - 2$, then $N(u)$ is a u -position set, so we can assume that $d(u) \leq n - 3$. Hence $V(G) = \{u\} \cup N(u) \cup N^2(u)$ and $|N^2(u)| \geq 2$.

Let x, y be any vertices in $N^2(u)$. Suppose that one of these vertices, say x , has at least two common neighbours with u . If $x \in S_u$, then we must have $N(x) \cap N(u) \cap S_u = \emptyset$; however, this contradicts $u \notin S_u$, implying that $x \notin S_u$ and $S_u = V(G) \setminus \{u, x\}$, so that $N(u) \subseteq S_u$. As $y \in N^2(u) \cap S_u$ and has a neighbour in $N(u)$, this is also a contradiction. Therefore every vertex in $N^2(u)$ has just one neighbour in $N(u)$.

Suppose that $N(u) \cap N(x) = \{v\}$ and $N(u) \cap N(y) = \{v'\}$, where $v \neq v'$. Then $|S_u \cap \{v, x\}| \leq 1$ and $|S_u \cap \{v', y\}| \leq 1$, which, together with u , accounts for at least three vertices missing from S_u . Thus we must have $v = v'$ and there is a vertex $v \in N(u)$ that is the unique neighbour in $N(u)$ of every vertex in $N^2(u)$. Hence $\{u, v\}$ dominates G . Furthermore in any such graph $V(G) \setminus \{u, v\}$ is a u -position set, so that $\text{vp}(G) = n - 2$. ■

Theorem 4.4. *For $n \geq 4$, a graph G with order n satisfies $\text{vp}^-(G) = \text{vp}(G) = n - 2$ if and only if G is isomorphic to an even clique with a perfect matching deleted, i.e. if and only if $G \cong K_{2,2,\dots,2}$.*

Proof. Assume that G is a graph such that $p_u(G) = n - 2$ for every $u \in V(G)$. Suppose that G contains a vertex u with degree $\leq n - 3$, so that by Lemma 4.3 u has eccentricity two and u has a neighbour v that is a cutvertex of G and $\{u, v\}$ is a dominating set of G . As $\text{vp}(G) = n - 2$, G contains no universal vertex, so that there is a neighbour w of u such that $v \not\sim w$. Hence if $x \in N^2(u)$ we have $d(x, w) \geq 3$ and x has eccentricity at least three, so that by Lemma 2.10 we have $p_x(G) \leq n - 3$, a contradiction. Therefore every vertex of G has degree $n - 2$ and G is isomorphic to a K_{2r} with a perfect matching deleted. Conversely in such a graph every vertex has vertex position number $n - 2$. ■

Theorem 4.5. *For $n \geq 4$, a graph G has $\text{vp}^-(G) = n - 2$ and $\text{vp}(G) = n - 1$ if and only if i) G is isomorphic to a clique with a non-empty, non-perfect matching deleted or ii) G is the join of K_1 with a disjoint union of cliques.*

Proof. Let G be a graph with $\text{vp}^-(G) = n - 2$ and $\text{vp}(G) = n - 1$. We can assume that G contains $r \geq 1$ universal vertices as well as at least two vertices with degree $\leq n - 2$. If every vertex has degree either $n - 1$ or $n - 2$, then G is isomorphic to a clique with a matching deleted. To avoid the graph having $\text{vp}^-(G) = \text{vp}(G) = n - 1$ the matching is non-empty and to avoid having $\text{vp}^-(G) = \text{vp}(G) = n - 2$ the matching is not perfect by Theorem 4.4.

Suppose that G contains a vertex u with $p_u(G) = n - 2$ and degree $d(u) \leq n - 3$. By Lemma 4.3 u has eccentricity two and has a neighbour

v that is a cutvertex. By Lemma 2.10 every vertex of G has eccentricity at most two, so, considering the vertices in $N^2(u)$, we see that v is a universal vertex. As v is a cutvertex, it is the unique universal vertex of G , so that every other vertex w of G must have $p_w(G) = n - 2$. For any $w \in V(G) \setminus \{v\}$, let S_w be a w -position set of order $n - 2$. Suppose that $v \in S_w$. Then S_w cannot contain w or any vertex from a component of $G - v$ not containing w ; this is impossible unless $G \cong P_3$, which has the stated structure, so we can assume that $S_w = V(G) \setminus \{w, v\}$ for each $w \in V(G) \setminus \{v\}$. Suppose then that there is a component W of $G - v$ that is not a clique, so that there are vertices w_1, w_2, w_3 in W such that w_1, w_2, w_3 is a path, but $w_1 \not\sim w_3$. However, this implies that w_2 and w_3 cannot both belong to a largest w -position set S_{w_1} , which is a contradiction, since $S_{w_1} = V(G) \setminus \{w_1, v\}$. Hence the graph must be the join of K_1 with a disjoint union of cliques, which is easily verified to have the correct vertex position numbers. ■

5. Computational complexity

Given a graph G , in this section we show that the vertex position number $p_x(G)$ can be computed in polynomial time for any vertex $x \in V(G)$. In particular, we will show that $p_x(G)$, for each $x \in V(G)$, can be computed as an independent set calculated on a graph obtained as a transformation of G . To this aim we need the following definitions.

Definition 5.1. *A graph is a comparability graph if the edges connect pairs of elements that are comparable to each other in a partial order.*

Definition 5.2. *Given a graph G and a vertex $x \in V(G)$, the reduced graph \tilde{G}_x is the graph on the same vertices $V(G)$ obtained from G by removing all the edges connecting vertices at the same distance from x .*

Definition 5.3. *Given a graph G and a vertex $x \in V(G)$, the graph G_x^* is the graph on the same vertices $V(G)$ obtained from the reduced graph \tilde{G}_x by adding an edge between any two vertices of any geodesic to x .*

See Figure 5.1 for a visualisation of \tilde{G}_x and G_x^* , starting from a graph G and a vertex x .

Lemma 5.4. *Given a graph G and a vertex $x \in V(G)$, G_x^* is a comparability graph.*




Figure 5.1: From left to right: a graph G with a vertex x , the graph \tilde{G}_x , and the graph G_x^* . The graphs G and \tilde{G}_x are drawn by placing the vertices at the same distance from x on a common horizontal level.

Proof. The partial order underlying the graph G_x^* consists of its vertices and, by definition, two vertices $u, v \in V(G_x^*)$ are such that $u < v$ if u and v are on the same geodesic to x and $d(u, x) < d(v, x)$. Since G_x^* has been built from \tilde{G}_x by adding an edge between every pair of vertices on each geodesic to x , then any two comparable vertices are adjacent and hence G_x^* is a comparability graph. ■

Lemma 5.5. *Given a graph G and a vertex $x \in V(G)$, S_x is an x -position set of G if and only if S_x is an x -position set for \tilde{G}_x . Then $p_x(G) = p_x(\tilde{G}_x)$.*

Proof. Note that any geodesic to x in G is also a geodesic to x in \tilde{G}_x . Then S_x is a x -position set for G if and only if there are no two vertices on the same geodesic to x in G , that is, if and only if there are no two vertices on the same geodesic to x in \tilde{G}_x . Hence, if and only if S_x is a x -position set for \tilde{G}_x . As consequence, any maximum vertex position set of G_x is a maximum vertex position set for \tilde{G}_x . Then $p_x(G) = p_x(\tilde{G}_x)$. ■

Given a graph G , let us denote the graph induced by vertices in $V(G) \setminus \{x\}$ as $G - x$.

Lemma 5.6. *Given a graph G and a vertex $x \in V(G)$, S_x is an x -position set of G if and only if S_x is an independent set of $G_x^* - x$. Then $p_x(G) = \alpha(G_x^* - x)$.*

Proof. Let S_x an x -position set in G . By Lemma 5.5, S_x is also a x -position set in \tilde{G}_x . Assume that S_x is not an independent set in $G_x^* - x$. Then there are two adjacent vertices $u, v \in V(G_x^* - x) \cap S_x$. By definition of G_x^* , u and v are on the same geodesic to x in \tilde{G}_x and then in G , a contradiction.


Assume now that S_x is an independent set of $G_x^* - x$. Let $u \in S_x$ and let P be any $u - x$ geodesic in G . Then it follows from the construction of G_x^* that u is adjacent to all the vertices of $V(P - u)$ in G_x^* . This immediately shows that $V(P) \cap S_x = \{u\}$. Consequently, S_x is a x -position set in G and hence $p_x(G) = \alpha(G_x^* - x)$. ■

Theorem 5.7. *Given a graph G and a vertex $x \in V(G)$, a maximum x -position set can be computed in $O(nm \log(n^2/m))$ time, where $n = |V(G_x^*)|$ and $m = |E(G_x^*)|$.*

Proof. Algorithm A in Figure 5.2 compute the distances of each vertex $v \in V(G)$ from x at Line 1. This requires $O(n + m)$ time. With the loop at Line 2, \tilde{G}_x is computed from G by removing edges between vertices at the same distance from x . This requires $O(m)$ time. The loop at Line 5 add edges to the graph in order to build G_x^* . This requires $O(n^2 + nm)$ time since Lines from 6 to 14 codifies for a breadth-first visit of the vertices on a geodesic to x passing through a vertex u . This visit, based on a queue Q and a set R of the visited vertices, requires $O(n + m)$ time and since it is repeated for each vertex u in $V(G - x)$, the total time is $O(n^2 + nm)$. Finally, at Line 15 an independent set S of the resulting comparability graph $G^* - x$ is computed. According to [12], the computation of an independent set for a comparability graph requires $O(nm \log(n^2/m))$. The last step determines the computational time of the whole algorithm. By Lemma 5.6, the set S is also a x -position set of G , then Algorithm A correctly returns S and its order. ■

Corollary 5.8. *Given a graph G , $\text{vp}^-(G)$ and $\text{vp}(G)$ can be computed in $O(n^4 \log(n))$ time, where $n = |V(G)|$.*

Proof. Given a graph G , by calling Algorithm A for each vertex x of G , $\text{vp}^-(G)$ and $\text{vp}(G)$ can be easily computed. Since by Theorem 5.7 each call



requires $O(nm \log(n^2/m))$, where $n = |V(G_x^*)|$ and $m = |E(G_x^*)|$. Considering that $n = |V(G_x^*)| = |V(G)|$ and $m = O(n^2)$, each call requires $O(n^3 \log(n))$ time, for a total of $O(n^4 \log(n))$ time. ■

Acknowledgements

The fourth author gratefully acknowledges funding support from EPSRC grant EP/W522338/1 and London Mathematical Society grant ECF-2021-27.

References

- [1] Anand B.S., Chandran, S.V.U., Changat, M., Klavžar, S. & Thomas, E.J., *Characterization of general position sets and its applications to cographs and bipartite graphs*. Appl. Math. Comput. 359 (2019), 84-89.
- [2] Apostol, T., *Introduction to Analytic Number Theory*. Springer-Verlag (1976).
- [3] Boltjansky, V. & Gohberg, I., *Results and problems in combinatorial geometry*. Cambridge University Press (1985).
- [4] Buckley, F. & Harary, F., *Distance in Graphs*. Addison-Wesley, Redwood City, CA (1990).
- [5] Chandran, S.V.U. & Parthasarathy, G.J., *The geodesic irredundant sets in graphs*. Int. J. Math. Combin. 4 (2016), 135-143.
- [6] Chartrand, G. & Zhang, P., *Introduction to Graph Theory*. Tata McGraw-Hill Edition, New Delhi (2006).
- [7] Di Stefano, G., *Mutual visibility in graphs*. Appl. Math. Comput. 419 (2022), 126850.
- [8] Dudeney, H.E., *Amusements in Mathematics*. Nelson, Edinburgh (1917).
- [9] Erdős, P., Gruber, P.M. & Hammer, J., *Lattice Points*. Harlow: Longman scientific & technical (1989).
- [10] Froese, V., Kanj, I., Nichterlein, A. & Niedermeier, R., *Finding points in general position*. Internat. J. Comput. Geom. Appl. 27 (2017), 277-296.
- [11] Ghorbani, M., Maimani, H.R., Mahid, F.R., Momeni, M., Klavžar, S. & Rus, G., *The general position problem on Kneser graphs and on some graph operations*. Discuss. Math. Graph Theory 41 (2021), 1199-1213.
- [12] Golumbic, M.C., *Algorithmic Graph Theory and Perfect Graphs*, Academic Press, New York (1980)

- [13] Hammer, J., *Unsolved Problems Concerning Lattice Points* Research Notes in Mathematics, Pitman (1977).
- [14] Hardy, G.H. & Wright, E.M., *An Introduction to the Theory of Numbers*. Oxford University Press (2008).
- [15] Manuel, P. & Klavžar, S., *A general position problem in graph theory*. Bull. Aust. Math. Soc. 98 (2018), 177-187.
- [16] Manuel, P. & Klavžar, S., *The graph theory general position problem on some interconnection networks*. Fundam. Inform. 163 (4) (2018), 339-350.
- [17] Payne, M. & Wood, D.R., *On the general position subset selection problem*. SIAM J. Discrete Math. 27 (2013), 1727-1733.
- [18] O'Rourke, J., *Art Gallery Theorems and Algorithms*. International Series of Monographs on Computer Science, Oxford University Press (1987).
- [19] Sylvester, J.J. *Sur le nombre de fractions ordinaires inégales qu'on peut exprimer en se servant de chiffres qui n'excèdent pas un nombre donné*. CR Acad. Sci. Paris 96 (1883), 409-413.
- [20] Thomas, E.J. & Chandran, S.V.U., *Characterization of classes of graphs with large general position number*. AKCE Int. J. Graphs Comb. (2020), 1-5.