

Demonstration of a high-volume tunable axion haloscope above 7 GHz

Taj A. Dyson,¹ Chelsea L. Bartram,² Ashley Davidson,¹ Jonah B. Ezekiel,¹ Laura M. Futamura,¹ Tongtian Liu,¹ and Chao-Lin Kuo^{1,2}

¹Stanford University, Stanford, CA 94305, USA

²SLAC National Accelerator Laboratory, 2575 Sand Hill Road, Menlo Park, CA 94025, USA

(Dated: February 15, 2024)

We present results from the first experimental demonstration of a tunable thin-shell axion haloscope. This novel geometry decouples the overall volume of the cavity-based resonator from its resonant frequency, thereby evading the steep sensitivity degradation at high-frequencies. An aluminum 2.6 L ($41 \lambda^3$) prototype which tunes from 7.1 to 8.0 GHz was fabricated and characterized at room temperature. An axion-sensitive, straightforwardly tunable TM_{010} mode is clearly identified with a room temperature quality factor, Q , of $\sim 5,000$. The on-resonance E -field distribution is mapped and found to agree with numerical calculations. Anticipating future cryogenic operation, we develop an alignment protocol relying only on rf measurements of the cavity, maintaining a form factor of 0.57 across the full tuning range. These measurements demonstrate the feasibility of cavity-based haloscopes with operating volume $V \gg \lambda^3$. We discuss plans for future development and the parameters required for a thin-shell haloscope exploring the post-inflationary axion parameter space (~ 4 to ~ 30 GHz) at DFSZ sensitivity.

I. INTRODUCTION

A range of astrophysical and cosmological observations point to the existence of dark matter (DM), but the particles of which it consists have remained elusive [1–4]. One of the most promising candidates for DM is the axion [5–7], which also solves the long-standing strong CP problem in particle physics [8–10].

A well-established type of axion search experiment is the *haloscope*, which consists of a resonating cavity immersed in a strong magnetic field [11–14]. The magnetic field interacts with putative ambient axions with coupling constant $g_{a\gamma\gamma}$, converting them into a weak photon signal (e.g., [15]). This signal resonantly drives the cavity at a frequency equal (in natural units) to the axion’s mass, an unknown parameter. In this letter, we report an experimental validation of a novel axion haloscope design that can extend axion sensitivity to frequencies above ~ 4 GHz.

The axion parameter space is scanned by tuning the resonant frequency f_0 of the haloscope. Integrating for longer at a certain f_0 tightens the upper bound on the coupling constant $g_{a\gamma\gamma}$ for DM of mass $m_{\text{DM}} = hf_0/c^2$. The rate at which a haloscope can scan across m_{DM} while reaching a given upper bound on the coupling is known as its scan rate, R . Considering only properties of the haloscope’s resonator,

$$R \propto V^2 C^2 Q, \quad (1)$$

where V is the resonator’s volume, Q is its quality factor, and C is the form factor of the axion-sensitive resonating mode, defined as

$$C = \frac{|\int dV \mathbf{E} \cdot \mathbf{B}|^2}{B^2 V \int dV |\mathbf{E}|^2} = \frac{|\int dV E_z|^2}{V \int dV |\mathbf{E}|^2}, \quad (2)$$

where \mathbf{B} is the external magnetic field and \mathbf{E} is the electric field of the mode. The second equality in Eq. 2

holds for cavities placed in a solenoid where $\mathbf{B} = B\hat{z}$, so $\mathbf{E} \cdot \mathbf{B} = E_z B$ and B is uniform. The mode most sensitive to axions is that with \mathbf{E} aligned with \mathbf{B} and with wavelength such that one half-cycle occupies the entire cavity. At frequencies around 1 GHz, haloscopes based on cylindrical cavities [12, 14] have reached sensitivity to Dine-Fischler-Srednicki-Zhitnitsky (DFSZ) models [16, 17]. However, the active volume of a proportionally scaled cylindrical haloscope decreases rapidly as f_0 increases. Since the scan rate R scales as V^{-2} , it becomes prohibitive to cover the frequency range predicted for post-inflationary axion scenarios ($\gtrsim 4$ GHz) [5, 18–21] down to the DFSZ limits.

In this work, we perform the first characterization of a prototype cavity implementing geometry proposed in [22] and [23] that alleviates the steep scaling of volume with frequency. Importantly, we show that the efficiency loss due to mode crossing in such an overmoded cavity is modest over a large frequency range. An overview of the novel geometry is presented in Sec. II. Details on the characterization of the prototype are given in Secs. III A, III B, and III C, and results are presented in Sec. III D. Finally, we discuss expansions to the design and the prospects for this high-frequency haloscope in Sec. IV.

II. THE THIN-SHELL GEOMETRY

It is possible to decouple the scan rate R from f_0 by departing from the conventional cavity geometry. Reference [23] provides a prescription to create *tunable* volume-filling thin-shell cavities with uniformly polarized eigenmodes. The simplest implementation of such a design consists of a rectangular wedge surrounded by a mechanically separate shell, shown in Fig. 1, where the coordinates used throughout this paper are also defined.

In the resulting cavity (a thin shell of vacuum space), standing waves in the X direction create a spatially uni-




FIG. 1: A cross-section through the center of the essential haloscope geometry, with the coordinate system used throughout this paper shown. The Z axis points vertically and the Y axis lies along the long edge of the wedge, with origin at the center of the wedge.

form Z-polarized mode that maximizes C . In keeping with the terminology from cylindrical resonators, we call this the TM_{010} mode. Its resonant frequency f_{010} is set by the gap width. The volume, on the other hand, can be scaled up by increasing the other dimensions to the size of the magnet bore without affecting f_{010} .

The cavity is tuned by moving the shell vertically along the wedge. Because the wedge and inner shell walls are tilted, such motion changes the width of the gap between them, thus tuning the TM_{010} mode. Note that the wedge must be longer than the shell to allow tuning. The shell also has corrugated end caps, thus reducing radiative losses and improving Q [22]. As described in the reference, these corrugations are $\lambda/4$ deep and confine the fields to within the cavity. Note that for the TM_{010} mode to be supported with appreciable C , the two parts of the resonator must be sufficiently well aligned.

III. THE PROTOTYPE CAVITY

A. Experimental setup

An aluminum resonator with the geometry discussed in Sec. II was constructed and studied. The wedge measures 40 cm tall, and the shell is 24 cm tall by 24 cm wide and 7 cm deep. The shell consists of six flat plates and was assembled using precision parallels for alignment and spacing. Both the wedge and the inner surfaces of the shell were lapped down to a maximum deviation from the plane of $10 \mu\text{m}$ to improve Q . The surface flatness is verified using a capacitive displacement sensor from




FIG. 2: Mode map showing the tuning range of the prototype cavity explored in this study. Each row is an S11 sweep at a given shell Z position. The measured resonant modes are visible as bright lines (the vertical ripples are known VNA artifacts). The axion-sensitive TM_{010} mode has the lowest frequency, and tunes uniformly from 7.1 GHz to 8 GHz. The wedge was aligned every 0.4 mm (3.9 MHz) using the procedure detailed in Sec. III C.

Micro-Epsilon.

The rectangular wedge is mounted vertically on a Newport Hexapod (HXP100V6-MECA) six-axis positioner. The shell is mounted to a single-axis positioner colinear with the Z axis. Both positioners are mounted on a leveled, low-vibration optical table. The resonator was designed to tune from 6.8 to 8.3 GHz. However, the maximum travel of the Z-axis positioner is 10 cm, which limits the tuning range.

The rf response of the haloscope is probed with a 6.8 cm copper antenna mounted on an SMA feedthrough to the shell at the top on the $-Y$ side of the cavity. Cavity resonances are probed via reflection measurement of this antenna using a commercial vector network analyzer (VNA). The antenna is weakly coupled to the cavity ($\beta \approx 0.1$), probing the unloaded Q of the resonator.

B. Mode identification

A simple alignment using caliper measurements was sufficient to produce a resonance with the expected tuning properties. The observed frequency is 15.2 MHz lower than predicted (0.2%), likely due to imperfect cavity construction. We proceed to verify that the detected mode is indeed the axion-sensitive TM_{010} mode against the background of spurious modes (see Fig. 2) by comparing its properties to those calculated using finite element analysis (FEA) by COMSOL-RF using two methods.

First, we measure the spatial distribution of the electric field inside the cavity using the “bead perturbation”




FIG. 3: The first column shows the TM_{010} mode mapped with a dielectric disk (top) and using eigenfrequency FEA using COMSOL-RF (bottom). The second column shows the same for the TM_{110} mode. The measured and simulated plots use independent $|E|$ scales. For details on the field mapping procedure, see the main text Sec. III B. The agreement between the measured and simulated field maps aids in identifying the TM_{010} mode.

technique [24]. When a dielectric probe is placed in a resonating cavity, the frequency of each mode shifts proportionally to the square of the electric field of that mode in the probe’s location. In our experiment, the probes are Zotefoam HD30 disks, 19 mm in diameter and 14.3 mm thick. The choice of a larger probe with a low dielectric constant (over a more conventional probe consisting of a small bead with high ϵ) is motivated by the large survey volume and the low spatial resolution required. Maps of $|E|$ within the cavity were produced by placing the probe at 25 evenly spaced points in each of the front (+X) and rear (-X) half of the cavity. The first row of Fig. 3 shows the front field maps of the modes with the lowest and second lowest frequency, while the bottom row shows the matching field maps produced by FEA, that of the TM_{010} and TM_{110} modes.

Next, we corroborated these results by observing the responses of the modes’ resonant frequencies to induced wedge misalignment. To do so, reflection measurements of the cavity were taken for several wedge positions along the X-axis, shown in Fig. 4. In this figure, the resonant frequency given by FEA for the lowest three modes at several X positions is overplotted in white, uniformly shifted by 15.23 MHz to match the TM_{010} mode’s frequency to the reflection measurements. We observe excellent agreements between the measured and simulated responses to misalignment for the first three resonances.

A feature of note in Fig. 4 is the avoided crossing be-




FIG. 4: Mode map showing the effects of misaligning the wedge in the X direction. Each row is an S_{11} sweep at a given wedge position. The measured resonant modes are visible as curved bright lines (the vertical bars are known VNA calibration artifacts). The resonant frequencies given by FEA, shifted down by 15.23 MHz, are overplotted as white points.

tween the two lowest modes. This behavior is consistent with the expectation of two coupled harmonic oscillators – the front (+X) and rear (-X) halves of the cavity. Furthermore, the next-lowest mode disappears when the wedge is aligned. This is expected because this mode corresponds to the anti-symmetric hybridization of the two halves. Since the antenna probe is located at the node, the coupling vanishes when the wedge is centered.

We have thus associated the physical modes in the cavity with those simulated in FEA and confirmed that the axion-sensitive mode is supported in the cavity.

C. Cavity alignment using rf measurements

Precision alignment of the wedge to the shell is important for optimal C for the TM_{010} mode. The simulated effects of wedge misalignment on C are shown in the left panel of Fig. 5, while the right panel shows the effects of those same misalignments on C and f_{010} together. When the wedge is misaligned, and C is thus decreased, some part of the cavity must widen, driving f_{010} lower. This can also be seen in Fig. 4: the aligned position has the highest f_{010} . Since f_{010} decreases monotonically with C , aligning the wedge by maximizing f_{010} will also maximize C . This correspondence enables alignment without measurements beyond the usual rf characterization of the cavity, which is indispensable in cryogenic environments where other measurements are impractical.

We developed an automated alignment algorithm to maximize f_{010} (and thus C) as a function of wedge position in each direction except Z (the tuning direction),




FIG. 5: The left panel shows C as predicted by FEA as a function of wedge misalignment along each non-tuning axis. The right panel shows the effects of those same misalignments on C as well as f_{010} , showing that they decrease together as misalignment becomes more extreme in any direction. In the left panel, dashed lines use the bottom position scale, solids use the top. Misalignment in the X, V, or W direction degrades C significantly, while the effects of misalignment in the Y or U directions are negligible.




FIG. 6: Position of the wedge as a function of NM iteration for a representative automatic alignment of the resonator. Dashed lines use the left axis, solid lines use the right axis.

including rotations. Given a position, the 6-axis hexapod places the wedge there. Then, an rf reflection measurement of the cavity with a VNA produces the cavity spectrum, from which f_{010} can be extracted. The above process is iterated, optimizing for maximum f_{010} , until the optimization algorithm converges. A standard Nelder-Mead (NM) optimization algorithm was chosen to minimize the 5-dimensional function. The optimization is set to converge when all vertices of the parameter simplex are separated by no more than $1 \mu\text{m}$ for the linear dimensions and 3.6 arcseconds for the angular dimensions. As can be seen in Fig. 4, there are no false local maxima near the aligned position. The wedge’s position during a representative alignment can be seen in Fig. 6. Each function evaluation takes ~ 1 s, and each alignment requires ~ 50 evaluations (~ 25 NM iterations). The suc-

Axis	X (μm)	Y (μm)	U (arcmin)	V (arcmin)	W (arcmin)
σ_x	2	10	0.4	0.2	0.1

TABLE I: Standard deviation of aligned position along each wedge axis from 100 NM alignments.

cessful implementation of the automated alignment was crucial in obtaining the data shown in Fig. 2, a key result of this letter.

The error on the aligned position of the wedge is estimated by aligning it 100 times, starting from uniformly random wedge positions. The error on the alignment position in each direction is then taken to be the standard deviation of the final aligned positions, and are recorded in Table I.

D. Haloscope figures of merit

Here we summarize the cavity’s relevant parameters for use as a haloscope, taking into account the alignment technique discussed above.

Since C requires information about the direction of \mathbf{E} inside the cavity, it cannot be measured directly. Instead, we calculate it from the FEA, which predicts that the fully aligned cavity has $C = 0.57$. The positioning error of the wedge around the aligned position after alignment (Table I) results in negligible degradation of C , see Fig. 5, left panel.

The cavity tunes linearly from 7.10 to 8.02 GHz, with no observed mode crossings (see Fig. 2). Alignments were performed every 0.4 mm to keep $C > 0.55$ throughout. Over this tuning range, four hours were spent on alignment, which is small compared to the expected data collection time during a future axion search. The demonstrated tuning range of 12% is smaller than the design range of 20% due to limitations in the mechanical setup and the coupling strength with the given antenna probe.

At room temperature, the aluminum cavity’s TM_{010} mode has a median Q of $4,700$ throughout the full tuning range shown in Fig. 2. FEA indicates that plating the cavity with copper and cooling to 100 mK will increase Q to $20,000$, as radiative loss through the top and bottom gaps starts to become important.

The cavity has volume $V = 2.59$ L, or $41 \lambda^3$, at 7.5 GHz. For a comparison with other experiments targeting a similar frequency range, see Table II.

IV. DISCUSSION

The axion scan rate R can be further improved by copper-plating, cooling the haloscope to cryogenic temperatures, and stacking multiple wedge cavities (in the X direction) to form a larger volume. In the multi-wedge design, the

Experiment	f_0 (GHz)	V/λ^3	$C^2V^2Q_L$ (L ²)
This work (cryogenic)	7.5	41	15,000
HAYSTAC [25]	4.7	6.0	2,600
CAPP quad-cell [26]	5.89	8.2	3,100
HAYSTAC 7-rod [27]	6.5	17	5,800
QUAX [28]	10.35	44	1,200
GigaBREAD [29]	11.6	390	110
ORGAN [30]	26.5	11	0.23

TABLE II: Comparison between this work and experiments targeting a similar frequency range. In cases where only Q_0 was reported (this work, HAYSTAC 7-rod, and CAPP quad-cell), cavity coupling $\beta = 2$ is assumed with $Q_L = Q_0/(\beta + 1)$. GigaBREAD is a dish antenna, so equivalent $V = A\lambda/2$ where A is its area, and for comparison C and Q_L are each taken to be 1. The Q_L quoted for this work is derived from the simulated Q_0 for cryogenic copper of 20,000.

sub-cavities are left open to each other, so a single axion-sensitive mode occupies the entire space.

Efforts are being made to develop a meter-scale cavity for cryogenic operations to verify the expected improvements to Q at low temperatures and tackle challenges relating to cryogenic positional control of the wedge. A three-wedge prototype is being developed to demonstrate the alignment of all wedges simultaneously. Additionally, an antenna scheme capable of coupling more strongly ($\beta \approx 1$ to 2) to thin-shell cavities is under development. We baseline a science-grade 5–8 GHz haloscope on a copper-plated three-wedge design.




FIG. 7: Discovery potential of thin-shell haloscopes. The green-shaded region is the post-inflationary axion mass range predicted by [19]. A modest projection is in dark blue, reaching KSVZ sensitivity from 5-8 GHz, and a futuristic projection is in light blue, reaching DFSZ sensitivity from 5-30 GHz. Details of the parameters used are in the main text, Sec. IV. The software used to produce this figure is adapted from [31].

The discovery potential of such a cavity is shown in Fig. 7, along with existing haloscopes' exclusions and the Kim-Shifman-Vainshtein-Zakharov (KSVZ) [32, 33] and DFSZ [16, 17] limits. In the following description, the frequency-dependent values Q and V are quoted at a fiducial frequency $f_{\text{fid}} = 5$ GHz, and Q scales as $Q = Q_{\text{fid}}(f_{\text{fid}}/f)^2$ while V scales according to the geometry of the cavity. The dark blue region is the parameter space excluded by an optimally coupled ($\beta = 2$ [34]) three-wedge cavity, scaled to fit in a 1 m solenoid with a 0.6 m inner bore ($V = 48$ L) obtaining $C = 0.57$ and $Q = 20,000$, cooled to 100 mK with a 300 mK first-stage amplifier (such as a Josephson parametric amplifier), immersed in an 8 T magnetic field, with 2 months of data collection time. The light blue region is a futuristic haloscope making use of a larger 10 T solenoid that is 2 m in length with a 0.8 m inner bore, containing a $V = 116$ L cavity achieving $Q = 100,000$ (again with $C = 0.57$ and cooled to 100 mK), using an amplifier with added noise at 1/2 of the standard quantum limit (achievable through squeezing [25]), and 3.5 years of data collection time.

V. CONCLUSION

In this paper, we characterized a prototype thin-shell resonator, as proposed in [22, 23], and found that it supports an axion-sensitive mode with appreciable form factor C and Q while achieving a V/λ^3 many times that of other experiments targeting a similar frequency range (see Table II). Furthermore, the resonator is tunable from 7.1-8 GHz via single-axis motion. The resonator consists of a thin shell of vacuum space in between a central wedge and its surrounding shell (see Fig. 1), and its C is maximized when those two pieces are aligned. An automated alignment procedure was developed using only rf measurements of the mode and requiring only a modest amount of time to complete.

The prototype characterization demonstrates that the thin-shell haloscope design can have an operating volume $V/\lambda^3 \gg 1$ while retaining many desirable features of the successful cavity haloscope programs: mechanically robust high- Q resonators, geometry compatible with a solenoid magnet, and a simple antenna readout. The wide frequency range covered shows that any efficiency loss due to mode crossing in such an overmoded cavity will be modest. Since for a haloscope $R \propto V^2$, the thin-shell cavity is a very promising approach to cover the important post-inflationary axion mass region. Compared to other innovative proposals to cover this range [35, 36], a straightforward extension to this successful prototype is a particularly low-risk approach that should be considered seriously. Forecasts on the discovery potential of thin-shell haloscopes, both in the near and long term, are shown in Fig. 7.

ACKNOWLEDGEMENTS

This material is based upon work supported by the National Science Foundation under Grant No. 2209576 and a KIPAC Innovation Award. We acknowledge the support of the Natural Sciences and Engineering Research Council of Canada (NSERC), 521528828. Chelsea

Bartram and simulations and data acquisition advising were supported by the Department of Energy, Laboratory Directed Research and Development program at SLAC National Accelerator Laboratory, under contract DE-AC02-76SF00515 and as part of the Panofsky Fellowship awarded to Chelsea Bartram.

-
- [1] V. C. Rubin and J. Ford, W. Kent, Rotation of the Andromeda Nebula from a Spectroscopic Survey of Emission Regions, *Astrophys. J.* **159**, 379 (1970).
- [2] N. Aghanim *et al.* (Planck), Planck 2018 results. VI. Cosmological parameters, *Astron. Astrophys.* **641**, A6 (2020), [Erratum: *Astron. Astrophys.* 652, C4 (2021)], arXiv:1807.06209 [astro-ph.CO].
- [3] G. Bertone, D. Hooper, and J. Silk, Particle dark matter: evidence, candidates and constraints, *Physics Reports* **405**, 279 (2005).
- [4] D. Clowe *et al.*, A direct empirical proof of the existence of dark matter, *The Astrophysical Journal* **648**, L109 (2006).
- [5] L. F. Abbott and P. Sikivie, A cosmological bound on the invisible axion, *Physics Letters B* **120**, 133 (1983).
- [6] J. Preskill, M. B. Wise, and F. Wilczek, Cosmology of the invisible axion, *Physics Letters B* **120**, 127 (1983).
- [7] M. Dine and W. Fischler, The not-so-harmless axion, *Physics Letters B* **120**, 137 (1983).
- [8] R. D. Peccei and H. R. Quinn, CP conservation in the presence of pseudoparticles, *Phys. Rev. Lett.* **38**, 1440 (1977).
- [9] F. Wilczek, Problem of strong p and t invariance in the presence of instantons, *Phys. Rev. Lett.* **40**, 279 (1978).
- [10] S. Weinberg, A new light boson?, *Phys. Rev. Lett.* **40**, 223 (1978).
- [11] P. Sikivie, Experimental tests of the “invisible” axion, *Phys. Rev. Lett.* **51**, 1415 (1983).
- [12] C. Bartram *et al.* (ADMX), Search for Invisible Axion Dark Matter in the 3.3–4.2 μeV Mass Range, *Phys. Rev. Lett.* **127**, 261803 (2021), arXiv:2110.06096 [hep-ex].
- [13] K. M. Backes *et al.* (HAYSTAC), A quantum enhanced search for dark matter axions, *Nature* **590**, 238 (2021), arXiv:2008.01853 [quant-ph].
- [14] A. K. Yi *et al.* (CAPP), Axion dark matter search around 4.55 μeV with dine-fischler-srednicki-zhitnitskii sensitivity, *Phys. Rev. Lett.* **130**, 071002 (2023).
- [15] D. J. Marsh, Axion cosmology, *Physics Reports* **643**, 1 (2016), axion cosmology.
- [16] M. Dine, W. Fischler, and M. Srednicki, A simple solution to the strong cp problem with a harmless axion, *Physics Letters B* **104**, 199 (1981).
- [17] A. R. Zhitnitsky, On Possible Suppression of the Axion Hadron Interactions. (In Russian), *Sov. J. Nucl. Phys.* **31**, 260 (1980).
- [18] S. Borsanyi *et al.*, Calculation of the axion mass based on high-temperature lattice quantum chromodynamics, *Nature* **539**, 69 (2016).
- [19] M. Buschmann *et al.*, Dark matter from axion strings with adaptive mesh refinement, *Nature Communications* **13**, 1049 (2022).
- [20] V. B. Klaer and G. D. Moore, The dark-matter axion mass, *Journal of Cosmology and Astroparticle Physics* **11**, 049.
- [21] M. Kawasaki, K. Saikawa, and T. Sekiguchi, Axion dark matter from topological defects, *Phys. Rev. D* **91**, 065014 (2015).
- [22] C.-L. Kuo, Large-volume centimeter-wave cavities for axion searches, *Journal of Cosmology and Astroparticle Physics* **2020** (06), 010.
- [23] C.-L. Kuo, Symmetrically tuned large-volume conic shell-cavities for axion searches, *Journal of Cosmology and Astroparticle Physics* **2021** (02), 018.
- [24] J. Maier, L. C. and J. C. Slater, Field Strength Measurements in Resonant Cavities, *Journal of Applied Physics* **23**, 68 (1952).
- [25] M. J. Jewell *et al.* (HAYSTAC), New results from HAYSTAC’s phase II operation with a squeezed state receiver, *Phys. Rev. D* **107**, 072007 (2023), arXiv:2301.09721 [hep-ex].
- [26] J. Jeong *et al.*, Concept of multiple-cell cavity for axion dark matter search, *Physics Letters B* **777**, 412 (2018).
- [27] M. Simanovskaia *et al.*, A symmetric multi-rod tunable microwave cavity for a microwave cavity dark matter axion search, *Review of Scientific Instruments* **92**, 033305 (2021), arXiv:2006.01248 [astro-ph.IM].
- [28] R. Di Vora *et al.*, High- Q microwave dielectric resonator for axion dark-matter haloscopes, *Phys. Rev. Appl.* **17**, 054013 (2022).
- [29] S. Knirck *et al.*, First Results from a Broadband Search for Dark Photon Dark Matter in the 44 to 52 μeV range with a coaxial dish antenna, arXiv e-prints (2023), arXiv:2310.13891 [hep-ex].
- [30] A. Quiskamp *et al.*, Exclusion of axionlike-particle co-generation dark matter in a mass window above 100 μeV , *Phys. Rev. Lett.* **132**, 031601 (2024).
- [31] C. O’Hare, cajohare/axionlimits: Axionlimits (2020).
- [32] J. E. Kim, Weak-interaction singlet and strong CP invariance, *Phys. Rev. Lett.* **43**, 103 (1979).
- [33] M. Shifman, A. Vainshtein, and V. Zakharov, Can confinement ensure natural cp invariance of strong interactions?, *Nuclear Physics B* **166**, 493 (1980).
- [34] S. Al Kenany *et al.* (HAYSTAC), Design and operational experience of a microwave cavity axion detector for the 20–100 μeV range, *Nuclear Instruments and Methods in Physics Research Section A: Accelerators, Spectrometers, Detectors and Associated Equipment* **854**, 11 (2017).
- [35] S. Beurthey *et al.* (MADMAX Working Group), MADMAX Status Report, arXiv e-print (2020), arXiv:2003.10894 [physics.ins-det].
- [36] A. J. Millar *et al.* (Endorsers), Searching for dark matter with plasma haloscopes, *Phys. Rev. D* **107**, 055013 (2023).