

Towards the understanding of heavy quarks hadronization: from leptonic to heavy-ion collisions

J. Altmann,^{1,2,*} A. Dubla,^{3,†} V. Greco,^{4,‡} A. Rossi,^{5,§} and P. Skands^{1,2,¶}

¹*School of Physics and Astronomy,
Monash University, Melbourne, Australia*

²*Rudolf Peierls Centre for Theoretical Physics, University of Oxford, UK*

³*GSI Helmholtzzentrum für Schwerionenforschung, 64291 Darmstadt, Germany*

⁴*Department of Physics and Astronomy,
University of Catania and INFN-LNS, Catania, Italy*

⁵*Università di Padova and INFN - Sezione di Padova, Padova, Italy*

(Dated: June 17, 2024)

Abstract

The formation of hadrons is a fundamental process in nature that can be investigated at particle colliders. As several recent findings demonstrate, with e^+e^- collisions as a "vacuum-like" reference at one extreme, and central nucleus–nucleus as a dense, extended-size system characterized by flow and local equilibrium at the opposite extreme, different collision systems offer a lever arm that can be exploited to probe with a range of heavy-flavour hadron species the onset of various hadronization processes. In this review, we present an overview of the theoretical and experimental developments. The focus is on open-heavy-flavour measurements. The comparison with model predictions and connections among the results in electron-positron, proton–proton, proton–nucleus, nucleus–nucleus collisions are discussed. After reviewing the current state, we suggest some prospects and future developments.

* javira.altmann@monash.edu

† a.dubla@cern.ch

‡ greco@lns.infn.it

§ a.rossi@cern.ch

¶ peter.skands@monash.edu

CONTENTS

I. Introduction	3
II. Models of hadronization in high-energy collisions	7
A. Baseline MC Models	7
1. String model – PYTHIA	8
2. Cluster model – HERWIG	12
B. Enhancing charm and beauty baryon yields	13
1. Extensions to the default (Monash 2013) PYTHIA tune	14
2. Colour reconnections in HERWIG	19
3. Statistical hadronization with additional baryon resonances	20
4. Hadronization via coalescence	22
5. EPOS4(HQ)	31
III. Heavy-flavour hadronization - experimental results	33
A. Production in ee and ep collisions and spectroscopy	34
B. Hadronic collisions: beam remnants and quantum-number conservation	40
C. Proton–proton collisions	41
D. Measurements as a function of multiplicity	56
E. Proton–nucleus collisions	62
F. Nucleus–nucleus collisions	66
IV. Prospects and future developments	75
Acknowledgements	93
References	94

I. INTRODUCTION

Hadronization is a fundamental process in nature representing the transition of a system of quarks and gluons to a state in which the degrees of freedom are colour-neutral quark-composite particles, namely hadrons. In the Early Universe, hadronization is supposed to have taken place about $10 - 20 \mu\text{s}$ after the Big Bang [1, 2]. A prominent feature of strong interaction is “colour confinement”, the phenomenon preventing the isolation and direct observation of free colour charges, i.e. of unbound quarks and gluons, in conditions of temperature and energy density typical of ordinary matter. However, particle accelerators make hadronization accessible in laboratory: in high-energy collisions of hadrons or leptons, quarks and gluons represent (for a very short time of the order of few fm/c) the system degrees of freedom. The details of the hadronization process influence the subsequent hadroproduction, the multiplicities of particles produced, the relative abundances of different hadron species, and the hadron kinematics.

Quantum Chromodynamics (QCD) is the theory of strong interactions within the Standard Model of Particle Physics. In QCD, colour-charge confinement appears in the static colour potential of a quark-antiquark pair as the presence of a term increasing linearly with distance and dominating the QCD potential at large distances. One of the fundamental properties of QCD is that the coupling constant, α_s , reduces with increasing squared 4-momentum transfer (Q^2), i.e. for short-distance interactions. Hadronization involves partonic processes characterized by small momentum transfers (i.e. $\approx \Lambda_{QCD} \sim R_H^{-1}$) and hence large values of the strong coupling constant, such that perturbative QCD calculations are not conceivable. Therefore, event generators which model parton production and the subsequent hadronization process event-by-event or (semi-)phenomenological models aimed at reproducing single-particle specific observables are used to infer various features of hadron formation and of its dependence on the properties of the collision system. In any kind of high-energy collision, from e^+e^- to nucleus–nucleus, modelling hadron production starting from the partonic stage requires a colour neutralization procedure that groups the quarks and gluons into colour-neutral objects, i.e. the final hadrons. In event generators, the quarks and gluons involved in this process can arise from the initial parton–parton scatterings, subsequent processes like parton-showers, and string-breaking. Other models assume the presence of a bulk of partons with given kinematic properties, without tracing their

history before hadronization.

The hadrons containing a charm or beauty quark (heavy-flavour hadrons), are always formed in the hadronization of a charm or beauty quark produced in initial hard-scatterings prior to hadronization, in which contrary to the soft interactions occurring at hadronization time, large Q^2 ($Q^2 > (2m_{c,b})^2$) are possible. The hadronization process determines the relative abundances of the different heavy-flavour hadron species and the hadron kinematics, but contrary to what occurs for light-flavour hadrons, the hadronization process itself generally does not influence the total heavy-flavour hadron production which instead matches the production rate of the parent heavy quarks. The large values of the charm and beauty quark masses ($m_{b,c} \gg \Lambda_{QCD}$) allow to employ perturbative QCD (pQCD) calculations of heavy-quark production down to zero momentum. For these reasons, heavy-flavour hadrons can be regarded as “calibrated” perturbative probes of the hadronization, which can provide unique information on this fundamental process, complementary to what can be inferred from studies of light-flavour production and of the event properties.

The transition of a heavy quark into a given hadron species requires the modelling of hadronization and of the soft non-perturbative processes involved. The simplest effective description of this transition, adopted in QCD calculations based on a factorization approach like FONLL [3, 4] and GM-VFNS [5–8], is to use fragmentation functions (FFunc). In the factorization approach, the transverse-momentum (p_T) and rapidity (y) differential heavy-flavour hadron production cross sections in proton–proton (pp) are computed as the convolution of three terms: (i) the parton distribution functions (PDFs) of the incoming (anti)protons, (ii) the partonic cross section, calculated as a perturbative series in powers of the strong coupling constant α_s , and (iii) the fragmentation functions, which parameterize the probability that a heavy-quark gives rise to a hadron of a given species carrying a given fraction (z_Q) of the parent quark momentum. Thus, FFunc allow to map the quark momentum-differential cross section into the final hadron momentum-differential cross section. The FFunc used in these pQCD calculations have been parameterized for decades from measurements performed in e^+e^- or ep collisions [9]. Charm and bottom quark production in e^+e^- annihilation offers the cleanest environment for constraining heavy-quark FFunc. However, the usage of FFunc parameterized on e^+e^- or ep data in pp collisions requires the assumption that FFunc are “universal”, independent of the colliding system. Under the universality assumption, once determined in a given collision system, like e^+e^- ,

FFunc can be applied to any reaction. An even more basic assumption, is the universality of fragmentation fractions (FF), which represent the probability that a heavy-quark produces a given heavy-flavour hadron species independently of z_Q , i.e. the z_Q integral of the FFunc. The modelling of hadronization in hadronic collisions with universal FFunc and FF relies on the hypothesis that, at large extent, the hadronization of a charm or beauty quark is not sensitive to the hard quark-production process and to the surrounding partonic environment in which hadronization occurs. In e^+e^- collisions the FF can be directly measured from the cross sections of the observed hadron species without the need of measuring all existing species, given that the heavy-quark production cross section can be calculated with high precision. Though practical limitations (e.g. kinematic reach of the measurements) may require extrapolation, this in principle allows the important check that the sum of FF of all observed weakly-decaying charm hadrons equals unity, thus the verification that all weakly decaying states are known. Though the universality assumptions are not a rigorous prediction of QCD and can be considered reasonable only within certain (quite vaguely defined) kinematic conditions, validating them has been an important goal of experimental measurements of heavy-flavour hadron production since the formulation of QCD and of the parton model. Hadron-to-hadron production cross section ratios are particularly sensitive to FFunc, FF, and in general, to heavy-flavour hadronization mechanisms, because the heavy-quark production cross-section, which depends on PDF and the hard-scattering process, substantially cancel in the ratios. The production of specific heavy-flavour hadron species has been measured in different energy regimes and “hadronic environments”: in e^+e^- collisions at LEP and B factories, in ep collisions, in proton-(anti)proton (pp/p \bar{p}) collisions, and in heavy-ion collisions (nucleus–nucleus, AA, or proton–nucleus, p–A). Before the Large Hadron Collider (LHC) era, the universality assumption had been tested mainly by comparing cross-section ratios of different D and B meson species in e^+e^- , $e^\pm p$, and pp (p \bar{p}) collisions, while data on baryon-to-meson cross-section ratios in hadronic collisions were not available or precise, and basically limited to Λ_c^+ and Λ_b^0 . The Λ_c^+/D ratios measured in $e^\pm p$ and e^+e^- collisions were consistent, thus supporting universality. Hadronization models developed in event generators, like the Lund string fragmentation model in PYTHIA [10, 11] or the cluster model in HERWIG [12], capable to reproduce several feature of e^+e^- data and pp data, were not expecting, in their standard implementation, significant differences in the hadron-species ratios from e^+e^- to pp collisions, also supporting the hypothesis that

modifications to the hadronization process could be small. On the contrary, the recent heavy-flavour baryon measurements in hadronic collisions at LHC energies indicated a significant difference in the fragmentation fractions of charm and beauty quarks into charm and beauty baryons compared to those measured in e^+e^- and ep collisions. In the beauty sector, the CDF experiment had found a difference in the Λ_b^0/B ratio in $p\bar{p}$ collisions at Tevatron with respect to LEP values [13]: at that time, however, the result was related to the different jet momenta involved in the two measurements (much higher at LEP) but not traced back to a breakdown of factorization, a modification of the hadronization process, or some other cause. The recent heavy-flavour baryon measurements in hadronic collisions challenge the assumption that heavy quark hadronization is a universal process across different colliding systems. The breaking of the universality can be related to higher-twist effects or other effects that make heavy-quark hadronization dependent on the underlying event.

In heavy-ion collisions, hadronization of heavy quarks (as well as that of light partons) can occur in a rather different way. In these collisions a colour-deconfined state of QCD matter is formed, the quark-gluon plasma (QGP) [14]. The heavy-quark hadronization process happens in a hot and dense environment with a large abundance of light coloured thermal particles nearby with which the heavy quark can recombine, neutralizing its colour charge. Accounting for this recombination process, very often modelled as a $2 \rightarrow 1$ (or $3 \rightarrow 1$ in the case of baryon formation) coalescence is a fundamental hadronization mechanism necessary to reproduce several experimental observations, like changes in baryon-to-meson ratios and the collective motion of final hadrons, which is associated with the expansion of the system, both in the light and the heavy-flavour sector. In heavy-ion collisions also other observables are sensitive to the hadronization processes, like the nuclear modification factor and the anisotropic flow coefficients. The nuclear modification factor (R_{AA}) is defined as the ratio of the yield measured in AA collisions to the pp cross section scaled by the average nuclear overlap function $\langle T_{AA} \rangle$ [15], a quantity proportional to the number of binary nucleon–nucleon collisions, for the considered centrality interval. In the absence of nuclear effects, $R_{AA} = 1$ is expected. The anisotropic flow coefficients are the Fourier coefficients (v_n) of the distribution of the heavy-flavour hadron azimuthal angle (ϕ) with respect to the reaction plane defined by the nuclei impact-parameter vector, which is the vector connecting the centres of the colliding nuclei, and the beam direction. The coefficient of the second-order harmonic (v_2) is called elliptic flow. It encodes the efficiency by which the hydrodynamic evolution of

the medium converts to momentum space the initial spatial azimuthal anisotropy of the fireball (and of the produced partons), which, in non-central collisions, principally arises from the non-zero eccentricity of the nuclei overlap region. The initial asymmetry gives rise to azimuthally anisotropic pressure gradients which drives the hydrodynamic expansion of the system.

In this review, we present an overview of the state-of-the-art of theoretical models and experimental measurements related to the characterization of heavy quark hadronization from e^+e^- to heavy-ion collisions. Theoretical models, including recent developments, are discussed in Sect. II. The experimental results are presented in Sect. III. The discrepancies between the measurements and theoretical predictions are discussed in detail. Finally, in Sect. IV we suggest new measurements and theoretical ideas that we consider important to achieve further progresses on the understanding of hadronization.

II. MODELS OF HADRONIZATION IN HIGH-ENERGY COLLISIONS

This section presents an overview of theoretical models for hadronization in high-energy collisions, with particular emphasis on aspects relevant to heavy-flavour hadron production in hadron-hadron and heavy-ion collisions. Table I shows a schematic overview of the available Monte Carlo generators and phenomenological models highlighting their main features. The check marks indicate whether a model has the potential to reproduce the indicated aspects and effects, regardless of how well the predictions match the existing data.

In section II A, we briefly summarize the foundations and basic aspects of the two main dynamical models of hadronization implemented in Monte Carlo (MC) event generators, the string and cluster models.

In section II B, we turn to the charm and beauty baryon sectors specifically, and consider both extensions to the baseline MC models as well as other key approaches like coalescence/recombination and thermal/statistical models.

A. Baseline MC Models

The explicit dynamical models that have been used for several decades to model the hadronization process in e^+e^- , ep, and pp collisions in Monte Carlo event generators, are the

TABLE I: Overview of hadronization models. The check marks indicate whether a model has the potential to reproduce the indicated aspects and effects, regardless of how well the predictions match the existing data.

	PYTHIA	PYTHIA ANGANTYR	HERWIG	EPOS	SHM	Coal- escence	POW- LANG
$e^+e^- \rightarrow$ hadrons	✓	✓	✓	✓	(✓) ⁷	✗	✗
pp (soft)	✓	✓	✓	✓	✓	✓	✓
pp (hard)	✓	✓	✓	(✓) ⁶	(✓) ⁸	✓	✓
pA	(✓) ¹	✓	✗	✓	(✓) ⁹	(✓) ⁹	(✓) ⁹
AA	(✓) ¹	✓	✗	✓	✓	✓	✓
Fully Exclusive Events	✓	✓	✓	✓	✗	✗	✗
Particle Yields	✓	✓	✓	✓	✓	✓	✓
Particle Spectra	✓	✓	✓	✓	✓	✓	✓
Charm baryon Enh.	(✓) ^{2,3}	(✓) ^{2,3}	(✓) ⁵	✓	(✓) ¹⁰	✓	✓
Strangeness Enh.	(✓) ³	(✓) ³	✗	✓	✓	✓	✓
Collective Flow	(✓) ⁴	(✓) ⁴	✗	✓	(✓) ¹¹	✓	✓

¹: Limited functionality, mainly intended for cosmic-ray cascades.

²: With the QCD Colour-Reconnection model.

³: With the Rope-Hadronization or Close-Packing models.

⁴: With the String-Shoving model.

⁵: With the Baryon Colour-Reconnection model.

⁶: In EPOS 4.

⁷: In some SHM approaches, but not in those discussed within this review for open heavy flavor.

⁸: Added as a contribution from independent fragmentation associated to a corona.

⁹: It can be done without modifying the approach, but it has not been published

¹⁰: Obtained by adding further states predicted by the relativistic quark model.

¹¹: Added coupling SHM to a blast wave with radial anisotropic flow.

string and cluster hadronization models. Below, we outline these as used in the PYTHIA [10, 16] and HERWIG [17] generators respectively.

1. String model – PYTHIA

Hadronization in PYTHIA [10, 16] is based on the semi-classical Lund string fragmentation model [18], and in PYTHIA it is mainly implemented to model hadronization from




FIG. 1: hadronization in the picture of string fragmentation. i) The initial q_0 and \bar{q}_0 begin to move apart. ii) The string begins to form between them. iii) A string break occurs, creating a new $q\bar{q}$ pair. iv) More string breaks occur. v) Jets of final-state hadrons from the fragmentation process.

e^+e^- up to pp collisions, with the relatively recent Angantyr extension allowing to study also heavy-ion collisions. In the Lund string model, the “string” represents the collapsed colour confinement field formed between a colour charge and anticolour charge in an overall singlet state (otherwise referred to as “colour-connected” partons). A key motivation for the modelling of the confinement field as a string is the linear potential — and therefore constant tension — observed at non-perturbative scales on the lattice and encapsulated by the QCD Cornell potential [19, 20]. Thus the string is defined by its characteristic constant string tension, $\kappa \sim 1$ GeV/fm, and can be modelled by the dynamics of a relativistic string [21].

In the context of high-energy collisions, colour-connected partons move apart from one another with high energies, stretching the string formed between them. Given sufficient energy, at some point it becomes energetically favourable to break the string rather than keep stretching it. At the site of the string break, a light-flavoured quark-antiquark (or diquark-antidiquark) pair is spontaneously pair produced, resulting in two smaller string systems. Note that in this context, light-flavoured refers to up, down and strange quarks. This string-breaking, or “fragmentation” process, occurs until there is no longer sufficient energy to keep breaking the string, resulting in on-shell final-state hadrons. A basic sketch of this fragmentation process can be seen in Fig. 1.

The string breaks are modelled via a quantum tunnelling process analogous to electron-positron pair production in the presence of a strong electric field described by the Schwinger mechanism [22]. The modified form of the Schwinger mechanism for QCD is given by

$$\exp\left(\frac{-\pi m_q^2}{\kappa}\right) \exp\left(\frac{-\pi p_{\perp q}^2}{\kappa}\right) \equiv \exp\left(\frac{-\pi m_{\perp q}^2}{\kappa}\right), \quad (1)$$

where $m_{\perp}^2 = m^2 + p_{\perp}^2$ is called the transverse mass and κ is the string tension mentioned above.

The Gaussian form of the Schwinger mechanism implies a strong suppression of breakups with high transverse momenta with respect to the string axis, and likewise a very strong suppression of heavier quarks relative to lighter ones. In particular, it is impossible to produce charm and heavier quarks this way, since, e.g., $\exp(-\pi m_c^2/\kappa) \lesssim 10^{-11}$. This also reflects that high- p_{\perp} excitations and heavy quarks should only be produced by perturbative mechanisms (partonic scattering processes and parton showers) and not by non-perturbative ones like string breaks.

Once a flavour and a $p_{\perp q}$ for the next string break in the iterative process has been selected, the next step is to select a hadron type compatible with the flavour of the current endpoint and that produced in the breakup. Since spin-1 mesons are heavier than spin-0 ones in QCD, the observed ratios between vectors and pseudoscalars are generally smaller than 3 (and equivalently for spin-3/2 baryons compared to spin-1/2 ones), however the baseline string model does not predict what these factors should be¹; instead, these are determined from data, via tuning².

To simplify the on-shell constraints of final-state hadrons, string breaks are performed such that on-shell hadrons are fragmented off directly from either string end. This is permissible since the individual string breaks are causally disconnected in the Lund model, meaning breaks can be performed in any order. Given this casual disconnect, a sensible constraint is that it should not matter which end of the string we start from; this limits the possible forms of the “fragmentation functions”, $f(z)$, we can choose to a family of “left-right symmetric” ones [18], parameterized by the two constants a , which may in principle

¹ We note the recent work on making the model more predictive in this regard [23].

² In the context of heavy quarks, we note that the default PYTHIA Monash tune has a known issue with the D^*/D ratio being too low. This can be improved by increasing the parameter `StringFlav:mesonCvector` from 0.88 to 1.5, which we recommend for charm studies.

be flavour-dependent, and b , which is flavour-universal:

$$f(z) = N \frac{1}{z} (1-z)^a \exp\left(\frac{-bm_{\perp}^2}{z}\right), \quad (2)$$

where N is a normalization constant that just ensures unit integral. Note that this fragmentation function does not have quite the same interpretation as the ones sometimes used in analytical contexts. The type shown here governs the probability distribution for the longitudinal component of the string-fragmentation process, in each step of the fragmentation. Given the transverse mass of the produced hadron, the function gives the probability the hadron will take a fraction z of the total energy of the string. The a and b parameters must be determined from data, via tuning; see, e.g., [11, 24–28].

Given a massless quark model, a Minkowski space-time diagram for a high energy $q\bar{q}$ pair moving apart from one another would result in the partons moving along a straight line along the light-cone. However given a heavy quark endpoint, this would no longer hold as a good approximation. Consider a scenario with a heavy quark and massless antiquark. Starting in the rest frame of the heavy quark, the equations of motion of strings show that the heavy quark will be dragged by the string field along a hyperbola rather than a straight line, reducing the area available for a string break. The Bowler modification [29] takes this into consideration by introducing an additional factor, $1/z^{r_Q bm_Q^2}$, into the fragmentation function. Here a multiplicative factor of r_Q is introduced to allow for flexibility and is set by the parameters `StringZ:rFactC` and `StringZ:rFactB`. Provided uniquely defined quark masses these parameters ought to be unity. There is however some deviation from unity in the default PYTHIA tune.

The above covers how string breaks occur, however one must also determine which partons are connected via strings in the first place. The default PYTHIA tune (called the Monash 2013 tune) [11] forms strings by colour-connecting partons in what is known as the Leading-Colour (LC) limit. This approximation takes the number of QCD colours (N_C) to infinity, meaning that each colour in an event is uniquely matched to a single anticolour, resulting in unambiguous string configurations. In this limit, only so-called “dipole” string configurations are allowed. These dipole strings are characterized by two endpoints, a colour and an anticolour charge endpoint (typically a quark and an antiquark), and can have any number of intermediate gluons between them which form “kinks” on the string. Examples of a dipole-type strings can be seen in the left-hand side images of Fig. 3.

Given the LC limit (and thus only dipole strings), diquark endpoints and diquark-antidiquark pair creation are the only mechanisms for baryon production in this model. As string breaks cannot produce heavy-flavour quarks, heavy-flavoured partons are therefore necessarily string endpoints, and thus the only mechanism for heavy-flavour baryon production via fragmentation in the LC limit is diquark-antidiquark pair creation next to a heavy-flavoured endpoint, while diquark production has some fixed probability of occurring (controlled by parameter `StringFlav:probQQtoQ` in PYTHIA) in the baseline string fragmentation model.

The LC approximation may be quite good in the environment of e^+e^- collisions (more specifically in the absence of multi-parton interactions (MPI)), as corrections to the LC approximation are naively expected to be $1/N_C^2$ suppressed. However, significant deviations from it are expected in pp collisions, particularly for baryon production, where the survival of the strict LC topology should be heavily suppressed.

2. Cluster model – HERWIG

Hadronization in HERWIG [17] uses the cluster model [30] which is based on the idea of colour pre-confinement. The cluster model starts by splitting gluons non-perturbatively, $g \rightarrow q\bar{q}$, after the parton shower. Assuming LC colour-connections in the baseline model, each colour-singlet $q\bar{q}$ pair forms a cluster. These $q\bar{q}$ clusters are often referred to as “mesonic clusters” (see Sect. II B 2 for other cluster types). Given these clusters, there are two main steps in the cluster hadronization process; cluster fission and cluster decay which are illustrated in fig. 2.

Cluster fission deals with large mass clusters where clusters with mass, M , above a threshold $M_{max}(q_1, \bar{q}_2)$ recursively undergo cluster fission. Working in the centre-of-mass frame of the initial cluster, a light $q\bar{q}$ pair is created from the vacuum with some flavour probability P_q , and with given momenta to align with the initial $q\bar{q}$ pair. For the example shown in Fig. 2a, the initial cluster, C , is reduced via cluster fission to two smaller clusters, C_1 and C_2 with masses M_1 and M_2 respectively, which are sampled by

$$M_{1,2} = m_{1,2} + (M - m_{1,2} - m_q)\mathcal{R}^{1/P}. \quad (3)$$

Here m_i is the constituent mass of each quark in the initial cluster, and m_q the constituent

mass of the new $q\bar{q}$ pair (special treatment of clusters with beam remnants can be found in Ref. [12]). This distribution of masses is controlled via a random number, \mathcal{R} , between 0 and 1, and the parameter P (`PSplitLight`, `PSplitCharm` or `PSplitBottom`), along with satisfying the conditions $M > M_i$ and $M_i > m_i + m_q$. It is important to note that no diquark formation is permitted in the cluster fission process.

After the cluster fission process comes cluster decays, a process which maps each cluster onto two hadrons as seen in Fig. 2b. This process is similar to cluster fission however it has hadronic mass constraints applied. When a cluster decays, the direction of the decay is typically isotropically chosen in the cluster rest frame. Here both quark-antiquark and diquark-antidiquark formation is allowed, allowing mesonic clusters to decay into either two mesons or a baryon and an antibaryon as per the example shown in fig. 2b. For clusters with perturbatively produced partons (thus particularly important for heavy-flavour hadron formation), the decay products retain the direction of the cluster rest frame up to a possible Gaussian smearing through an angle θ_{smear} , such that

$$\cos \theta_{smear} = 1 + \text{ClSmr} \log \mathcal{R}, \quad (4)$$

where the parameter `ClSmr` can be set independently for clusters containing light, charm and bottom quarks. Similarly to PYTHIA, the LC limit is insufficient to describe baryon production in pp collisions [31, 32].

B. Enhancing charm and beauty baryon yields

Several models based on different developments and assumptions, like the inclusion of beyond leading-colour (BLC) effects on string [33] or cluster [31] formation, or the inclusion of hadronization via coalescence [34–37], or the addition of a set of yet-unobserved higher-mass charm-baryon states in a statistical-hadronization framework [38–40], expect an enhancement of heavy-flavour baryon production relative to that of meson states, in hadronic collisions with respect to e^+e^- collisions.





FIG. 2: Schematics of the cluster fission and decay processes used in cluster hadronization, with top image showing the initial cluster in the centre-of-mass frame, and the bottom image shows the system after the cluster fission/decay process has occurred.


1. Extensions to the default (Monash 2013) PYTHIA tune

One model critical for modelling baryon production in pp collisions using PYTHIA is the so-called QCD-based colour reconnection (CR) model [33]. Extending the string model beyond the leading-colour approximation reintroduces colour-space ambiguities due to the $N_C = 3$ finite colour structure of QCD. Modelling partons using SU(3) colour-space means that each colour is not necessarily unique, allowing multiple different partons to be colour-connected and causing ambiguity in where confining potentials arise. To determine between which partons the confining fields form, the configuration that minimizes the string “length”, or the action potential of the system, is chosen. This “string length” is a Lorentz-invariant measure called the lambda measure [41], which is a measure of the energy density per unit length of the string. By requiring minimized string lengths between colour-connected partons, strings are thus able to form between partons not produced in the same hard scatterings, allowing topologies to span across different MPI. The so-called QCD-based CR model developed within PYTHIA 8 stochastically reintroduces the SU(3) colour correlations, doing so using SU(3) algebra to describe the probabilities associated with overlaps in colour-space. These overlaps become particularly relevant for hadronic collisions at high energies, where MPI produce densely populated partonic environments.


Given the colour singlet requirement with the inclusion of sub-leading colour effects, there are three general types of string configurations to consider: dipole strings, junction topologies, and gluon loops. Both junctions and gluon loops are explicitly beyond LC configurations. Dipole reconnections and gluon loops make use of the colour-anticolour singlet state, whereas junction topologies occur due to the colour-neutral red, green, and blue colour combination. Fig. 3 demonstrates examples of each of these CR types, where the length of the lines representing strings are meant to give an indication of the string length which we want to minimize via CR. The left images show an example LC configuration, and the right show beyond LC strings after allowing CR.



(a) Dipole-type reconnection.



(b) Junction reconnection.



(c) Gluon-loop formation.

FIG. 3: For each reconnection type, the left images show a LC string configurations, and the right-hand side images show possible alternative colour reconnected configurations.

Note that colour-octet gluons carry a colour and an anticolour charge, which are represented by the colours on the top and bottom half of the gluons respectively.

Beyond LC effects are particularly important for heavy-flavour baryon production due to the formation of junction topologies. Junctions provide a new mechanism for baryon production via fragmentation whereby the baryon number of the junction system is preserved. The hadronization of these topologies is depicted in Fig. 4, where each junction “leg” fragments in a similar manner to dipole string fragmentation. The quarks formed by breaks nearest to the junction itself form a baryon, which in the Fig. 4 example has quarks $q_3q_5q_9$ forming the “junction baryon”. This additional baryon production mechanism leads to baryon enhancement as shown in the left panel of Fig. 6 for the Λ_c^+/D^0 yield ratio case. As heavy-flavour (charm and beauty) quarks cannot be created via string breaks, heavy-flavour hadrons from fragmentation necessarily come from string breaks nearest to the string endpoints. Therefore heavy-flavour baryons can either be created via diquark creation next to a heavy-flavour endpoint, or from junction baryons. For a junction baryon to be heavy-flavoured, the junction leg containing the heavy-quark endpoint cannot fragment. The effects of this can be observed by examining the p_T dependence of heavy-flavour baryons.

In the standard fragmentation framework, diquark-antidiquark pair creation has some fixed probability of occurring with no p_T dependence, making it insufficient to describe the measured increase of heavy-baryon production at low p_T . However, junction baryons are expected to predominantly sit at low p_T due to the way dipole strings reconnect into junctions. Junction reconnections mostly occur between dipoles in different jets, and given the large phase space available, these jets are likely to have large opening angles. As the junction forms between these generally large opening-angled jets, the junction (and therefore the junction baryon) is expected to sit at low p_T , making them particularly interesting for p_T studies of heavy-flavour baryons.

Junction topologies are also expected to affect heavy-flavour asymmetries. This is due to how junction reconnections map three dipole configurations onto two junctions, as seen in Fig. 3b, resulting in both junctions and antijunctions forming in equal quantities. This would therefore contribute towards both heavy-flavour baryons and antibaryons, reducing the baryon asymmetry (particularly at low p_T) and in turn also altering the meson asymmetries in the heavy-flavour sector.

In e^+e^- collisions, modifications to the leading-colour picture are small, suppressed by both colour and kinematics factors. However, in dense partonic environments such as pp collisions, MPI increase the number of possible subleading connections, counteracting their

naive $1/N_C^2$ suppression. This model represents a significant step in the right direction of probing for the first time the effects of sub-leading colour on hadronization in a systematic way.




FIG. 4: A sketch of a junction system after fragmentation, with the junction baryon consisting of quarks $q_3q_5q_9$.

To understand baryons produced via diquark-antidiquark pair creation, it is important to look at how diquarks are treated in PYTHIA. Using standard string fragmentation, these diquarks are given a constituent mass and treated on equal footing as quark-antiquark string breaks. However there is an alternative approach, called the popcorn mechanism [42, 43], which models diquark creation as a stepwise process using virtual $q\bar{q}$ fluctuations of colour charges on the string. For example, given a $q\bar{q}$ string with colours red and antired, then two virtual fluctuations with colours green-antigreen and blue-antiblue can potentially combine to form a real red-antired diquark-antidiquark pair. Furthermore, again using the colour structure of the virtual fluctuations, mesons can therefore be created between such diquark-antidiquark pairs. Thus unlike the standard string fragmentation mechanism where a diquark-antidiquark pair must be created next to one another, the popcorn mechanism allows for the decorrelation of the baryons produced.

These virtual fluctuations can also in principle colour reconnect with a diquark endpoint,

meaning the constituent quarks forming the diquark will contribute towards two separate hadrons. Given a virtual $q\bar{q}$ fluctuation with the correct colour structure, one quark from the initial diquark could form a meson with the fluctuation \bar{q} , and the other would thus recombine into a diquark with the fluctuation q . This means that the first hadron produced from a diquark string end may not be a baryon, and therefore a heavy-flavoured diquark does not necessarily guarantee a heavy-flavoured baryon.

Another feature of the popcorn model is the suppression of leading-baryon production, and is controlled in PYTHIA by parameters `StringFlav:suppressLeadingB`, `StringFlav:heavyLeadingB` and `StringFlav:lightLeadingB`. Though strictly speaking this should be a suppression of early production time baryons, a simpler version is implemented where the baryon production at the end of the string (otherwise known as a rank 1 baryon) is suppressed. This is a reasonable simplification as the rank 1 baryons are associated with lower average Γ values compared to higher ranks (breaks in the centre of the string), where Γ is a variable associated with the proper time of the string break, $\Gamma = \kappa^2 \tau^2$. However, $\langle \Gamma \rangle$ of heavy-flavour rank 1 baryons is approximately the same size as the limiting value of $\langle \Gamma \rangle$ for light flavours, meaning that no suppression is expected for leading heavy-flavour baryons relative to string breaks in central regions of a string. As heavy-flavour baryons are expected to only come from fragmentation near string ends, the suppression of endpoint baryon production needs careful handling.

To complete a comprehensive study on heavy-flavour hadron production in PYTHIA, one must also consider models that alter the light-flavour quark sector, particularly strange quark production rates. Strangeness enhancement has been observed at ALICE [44, 45], which shows a rise in strange-hadron production with respect to charged multiplicity that neither the default tune nor QCD-based CR in PYTHIA can describe. To describe the multiplicity dependence seen at ALICE, additional collective effects are required on top of the standard fragmentation framework. The two primary models proposed to describe this strangeness enhancement are rope hadronization [46, 47] and close-packing [48]. Both models are readily available for use in PYTHIA 8.311, however the close-packing implementation is not catered to strangeness in jets or e^+e^- collisions as of yet. Such models have shown to successfully result in increased strange-hadron production. Both models work by increasing the string tension in more densely packed string environments, which are correlated with high multiplicity events. An increased string tension translates to a greater energy density per

unit length of the string, allowing for higher mass particles to be created via string breaks with a greater probability, enhancing both strange quark and diquark production. The distinction between the two models lies in how the altered string tension is calculated. Rope hadronization treats a collection of strings as a coherent structure, where a larger collection of strings results in higher string tensions, and the order of string breaks becomes important. Close-packing proposes a simpler mechanism, whereby the number of surrounding strings determines the rise in string tension and directly changes the string tension.

Another avenue for exploration is alternatives to the Schwinger mechanism, with one such model already implemented in PYTHIA being the thermodynamical string breaking model [48]. This alternative model uses a thermal exponential instead of the Gaussian form provided by the Schwinger mechanism to model pair creation due to string breaks. The “temperature” dependence, T , in the exponent is directly related to the string tension κ via $T \propto \sqrt{\kappa}$, and particularly alter the p_T spectra of string breaks.

2. Colour reconnections in HERWIG

HERWIG also allows for colour reconnections [31] in their hadronization model, allowing for both mesonic ($q\bar{q}$) and baryonic (qqq and $\bar{q}\bar{q}\bar{q}$) cluster reconnections. In order to determine whether to reconnect clusters, the closeness in phase space using a rapidity measure is considered along with a probability to accept the reconnection. The procedure works by first selecting a cluster (call this cluster A) and boosting to its centre-of-mass frame. The centre-of-mass frame momenta then defines a z-axis, with the positive z-direction defined by the direction of the antiquark. In this frame, the rapidity of the remaining clusters are calculated and are used as a measure of closeness between which partons these clusters should form. For a given cluster (call this cluster B), the possible reconnection types available are determined by the rapidities of the $q\bar{q}$ pair; $y(q_B) > 0 > y(\bar{q}_B)$ allows for mesonic reconnections, $y(\bar{q}_B) > 0 > y(q_B)$ allows for baryonic reconnections, and if neither conditions are satisfied then no reconnection type is considered. For a mesonic reconnection, the configuration with the maximal $y_{sum} = |y(q_B)| + |y(\bar{q}_B)|$ is considered and the reconnection is accepted with a probability of P_M . This is demonstrated in Fig. 5a where initial clusters A and B reconnect to clusters C and D. For baryonic reconnections, the two largest y_{sum} values are considered and the reconnection of clusters A, B and C to form clusters D and

E (as seen in Fig. 5b) is accepted with probability P_B . This process is then repeated for all other clusters. Similarly to string junctions in PYTHIA, baryonic clusters contribute to an additional baryon production mechanism to the LC hadronization model as the baryon number of the cluster is preserved.




FIG. 5: The grey clusters represent the initial cluster, and given colour reconnections the red represents the possible alternative cluster formations that are chosen with acceptance probability (a) P_M or (b) P_B .

3. Statistical hadronization with additional baryon resonances

The Statistical Hadronization Model (SHM) assumes that hadrons are produced according to the density of thermal yields $N_h^{th}(T)$. In ultra-relativistic heavy-ion collisions, the SHM successfully reproduces the yields of meson and baryon ground states with one chemical freeze-out temperature of $T_{cf} \simeq 156$ MeV [40], which represents the temperature of the medium at which the different particle abundances get fixed. Its extension to charm (and beauty) hadrons needs to consider that the charm quarks are produced in the initial stage of the collisions with a multiplicity that is quite larger than the one expected from thermal charm production at T_{cf} . To this purpose, a charm-quark fugacity factor g_c , which represents the ratio of total charm yield to the thermal charm one, is included in the model to take into account this excess. A charm balance equation is needed to guarantee the conservation of charm quarks for a given value of g_c , while allowing the relative abundances of

the different open and hidden charm hadrons to follow the statistical thermal ones, it can be written as:

$$\frac{N_{c\bar{c}}}{V} = \frac{1}{2}g_c \sum_{h_{oc,1}^i} n_i^{\text{th}} + \frac{1}{2}g_c^2 \sum_{h_{oc,2}^j} n_j^{\text{th}} + g_c^2 \sum_{h_{hc}^k} n_k^{\text{th}}, \quad (5)$$

where $N_{c\bar{c}}$ is the total charm yield in the rapidity range considered, $n_{i,j,k}^{\text{th}}$ are the (grand-canonical) thermal yields for open charm with one charm quark ($h_{oc,1}$) and two charm quarks ($h_{oc,2}$) and for hidden charm (h_{hc}). In principle, Eq. 5 should include the hadrons with three charm quarks but, in the current implementations, they are discarded under the reasonable assumption that their contribution to the sum is negligible. Fugacity factors in elementary collisions are introduced to account for the non-equilibrium yield of quarks heavier than u and d , thus for strangeness as well as for charm. However, due to the dominance of hadrons with one charm quark this does not affect baryon-to-meson yield ratios of single charm hadrons, because both baryons and mesons contain one charm. On the other hand, one can also notice that doubling $N_{c\bar{c}}$ implies doubling g_c , with a consequent enhancement by a factor of 2 of single-charm hadrons and a factor of 4 increase of double-charm hadrons. Such a scaling with $N_{c\bar{c}}$ is expected also in the coalescence model described in the next paragraph.

Such an approach, which correctly predicts the relative abundances of D-meson states, has been challenged by the large Λ_c^+/D^0 values measured in pp, p-Pb, and Pb-Pb collisions, which will be discussed in the Sect. III. In particular, using the resonance states listed in PDG [49] the charm baryon yields are substantially underpredicted by the SHM. However, it is argued in Refs. [38, 50] that the charm and beauty baryon enhancement is to be attributed to the enhanced feed-down from “missing” charm- and beauty-baryon states in the PDG with respect to the predictions of the relativistic quark model (RQM) [51] and lattice QCD calculations [52]. Including the additional baryon resonances makes a decisive difference and enables a significant heavy-flavour baryon enhancement. The additional baryon states almost double the fraction of the ground-state Λ_c^+ in the system relative to the PDG scenario when a hadronization temperature of 170 MeV is used. The SHM is usually employed to evaluate the total hadron yield. However, in the heavy-flavour sector for pp collisions, it has been coupled to the concept of independent fragmentation functions to compute pertinent p_T spectra by the TAMU group [38]. In this approach, a thermal distribution function is exploited to determine the fragmentation fractions, but when comparing to experimental data the

baryons and mesons are non-thermally distributed in p_T but according to the fragmentation functions. The model employs a modern fragmentation function formalism developed for heavy quarks that depend on one parameter r defined as follows for each hadron species. For D^0 and Λ_c^+ the related parameters (r_{D^0} , $r_{\Lambda_c^+}$) are tuned to reproduce the measured p_T spectra. For higher meson (M) and baryon (B) resonances, the related parameters are obtained by rescaling those of D^0 and Λ_c^+ according to their mass, $r_{M[B]}/r_{D^0[\Lambda_c^+]} = ((m_{M[B]} - m_c)/m_{M[B]})/((m_{D^0[\Lambda_c^+]} - m_c)/m_{D^0[\Lambda_c^+]})$. The results of this model calculation are reported in the middle panel of Fig. 6 for the Λ_c^+/D^0 yield ratio: a significant enhancement at low p_T is observed. The uncertainty band in the model is obtained by varying the assumptions on the branching ratios of excited charm-baryon state decays to the ground state. In heavy-ion collisions, the TAMU model employs a recombination approach that inherits the SHM yields, similarly to the pp-collision case, but evaluates the p_T distribution functions according to a recombination model based on the Boltzmann collision integral (see next section).

More recently, also the standard SHM approach, originally set up to predict the p_T -integrated yields of the different hadrons has been extended, when applied to the charm sector, to supply a first tentative modelling of the p_T distribution in AA collisions [40, 53]. A two-component model containing a thermalized distribution with a radial flow plus a contamination from a “corona shell”, to which a p_T distribution like that of pp collisions is associated, is implemented. The method shows a qualitative agreement with the data mainly in the low p_T region ($p_T \lesssim 2 \text{ GeV}/c$), while already at intermediate p_T there is a significant lack of yield that cannot be compensated only by the corona contribution. This is in line with the general finding of all dynamical approaches to charm in-medium interaction, namely that charm gets close to equilibrium in the low p_T region [54, 55], but it might retain a long- p_T -tail of non-equilibrium.

4. Hadronization via coalescence

The idea of quark coalescence in heavy-ion collisions dates back to about two decades ago and was applied to account for the first observation of an enhancement in the p/π ratio at intermediate p_T [56–59]. Contrary to the fragmentation process, where the final heavy-flavour hadron always carries smaller energy than the parent heavy quark, the idea of the coalescence model comes from the fact that partons in a dense medium (even if not

necessarily thermalized) combine their transverse momentum to produce a final-state meson or baryon with higher transverse momentum. Thus, with coalescence the average hadron p_T is pushed to larger values with respect to fragmentation.

In heavy-ion collisions it has been possible to associate to hadronization by coalescence signatures going beyond the particle-yield ratios, predicting a quark-number scaling of the azimuthal anisotropy of the production that is quantified by the elliptic flow [56, 60, 61]. According to this the $v_2(p_T)$ should scale into a universal curve given by $1/n_q * v_2(p_T/n_q)$ with $n_q = 2$ for meson and $n_q = 3$ for baryons. A moderate breaking of such scaling is expected mainly at low p_T in realistic coalescence models due to the finite width effect of the hadron wave function, feed-down by hadron resonance decays, and radial flow correlations [61, 62]. In addition, it has been shown that off-shell dynamics with the constraint of energy conservation drives the p_T scaling toward an m_T scaling [63] at low p_T . Furthermore, at intermediate p_T the interplay with the fragmentation function induces a further explicit significant breaking of the scaling [64]. Data at the Relativistic Heavy Ion Collider (RHIC) and the LHC confirmed that at intermediate p_T (around the peak value of $v_2(p_T)$) the elliptic flow follows two different branches depending on their valence quark number such that $v_{2M}(p_T/2)/2 \simeq v_{2B}(p_T/3)/3$ for light quark hadrons.

The coalescence approach has been extended to the charm sector to study the production of D mesons [65]. There is a quite general consensus that including this process is necessary to correctly reproduce the main observables like $R_{AA}(p_T)$ and $v_2(p_T)$ [66, 67]. It has to be noticed that being the mass of the light and heavy-flavour quarks quite different, one expects that a D meson at a certain p_T is formed from the recombination of a light quark quark of transverse momentum $p_q \simeq \frac{m_q}{m_q+m_c} p_T$ with a charm quark with $p_c \simeq \frac{m_c}{m_q+m_c} p_T$ [68]. Therefore, having usually $m_c \simeq 4m_q$, this implies that on average the D meson gets about 0.2 p_T from the light quark and 0.8 p_T from the charm quark. Hence, one envisages that $v_{2,D}(p_T) \simeq v_{2,q}(0.2 p_T) + v_{2,c}(0.8 p_T)$. This simple argument must be complemented considering the finite width of the wave function and the slope in p_T of quark distribution functions as well as the contribution from the fragmentation, which is non-negligible at intermediate p_T .

The coalescence plus independent fragmentation approach predicted already in 2009 that in AA collisions one could expect a quite large Λ_c^+ production and $\Lambda_c^+/D^0 \sim O(1)$ [34], a value about one order of magnitude larger than that measured in e^+e^- collisions in which the Λ_c^+ fragmentation fraction was estimated to be $f(c \rightarrow \Lambda_c^+) \simeq 0.06$ [69]. The first measurements

made by the STAR Collaboration and ALICE Collaborations in Au–Au collisions at $\sqrt{s_{\text{NN}}} = 200$ GeV and Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, respectively, qualitatively confirmed such a prediction [70, 71]. Successive measurements by ALICE and CMS allowed to better profile the evolution of Λ_c^+/D^0 ratio with p_T and centrality [72, 73].

Catania model: This model has been applied extensively to particle production not only in the light sector but also to charm baryon and meson production in both AA collisions [37, 65, 67] and pp collisions [36]. The model has been recently expanded to provide first predictions for multi-charm baryons [74] that are expected to be measured in heavy-ion collisions at the LHC with the future ALICE 3 experiment [75]. The Catania approach implements hadronization of charm quarks via both coalescence and independent fragmentation and assumes the presence of a flowing thermalized medium of light quarks (u, d, s). In pp collisions the general expectation was that a QGP would not be created. However, experimental measurements provide strong indications for the formation of an expanding medium in small collision systems [44, 76–78]. In addition, viscous hydrodynamics and transport calculations supply a reasonable description of experimental measurements [79–81]. Recently, an approximate quark-number scaling of hadron elliptic flows was also shown for small collision systems [82]. This motivated the extension of the Catania model assuming a small fireball of expanding QGP even in pp collisions.

In the model, a blast wave parameterization [83] for light quarks at the hadronization hypersurface with the inclusion of a contribution from mini-jets is considered. For charm quarks, the spectra from FONLL calculations are used in pp collisions, while in AA collisions the spectra are taken after collisional energy loss in the medium evaluated through a Quasi Particle Model (QPM) implemented in a Boltzmann transport dynamics or in a Langevin equation through the corresponding drag and diffusion coefficients [67, 84, 85]. The coalescence approach is based on a phase space description of the system created in AA collisions. The basic formula is written in terms of the Wigner function describing the spatial and momentum distribution of quarks in a hadron. In particular, the momentum spectrum of hadrons formed by coalescence can be written as:

$$\frac{dN_H}{dyd^2P_T} = g_H \int \prod_{i=1}^{N_q} \frac{d^3p_i}{(2\pi)^3 E_i} p_i \cdot d\sigma_i f_{q_i}(x_i, p_i) \mathcal{C}_H(x_1 \dots x_{N_q}, p_1 \dots p_{N_q}) \delta^{(2)} \left(P_T - \sum_{i=1}^n p_{T,i} \right), \quad (6)$$

with g_H indicating the statistical factor giving the probability that two (or three) random

quarks have the right quantum numbers to match the quantum number of the hadron (flavour, spin, isospin) in a colourless combination. For D mesons the statistical factor $g_D = 1/36$ gives the probability that two random quarks have the right colour, spin, and isospin to match the quantum number of the considered mesons. For Λ_c^+ the statistical factor is $g_{\Lambda_c^+} = 1/108$. N_q is the number of quarks that form the hadron, $N_q = 2$ for mesons and $N_q = 3$ for baryons. The $d\sigma_i$ denotes an element of a space-like hypersurface, while f_{q_i} are the quark (anti-quark) phase-space distribution functions for i^{th} quark (anti-quark) and the coalescence function $\mathcal{C}_H = C^{N_q-1} f_H(x_1 \dots x_{N_q}, p_1 \dots p_{N_q})$ is directly proportional to the Wigner function which describes the spatial and momentum distribution of quarks in a hadron, f_H . The constant C^{N_q-1} is an important and specific aspect of the Catania model, not present in the standard coalescence approach. It is this constant that allows normalizing the coalescence probability for charm quarks such that the total coalescence probability (i.e. summing up all the mesons and baryons channel considered) in the limit $p_T \rightarrow 0$ is $P_{coal}(p_T \rightarrow 0) = 1$. Such a constant C can be determined only by calculating all the charmed mesons and baryons. In the first work [37] it was evaluated considering only D, D^{*+} , D_s^+ , Λ_c^+ , and $\Sigma_c^{0,+}$ hadrons. However, more recently the production of $\Xi_c^{+,0}$ and Ω_c^0 was observed not to be negligible [36]. Having fixed such a normalization, the probability of a charm quark to hadronize via coalescence or fragmentation depends as in the standard approach on its transverse momentum according to Eq. 6. The coalescence probability is high for low quark momenta and quickly decreases with increasing transverse momentum, meaning that most of charm quarks hadronize via coalescence at low p_T whereas, in the high momentum region, fragmentation is the dominant contribution. Imposing the condition $P_{coal}(p \rightarrow 0) = 1$ is a key aspect underlying the prediction of quite large values of heavy baryons: $\Lambda_c^+/D^0 \sim O(1)$, $\Xi_c^0/D^0 \sim 0.2$ and $\Omega_c^0/D^0 \sim 0.1$ [36]. The physical motivation is related to the fact that in the standard coalescence approach there is no dynamics related to confinement. The renormalization constant C appears linearly for mesons and quadratic for baryons. This is physically motivated at least by two considerations. First, enforcing $P_{coal}(p_T \rightarrow 0) = 1$ implies that there is an enhancement of the recombining probability (with respect to the one from a simple phase space overlap of the wave functions) that can be associated to the dynamics of the confining interaction that increases the coalescence probability (here accounted for just by a renormalization of a coupling constant). Such an effect has to be squared for baryons for which two relative distances among the quarks have

to be defined. Second, one has to consider that the density of the medium at which the hadrons are formed is not known, and being the phase transition a cross-over it is likely that there is a density interval over which it occurs. Therefore the hadrons yields and ratios in a standard coalescence approach (i.e. without imposing $P_{coal}(p_T \rightarrow 0) = 1$) would significantly depend on the specific value of the density chosen. In the Catania approach the probability of forming a hadron scales linearly with the density for mesons and quadratically for baryons. If one chooses a lower value density value, implying a reduced standard coalescence probability, the constraint $P_{coal}(p_T \rightarrow 0) = 1$ increases the value of the coefficient C^{N_q-1} , making the yields and the baryon-over-meson ratios quite stable and nearly independent of the specific value of the density of the background fireball employed to perform the calculation.

Another relevant aspect of the Catania approach is the width of the Wigner function for the various mesons and baryons. These are related to the root mean square charge radius of the hadron taken from the quark model [86, 87]. A Gaussian wave function is assumed for simplicity and it implies that also the associated hadron Wigner function is Gaussian:

$$f_H(x_{ri}, p_{ri}) = \prod_{i=1}^{N_q-1} 8 \exp\left(-\frac{x_{ri}^2}{\sigma_{ri}^2} - p_{ri}^2 \sigma_{ri}^2\right), \quad (7)$$

with x_{ri} and p_{ri} relative coordinates in space and momentum. We notice that an important aspect of a proper implementation of the coalescence approach is that, respecting the basic feature of quantum mechanics, the width σ_r of the wave function in r-space constraints also the Wigner function width in p-space; for a Gaussian wave function for each relative coordinate we have $\sigma_{ri} \cdot \sigma_{pi} = 1$ and σ_p cannot be used as a further independent parameter. It can be noticed that the coalescence process, and the related formula, can be factorized as a diquark recombination followed by a diquark-quark coalescence if the diquark binding energy is vanishing.

It is interesting to discuss the dependence of the coalescence results on the specific value of the wave-function width, which is the main parameter of the model. This can be easily evaluated analytically considering a non-relativistic reduction, which, even if not quantitatively exact, allows having a semi-quantitative estimate of the main aspect involved in the coalescence process. Assuming a non-relativistic boost invariant thermal distribution function homogeneous in r -space, discarding the radial flow, and assuming a Gaussian wave function, it can be shown that the coalescence yield for mesons and baryons scales as:

$$N_M \sim \frac{\sigma_r^2}{\sigma_r^2 + (2\mu_{12}T)^{-1}} \quad \text{and} \quad N_B \sim \frac{\sigma_{r1}^2}{\sigma_{r1}^2 + (2\mu_{12}T)^{-1}} \frac{\sigma_{r2}^2}{\sigma_{r2}^2 + (2\mu_{(12)3}T)^{-1}}, \quad (8)$$

where μ_{12} is the reduced mass of the two quarks undergoing coalescence and T is the temperature of the medium. The numerator is associated with the probability of forming a meson in r -space, which of course increases with the width σ_r . On the other hand, this increase is compensated by the probability in momentum space where the effective width is given by $\sigma_p = 1/\sigma_r$, hence decreasing with increasing σ_r . From the denominator of Eq. 8 we can see that there is another scale that plays a role and is given by $1/2\mu T$. This represents the width of the distribution of relative momentum of the coalescing objects. In the infinite temperature limit that would give a distribution in momentum space asymptotically flat, and the yield would become independent on the wave function width. Increasing σ_r one increases the probability of coalescence in r -space but this is exactly compensated by the shrinking of the Wigner hadron function in momentum space. Apart from this extreme ideal case, the increase of the width σ_r leads to an increase that quantitatively depends on the comparison between the width of the hadron wave function σ_r and the width of the thermal distribution $1/2\mu T$. For $\sigma_r^2 \ll (2\mu T)^{-1}$ the yield is strongly dependent on the size of the hadron wave function, while for $\sigma_r^2 \gg (2\mu T)^{-1}$ the yield is nearly independent on the hadron wave function. For the specific case of charm meson and baryons, $\sigma_r^2(D^0) = 0.65 \text{ fm}^2$ and $(2\mu T)^{-1} = 0.5 \text{ fm}^2$, hence an increase of $\langle r^2 \rangle$ by a factor of two implies an increase of the yield of about 30%. Smaller baryons like Ω_c have the relative widths $\sigma_{r1}^2(\Omega_c) = 0.34 \text{ fm}^2$ and $\sigma_{r2}^2(\Omega_c) = 0.14 \text{ fm}^2$ and $(2\mu_{ss}T)^{-1} = 0.6 \text{ fm}^2$ and $(2\mu_{(ss)c}T)^{-1} = 0.6 \text{ fm}^2$ such that an increase of $\langle r^2 \rangle_{\Omega_c^0}$ by a factor of 2 induces an increase of the yield of about a factor 2.2. Therefore, hadrons that have a large mean square radius and large mass are in general not very sensitive to the parameter σ_r , if the relation $\sigma_p = 1/\sigma_r$ is employed. However, on top of this standard coalescence feature, one has to consider the constraint that $P_{coal}(p_T \rightarrow 0) = 1$ strongly damp such dependence for the D and Λ_c^+ hadrons, which dominate the overall charm-hadron yield [74]. The Catania coalescence plus fragmentation model was first applied to AA collisions prediction of Λ_c^+/D^0 both at RHIC and LHC energy [37], but soon after it led to a quite good prediction of the Λ_c^+/D^0 yield ratio in pp collisions, as shown in the right panel of Fig. 6. It also provided within the current uncertainties also a reasonable predictions for the Ξ_c^0 and $\Sigma_c^{0,+}$ production, see also Figs 15 and 16 in Sec.III.C.

Other coalescence approaches: In other approaches [34, 88], applied to AA collisions and based on a formulation formally very similar to Eq. 6 and 7, the constraint to have $P_{coal}(p_T \rightarrow 0) = 1$ is also implemented, but it is achieved artificially increasing the width σ_{r_i} of hadrons by a constant factor, resulting in radii about a factor 1.8 larger than the one employed by the Catania model [37] that relies on the quark model prediction in Ref. [86, 87]. This choice should also affect the width in momentum space modifying the p_T dependence of the spectra. A study of such an effect, and a direct comparison to the Catania model, would be instructive but has not yet been performed. A refinement of the coalescence approach is to consider the different wave function of $l = 1$ states, which leads to a non-Gaussian Wigner function [88], different from that of the Catania model. This is done also in the hadronization mechanism implemented in the Parton Hadron String Dynamics (PHSD) [89].

The PHSD model provides a realistic simulation of the entire heavy-ion collision and it also implements a coalescence approach to hadronization of heavy quarks [89]. The quark masses are distributed according to the spectral function of a dynamical quasi-particle model (DQPM) [90], very similar to the QPM used in Catania to describe the heavy-quark dynamics. Then, as in the Catania model, the probability of coalescence is evaluated by a superposition of the quark distribution with the Wigner hadron wave function, but considering both S- and P-wave states. Differently from the Catania model, it does not implement the constraint $P_{coal}(p_T \rightarrow 0) = 1$ and the coalescence process is not instantaneous but occurs during the fireball expansion when the local energy density spans the interval $0.3 < \epsilon < 0.9 \text{ GeV/fm}^3$. Hadronization for heavy flavor within the PHSD approach has been extensively applied to study charm dynamics in AA collisions; only very recently it has been done an extension to pp collision studying the bottomonium production [91].

Finally, a more simplified approach to hadronization by coalescence is the Quark recombination Model (QCM) which, though based on the idea of quark recombination, has several features that are different from the other approaches discussed above. The model is developed in one dimension representing the transverse momentum. The coordinate space is not considered. The model does not employ as light-quark sources quark distribution functions as thermal+flow distributions and/or resulting from a dynamical study of heavy quark dynamics. Rather, it extracts them from a fit to π , K, and D mesons [35, 92]. Furthermore, hadronization is occurring by coalescence at all momenta, without any contribution from fragmentation. Once the u, d, s, and c quark distribution functions are extracted from the fit,

they are used as a source to compute the spectra as a function p_T of all hadron species: p , Λ , ϕ , Ω , Λ_c^+ etc... The role of Wigner hadron function in the standard recombination approach is substituted by a recombination function that is given by a delta function, which imposes quarks with the same velocity to recombine. The ratio between vector and pseudoscalar meson yields is fixed by a parameter $R_{V/P} = 3/2$ indicated as thermal weight because it corresponds to the value of $D^*/D \simeq 3 (M_D/M_{D^*})^{3/2} \exp[-(M_D - M_{D^*})/T_H] \simeq 3/2 = R_{V/P}$, if one assumes a thermal production at a temperature $T_H = 170 - 175$ MeV, as done also in [93] in the context D meson production in πN collisions, see Sect. III.B. This is the same assumption exploited in the Catania coalescence model even if in this case the temperature, $T_H = 165$ MeV is the one of the hadronizing medium that determines the light and strange quark thermal distribution, while in QCM the concept of temperature does not really play a direct role because the quark distribution functions are deduced from a fit to π , K, and D mesons experimental data. A similar ratio parameter is used to fix the ratio between the baryons of the octet ($J^P = (1/2)^+$) and decuplet ($J^P = (3/2)^+$) by the parameter $R_{O/D} = 2$.

Resonance recombination model: Another main approach to charm hadron formation is the Resonance Recombination Model (RRM) of TAMU group where hadronization is described by scattering of thermal light quarks with heavy quarks into broad D-meson like resonances [63]. This model is also based on the idea that hadronization occurs by a recombination of quarks in the medium, but the process is modelled like a scattering of two particles into a hadron resonance with a finite width Γ . The meson spectrum is written in terms of the quark and anti-quark distribution as:

$$\frac{dN_M}{d^2p_T dy} = \int \frac{d^3\vec{p}_1 d^3\vec{p}_2}{(2\pi^3)^2} f_q(\vec{x}, \vec{p}_1) f_{\bar{q}}(\vec{x}, \vec{p}_2) \frac{\sigma_M(s)}{M\Gamma} v_{rel}(\vec{p}_1, \vec{p}_2) \delta^3(\vec{p} - \vec{p}_1 - \vec{p}_2), \quad (9)$$

where $\sigma(s)$ is the relativistic resonance cross section (Breit-Wigner). We can envisage from Eq. 9 and Eq. 6 that RRM approach shares with the coalescence approach several features because the main underlying process consists in adding momenta of particles coming from the medium and the relative momenta of quarks determine the formation probability according to the values of $\sigma_M(s) v_{rel}$. On the other hand, the formation of the hadron is not directly related to the wave function width. However, the main features of modifying $R_{AA}(p_T)$ from charm to D meson inducing an enhancement of D-meson R_{AA} at $p_T \gtrsim m_Q$ accompanied by an enhancement of the elliptic flow are similar to those resulting from the coalescence approach. The main difference with respect to coalescence is in the momentum

dependence of the probability of hadron formation by recombination. Also in RRM there are two competing hadronization processes, with independent fragmentation applied to the charm quark that does not recombine according to Eq. 9. However, the recombination in RRM is dominant over fragmentation in a wider p_T range with respect to coalescence [94]. The RRM approach has been more recently applied also to the Λ_c^+ production, which is modelled as a two-step process: the formation of a diquark according to Eq. 9 followed by a scattering process between the diquark and the charm quark. An important ingredient introduced in recent years in the modelling of coalescence in the TAMU model are space-momentum correlations between the recombining quarks. Given that recombination is more probable for quarks that are close in both momentum and space, the correlation between the heavy-quark momentum vector and their spatial position in the fireball, induced by the interplay of the heavy-quark interaction in the medium and the medium expansion, influences significantly the heavy-flavour hadron R_{AA} , v_2 , and the relative particle-species abundances. Furthermore, being the hadronization modelled like a scattering process $2 \rightarrow 1$ going into an off-shell hadron it is possible to conserve the 4-momentum and it has been shown that under the assumption of local thermal equilibrium the D meson spectrum converges to the equilibrium thermal spectrum. A more thorough comparison to the coalescence approach has indeed to consider that qualitatively coalescence is quite similar to RRM because the pair going into coalescence to form a D meson have an invariant-mass distribution around the D-meson mass with a finite width, so that energy is conserved with respect to an off-shell D-meson-like resonance also in a coalescence approach. The difference is that however in RRM the exact thermal equilibrium is constrained while in coalescence one has simply an invariant-mass distribution regulated by the relative quark momentum distribution in the medium and its interplay with the wave function width. This aspect has never been pointed out: a direct comparison of coalescence, RRM, and the diquark-quark in medium hadronization, recently developed by the Turin group within the Powlang model discussed below, could be interesting.

Powlang: Another approach to in-medium hadronization also based on the idea of quark recombination is the one developed by Powlang [95–97], which implements a Langevin evolution of charm quarks produced with a POHWEG+PYTHIA Monte Carlo event generator into a hydrodynamical background. In such an approach a charm quark is recombined with a thermal quark or di-quark on a hadronization hyper-surface identified by the local temper-

ature $T_H = 155$ MeV. Hence each (anti-)charm quark can randomly form pairs with quarks or di-quarks distributed according to a thermal spectrum corresponding to the density:

$$n = g_s g_I \frac{T_H M^2}{2\pi^2} \sum_{n=1}^{\infty} \frac{(\pm 1)^{n+1}}{n} K_2 \left(\frac{nM}{T_H} \right), \quad (10)$$

where the mass M of quark and di-quarks are taken in the range of the constituent quark picture: $m_{u/d} = 0.33$ GeV, $m_s = 0.5$ GeV, $m_{(ud)_0} = 0.579$ GeV, $m_{(sl)_0} = 0.804$ GeV, $m_{(ss)_1} = 1.0936$ GeV; while g_s is the spin degeneracy and g_I the isopin degeneracy. The recombination occurs if the invariant mass of the pair, M_C , is larger than the mass of the lightest charmed hadron. Then the cluster decays into a charmed hadron that has the same baryon number and strangeness of the cluster or, for large invariant masses, $M_C > M_{max} \simeq 3.8$ GeV, it hadronize via string-fragmentation according to PYTHIA 6.4. Therefore, differently from the coalescence approach, the probability of hadronizing via recombination is not determined by a hadron wave function with a finite width in momentum space (typically of the order of a few hundred MeV), but rather by the formation-probability of clusters of quite large invariant mass undergoing to decay. Instead, in a coalescence approach the invariant-mass distribution from the recombination of a light (strange) quark and a heavy quark can be quite narrower due to the constraint of the wave function. Another difference is the assumption of a thermal population of di-quarks that in the modelling acquire also a hydrodynamical radial and elliptic flows. The assumption in the model of local colour neutralization leads to a strong space-momentum correlation, which provides a substantial enhancement of the elliptic flow of the final-state charmed hadrons, affecting both their momentum and their angular distributions. This hadronization scheme has been applied to AA collisions [96] and very recently to pp collisions [97] showing a behavior of Λ_c^+ / D^0 similar to the coalescence approach, apart from the tendency to over estimate the D_s^+ production especially at low p_T .

5. *EPOS4(HQ)*

The EPOS Monte Carlo event generator [98, 99] is based on the assumption that hadronization in QCD is string-like below a certain critical energy density, while it exhibits thermal (QGP) behaviour above that density. The idea is that the critical density is not reached in e^+e^- collisions nor in low-multiplicity pp collisions. These systems can

therefore be described by a conventional Lund string fragmentation model (much like in PYTHIA, though EPOS has its dedicated implementation of string fragmentation). At higher energy densities, which are reached in high-multiplicity pp collisions and in heavy-ion collisions, EPOS invokes a QGP-like medium with non-zero temperature and hydrodynamic properties.

An elegant interpolation between the two limits is achieved via the *core-corona* picture [99, 100], in which dense (“core”) regions of phase space (above the critical density) are described via the QGP-like thermal modelling of particle production, while more dilute (“corona”) ones (below the critical density $\epsilon = 0.57 \text{ GeV}/\text{fm}^3$) are described by string fragmentation. Crucially, these two types of regions can coexist *within one and the same collision*, with a smooth transition between low core fractions at high impact parameters and high core fractions at central ones. In terms of observable consequences, this produces an overall modelling that reliably interpolates between vacuum-like string fragmentation in e^+e^- and low-multiplicity pp collisions and a QGP limit in central AA collisions.

Historically, the scattering modelling in EPOS was based on a zero-momentum limit of cut pomerons and hence did not aim at describing high- p_\perp jet fragmentation (or other perturbative scattering processes). This has changed with EPOS4, which incorporates both factorization for hard processes and saturation for the low- x scatterings. More specifically related to the purposes of this review, the main aspect of EPOS4HQ is the inclusion of the scattering dynamics of heavy quarks in the “corona” medium even in pp collisions and of hadronization via coalescence plus fragmentation [101, 102]. The hadronization mechanism employed is in many aspects very similar to the coalescence plus fragmentation approaches described in Sect. II B 4. The coalescence for heavy mesons and baryons is evaluated in the Wigner formalism, see Eq. 6. The wave function is a Gaussian and the excited states are included assuming a suppression like in the statistical model as in the Catania model. Heavy quarks not recombining with light partons undergo fragmentation. Similarly to the SHM-TAMU approach, all the possible excited states are considered, including the unobserved baryon states not listed in the PDG, which are predicted to exist by the quark model and lattice QCD. A more “technical” difference is the mass of the light quarks which in EPOS are taken to be $m_{u/d} = 0.1 \text{ GeV}$, while in the Catania, TAMU, and PHSD models values close to the constituent quark mass of about 0.33 GeV are used, reducing the violation of energy conservation in the coalescence process. Also EPOS4HQ has shown to generate for

pp collisions ratios of Λ_c^+/D^0 and Ξ_c^0/D^0 that are in fair agreement with the experimental data by ALICE and CMS, only if coalescence is included [101, 102]. Moreover, EPOS4HQ being a realistic fully dynamical approach showed that also the elliptic flow $v_2(p_T)$ of D^0 in pp collisions agrees with the data and origins from the scattering of charm quarks in the medium generated in high-multiplicity events.




FIG. 6: Λ_c^+/D^0 ratio obtained by three model calculations in pp collisions at $\sqrt{s} = 5.02$ TeV. Left panel: PYTHIA 8 MC generator with (dashed line) and without (solid line) the implementation of junction topologies. Middle panel: SHM with (band) and without (line) the inclusion of the additional charm baryon resonance states predicted by the RQM model. Right panel: Catania model in which charm quark hadronization is implemented via fragmentation only (line) or via fragmentation and coalescence (band).

III. HEAVY-FLAVOUR HADRONIZATION - EXPERIMENTAL RESULTS

In the following we explore a selection of experimental measurements on heavy-flavour production sensitive to heavy-quark hadronization. Firstly we discuss results in e^+e^- and $e^\pm p$ collisions. Then the measurements in hadronic collisions are presented using event multiplicity as the order criterion: minimum-bias pp collisions are discussed first and are followed by studies differential in multiplicities, which allow to bridge the pp collisions to both p-A and A-A collisions, as well as to e^+e^- collisions. Measurements in hadronic collisions sensitive to beam remnants and quantum-number conservation, which probe peculiar regions of phase space in which the fragmentation approach was already found (and expected) to not be effective, are discussed separately.

A. Production in ee and ep collisions and spectroscopy

Electron–positron collisions present many advantages to study the fragmentation process of heavy quarks. In e^+e^- collisions there is not an hadronic initial state, thus there are no concurrent partonic interactions nor beam remnants, and the centre-of-mass energy of the partonic system is known (up to radiative corrections) and coincides with the e^+e^- collision centre-of-mass energy. The $q\bar{q}$ pair is produced mainly in a colour-singlet topology and soft gluon emission can be described as the radiation of a colourless antenna [104]. On the other hand, e^+e^- collisions offer little sensitivity to study heavy-flavour hadron production in events in which heavy-quark production involves gluons in the hard scattering. The production cross section and properties of several charm-hadron species were measured at very different collision energies in e^+e^- collisions at both B-factories ($\sqrt{s} \sim 10.5 \text{ GeV}/c^2$) and in Z^0 -boson decays at LEP ($\sqrt{s} \sim 90 \text{ GeV}/c^2$) [103, 105–108].

A variable typically considered to constrain the heavy-quark fragmentation functions used in theoretical calculations is the beam-momentum fraction $x_p = 2p_{\text{HC}}/\sqrt{s/4 - M^2c^4}$. The x_p -differential cross section of several charm-baryon species measured by Belle [103], namely of Λ_c^+ , $\Lambda_c(2595)^+$, $\Lambda_c(2625)^+$, $\Sigma_c(2455)^0$, $\Sigma_c(2520)^0$, Ω_c^0 (cross section times branching ratio), Ξ_c^0 (cross section times branching ratio), are shown in Fig. 7. The Λ_c^+ , $\Sigma_c(2455)^0$, and $\Sigma_c(2520)^0$ are compared to PYTHIA calculations [109]. Overall, though differences between data and PYTHIA can be appreciated thanks to the high precision of the data, the Λ_c^+ and $\Sigma_c(2455)^0$ x_p -differential cross sections are reasonably well reproduced by PYTHIA both in magnitude and in shape. The $\Sigma_c(2520)^0$ cross section is instead underestimated by about a factor of two by PYTHIA, which also predicts a harder x_p distribution.

The precise theoretical knowledge of the total $c\bar{c}$ cross section allows the direct measurement of the fragmentation fraction of charm quarks to a given charm-hadron species, $f(c \rightarrow H_c)$, without the need to measure the cross section of the other charm-hadron species. At LEP it was verified (see e.g. ALEPH analysis in Ref. [105]) that the total charm-production cross section, obtained as the sum of the measured D^0 , D^+ , D_s^+ , and Λ_c^+ cross sections, and of an additional contribution for the unmeasured $\Xi_c^{+,0}$ and Ω_c^0 cross sections, assumed to be around 2% of the measured one, is consistent with the Standard Model expectation. In Ref. [69] charm-hadron production measurements in e^+e^- collisions at B factories [110–117] and in Z^0 -boson decays [105–107, 118, 119] were analysed together with




FIG. 7: Differential inclusive cross sections of charmed baryon production with and without radiative corrections measured by the Belle Collaboration [103]. The closed circles are shifted slightly to the left for clarity. Triangle points show PYTHIA predictions where all radiative processes are turned off.

data from photoproduction (PHP) and deep-inelastic scattering (DIS) in $e^\pm p$ collisions at HERA [120–124], and with first results from pp collisions at the LHC. As shown in Fig. 8, no significant difference emerged among the charm FF measured in the various collision systems and collision energies. In $e^\pm p$ and hadronic collisions charm-quark pairs are produced in hard-scattering processes from gluons, differently from e^+e^- collisions in which $g \rightarrow c\bar{c}$ splittings occurs only in a fraction of events. At LEP, the fraction of $Z \rightarrow$ hadrons events proceedings via $Z \rightarrow q\bar{q}g, g \rightarrow c\bar{c}$ is about 3%, representing less than 20% of events with charm in Z decays [105, 125–127]. The consistency of the FF measured in e^+e^- and $e^\pm p$ collisions was considered as a signal supporting the hypothesis of universality of the fragmentation fractions, which was expected to hold also in pp collisions at the LHC. First LHC data on D-meson production supported this hypothesis, which as will be discussed in next sections turned out not to be true.

Spectroscopy measurements provide important pieces of information for understanding heavy-flavour production and hadronization. The measured production yield and p_T -differential spectrum of a given heavy-flavour hadron species, H_Q , depends on the number and mass spectrum of existing hadron states energetically accessible, which determines both the direct-production probability of the given state at hadronization and the feed-down contribution. There is a large impact on the heavy-flavour baryon-to-meson ratio expected by models whether one assumes or not the existence of the rich set of excited states expected from the relativistic quark model (RQM) [51] (see Sect. II B 3), most of which have not yet been observed. Searching for new states in the charm sector has been a major part of the physics program of B factories, whereby exploiting the rather “clean” environment of e^+e^- collisions allows these states to be looked for both in the direct production from charm-quark hadronization and in the decay of beauty hadrons. A review of relevant spectroscopy measurements at B factories can be found in Ref. [130]. Despite the observation of several states, the number of known states is not comparable to that expected by the RQM. This remains valid also including the significant number of states detected for the first time in hadronic collisions at Tevatron and the LHC [131, 132]. At these colliders, as at LEP, several ground and excited states were discovered and studied also in the open-beauty sector, which is energetically almost precluded to B factories. As reported in Fig. 9, overall more than 70 new hadrons in the charm and beauty sectors were discovered at the LHC, out of which 19 “conventional” mesons, 30 conventional baryons, and 23 “exotic” hadrons,




FIG. 8: Charm fragmentation fraction to D mesons and Λ_c^+ in e^+e^- and $e^\pm p$ collisions calculated in Ref. [69] by combining measurements from CLEO [110, 111], ARGUS [112–114], BABAR [116, 117], Belle [115], OPAL [106, 118], ALEPH [105], DELPHI [107, 119], ZEUS [122, 123, 128, 129], and H1 [124]. In the calculation, the sum of the fragmentation fractions to all known weakly decaying ground states is constrained to unity and it is assumed that the sum of the fragmentation fractions to $\Xi_c^{+,0}$ and Ω_c^0 is a factor of about 0.136 that to Λ_c^+ in analogy to strange-quark fragmentation fractions to Ω^- , Ξ^- , and Λ^0 .

i.e. tetraquark and pentaquark candidates. However only for a few of these states information about the production yield is available. Whether further states exist remains an open question and a major goal of future experimental research at both hadronic and leptonic colliders. In hadronic collisions heavy-flavour baryon production may occur via additional processes than those effective in leptonic collisions. This further highlights the importance of measuring the relevant abundances of the various states in both collision systems.

The probability that a given state is formed can depend on the hadron internal structure and state quantum numbers, for the determination of which spectroscopy measurements are essential. Charm and beauty baryons are also good probes to study diquark effective degrees of freedom. Theoretical calculations suggested that heavy-flavour baryons can be




FIG. 9: Hadrons with charm and beauty quarks discovered at the LHC. Figure from [132].

interpreted rather simply as a bound state of a diquark and a heavy quark [130, 133], a picture that requires experimental confirmation via a systematic comparison of measured and predicted spectra. Reviews on the topic, including discussions extended to exotic states, can be found in Ref. [130, 131, 134–136].

An important example is given by the lower production yields of the isovector $\Sigma_c^{0,+,++}$ states compared to the isoscalar Λ_c^+ states in e^+e^- collisions. This can be appreciated looking at Belle result [103] in Fig. 10, which shows the direct cross sections of Λ_c^+ and $\Sigma_c^{0,+,++}$ states divided by the state spin-degeneracy factor as a function of the particle mass. The Λ_c^+ and $\Sigma_c^{0,+,++}$ states, which in terms of valence quarks are all composed of a charm quark and a pair of light u/d quarks, lie on two different exponential lines. In the string-fragmentation picture, charm baryons are formed in e^+e^- collisions via diquark-antidiquark pair creation from string breaks next to a c-quark string endpoint, whereby such diquark-antidiquark pair creation is modelled by a Schwinger tunnelling process. To form a $\Sigma_c^{0,+,++}$ state an isovector diquark is needed, whereas the isoscalar diquark is needed for Λ_c^+ states. Isovector diquarks have spin 1 and are heavier than isoscalar spin-0 diquarks, and thus the larger mass suppresses their production probability via the Schwinger mechanism. Though




FIG. 10: Charm-baryon direct production cross section scaled by the spin-degeneracy factor as a function of the baryon mass measured in e^+e^- collisions by Belle [103].

this argument might not take into account the possible role of dynamical diquark degrees of freedom [134], the observed difference of the production yields of hadron states with the same valence quarks is exemplary experimental evidence of the fact that the internal hadron structure can affect the production probability. The impact of this can depend on the properties of the collision system, both because the relative abundances of the hadron “building blocks” (quarks and diquarks) can differ in different systems and because of the emergence of concurrent formation processes that may overcome limitations and constraints set by the hadron internal structure. Whether diquarks could constitute relevant degrees of freedom in the QGP close to the hadronization phase, possibly affecting hadrochemistry also in the heavy-flavour sector [39, 96], is an open question. The structure of “exotic” hadrons is still unclear. Diquark degrees of freedoms could constitute relevant building blocks also for tetraquarks and pentaquarks production. On the other hand, it is also unknown if nuclear-type forces can bind mesons to other mesons or baryons in “molecular” states. The study of exotic state properties and production in different collision systems can therefore be an important direction for determining both their nature as well as the relevant degrees of freedom of the systems, as further discussed in Sect. IV.

B. Hadronic collisions: beam remnants and quantum-number conservation

Quantum-number conservation affects the relative abundances of the particle species produced at hadronization time leaving a trace that is more evident when phase-space for particle production is limited (e.g. hadronic collisions at low energies, particle decays) or in specific kinematic regions, e.g. close to beam rapidities. However, in high-energy hadronic collisions far from beam rapidities hadronization is not expected to be significantly influenced by the quark content of the beam particles. Of course, quantum-number conservation dictates a departure from the particle ratios observed in a “vacuum-like” system as e^+e^- , and it spoils the effectiveness of factorization approach using e^+e^- FF in certain kinematic ranges. In many of these cases, the modelling of hadronization involves the recombination of valence quarks with other quarks produced in the event. Effects that can not be reconciled with a modelling of hadronization via universal fragmentation fractions/functions, were already observed at FNAL in π -A collisions. An example is the so-called beam-remnant drag [137], i.e. the tendency in a hadronic collision to produce at forward rapidity particles that share a valence quark (or diquark) with the remnant of the projectile moving in the same direction. Focusing only on the heavy-flavour sector, asymmetries in the production of D^-/D^+ [138–141], D_s^-/D_s^+ [140, 142], Λ_c^+/Λ_c^- [140, 143] and $\Lambda_b^0/\bar{\Lambda}_b^0$ [144] in various hadronic collisions have been observed. In Fig. 11 the asymmetry $A = \frac{\sigma_{D^-} - \sigma_{D^+}}{\sigma_{D^-} + \sigma_{D^+}}$ measured in π^- -nucleus collisions (using platinum and diamond foils as target) by the E791 Collaboration is shown as a function of the Feynman x_F variable [141]. The positive asymmetry values emerging at large x_F indicate that the production of hadrons sharing valence quarks with beam hadron (the pion) is favoured.

The measurement is compared to predictions based on two PYTHIA 5.7 tunes [109], to the prediction for charm quarks by NLO QCD [145, 146], and a calculation involving intrinsic charm by Vogt and Brodsky [147]. The NLO calculation shows an asymmetry ratio almost flat in x_F and close to unity. The model from Vogt and Brodsky, in this case specifically calculated for the E791 beam momentum, presents a shape of the asymmetry A similar to the data one, however, the prediction is too low at all x_F . The PYTHIA predictions are shown with two different tunes. The dashed line shows the prediction from the PYTHIA generator, which is significantly higher than the experimental data for $-0.2 < x_F < 0.4$. This is because PYTHIA predicts a higher overall production ratio of D^- to D^+ than is




FIG. 11: The D^\pm -meson asymmetry A (see text) measured in π^- -nucleus (C,Pt foils) collisions as a function of x_F compared to model calculations [141].

seen in the data. A tuned PYTHIA prediction that is consistent with the experimental data is shown as the solid line. The tuning included an increased mass of the c quark from $m_c = 1.35 \text{ GeV}/c^2$ to $m_c = 1.7 \text{ GeV}/c^2$ and an increased average primordial k_t^2 of the partons from $(0.44 \text{ GeV}/c)^2$ to $(1.0 \text{ GeV}/c)^2$. This decreases the likelihood that the remnant d quark can combine with the \bar{c} quark with a small enough invariant mass to collapse to a D^- meson. Anyhow, in order to reproduce the data, models must assume that the heavy quark hadronizes via recombination with some other parton already present in the system, in this case belonging to the beam remnant [93, 148–150].

C. Proton–proton collisions

As several measurements show [151–161], p_T -differential cross sections of open charm- and beauty-meson production in pp collisions are successfully described by quantum chromodynamics (QCD) calculations based on the factorization of the soft (non-perturbative) and hard (perturbative) processes and making use of FFs parameterized to reproduce measurements performed in e^+e^- or ep collisions. Implicitly, it is assumed in these calculations

that the fragmentation and hadronization of charm and beauty quarks are universal processes independent of the collision system, or at least that they are approximately the same in e^+e^- and pp collisions. The charm-meson p_T -integrated cross sections measured by several Collaborations in different colliding systems were used to compute the ratios of production yields among the different D-meson species (D^0 , D^+ , D_s^+) [157, 162–165]. The prompt $D_s^+/(D^0 + D^+)$ ratio represents the FF of charm quarks to charm-strange mesons f_s divided by the FF to non-strange charm mesons $f_u + f_d$, given that all D^{*+} and D^{*0} mesons decay to D^0 and D^+ mesons, and D_s^{*+} mesons decay to D_s^+ mesons. The charm-quark fragmentation-fraction ratios $f_s/(f_u + f_d)$ from the ALICE [157, 166], H1 [124], ZEUS [120], and ATLAS [167] Collaborations are shown in the upper panel of Fig. 12. All the values are compatible within uncertainties and with the average of measurements at LEP [108]. The experimental data is also compared to the value obtained from a PYTHIA 8 simulation of pp collisions using the Monash tune [11], which is found to be compatible with the data within the uncertainties. The fragmentation fractions of beauty quarks to beauty-strange mesons divided by the one to non-strange beauty mesons computed by the ALICE [157], CDF [13], LHCb [168, 169], and ATLAS [170] Collaborations are also reported in the lower panel of Fig. 12. All the $f_s/(f_u + f_d)$ values measured in pp and $p\bar{p}$ collisions are found to be compatible with the LEP average, computed by the HFLAV Collaboration [171], and with the value obtained from PYTHIA 8 simulation of pp collisions with the Monash tune. With a more recent measurement, the CMS Collaboration observed a mild p_T dependence ($\sim 10\%$) of B_s^0/B^0 ratio in the p_T interval 12–18 GeV/ c followed by a flat high- p_T trend, while the ratio B^-/B^0 is found to be consistent with unity and independent of p_T and rapidity [172]. In general, the production cross sections and cross-section ratios of charm and beauty mesons do not show evidences of violation of the assumption of universality of the fragmentation and hadronization processes. However, recent measurements of charm and beauty baryon-to-meson production ratios and fragmentation fractions in pp collisions at LHC energies showed significant deviations from the values measured at e^+e^- and ep colliders, demonstrating that the assumption of universality of the hadronization process across collision systems has to be reconsidered.

The Λ_c^+/D^0 baryon-to-meson yield ratio as a function of p_T at midrapidity in pp collisions at $\sqrt{s} = 5.02$ TeV [173] is shown in the top-left panel of Fig. 13. The ratio is measured to be 0.4-0.5 at low p_T , and decreases to around 0.2 at high p_T . The strong p_T -dependence of the




FIG. 12: Charm-quark (top panel) and beauty-quark (bottom panel) fragmentation-fraction ratio $f_s/(f_u + f_d)$ measured by several collaborations in pp, $p\bar{p}$ (beauty case only), and $e^\pm p$ (charm case only) collisions, compared to the averages of LEP measurements [108, 171]. The values obtained from PYTHIA 8 simulations of pp collisions with Monash tune [11].

Λ_c^+/D^0 ratio contrasts with the ratios of strange and non-strange D mesons, which do not show a significant p_T dependence. This indicates that, interpreting the ratio within a pure fragmentation scheme, the fragmentation functions of baryons and mesons must differ significantly. The data are compared with model calculations in which, as described in Sect. II, different hadronization processes are implemented. The Monash tune of PYTHIA 8 [11] predicts an integrated value of about 0.065 for the Λ_c^+/D^0 ratio, with a mild p_T dependence. This model calculation significantly underestimates the data at low p_T by a factor of about 5–10, while at high p_T the discrepancy is reduced to a factor of about 2. The expectations of models including processes that enhance baryon production (see Sect. II B), such as PYTHIA 8 with QCD-based CR including junction string topologies [33], SHM+RQM [38], QCM [35], and Catania [36] are also shown. All of these models qualitatively reproduce the data. The data hints at a decrease of the Λ_c^+/D^0 yield ratio in the interval $0 < p_T < 1$ GeV/ c , though a more precise measurement is needed to reach a firm conclusion about the actual trend and the possible discrepancy with model predictions. The Λ_c^+/D^0 yield ratio at $\sqrt{s} = 5$ TeV also by the CMS Collaboration in $|y| < 1$. A first measurement in the $5 < p_T < 20$ GeV/ c [174] was recently followed by a second one extended in p_T down to 3 and up to 30 GeV/ c [73]. In the p_T region covered by both experiments, the results are consistent with each other [78, 175]. The Λ_c^+/D^0 ratio was measured also at $\sqrt{s} = 7$ and 13 TeV by ALICE: within uncertainty, no significant energy dependence was observed [158, 176]. The more recent CMS results at $\sqrt{s} = 5$ TeV and ALICE results at 13 TeV, which extends up to $p_T = 24$ GeV/ c , indicate that the Λ_c^+/D^0 ratio decreases below 0.2 at high p_T , further approaching the values measured in e^+e^- collisions.

Another important measurement related to the enhancement of the Λ_c^+ baryon performed by the ALICE Collaboration, is the measurement of the $\Sigma_c^{0,+,++}$ baryon at midrapidity in pp collisions at $\sqrt{s} = 13$ TeV [176]. As discussed in Sect. III A, the production of $\Sigma_c^{0,+,++}$ states is suppressed with respect to Λ_c^+ -states [103] in e^+e^- collisions. As shown in the top-right panel of Fig. 13, in pp collisions the $\Sigma_c^{0,+,++}/D^0$ ratio is close to 0.2 for $2 < p_T < 6$ GeV/ c , and decreases with p_T down to about 0.1 for $8 < p_T < 12$ GeV/ c , though the uncertainties do not allow firm conclusions about the p_T dependence. From Belle measurements (Table 4 in Ref. [103]), the $\Sigma_c^{0,+,++}/\Lambda_c^+$ ratio in e^+e^- collisions at $\sqrt{s} = 10.52$ GeV can be evaluated to be around 0.17 and, thus, the $\Sigma_c^{0,+,++}/D^0$ ratio can be estimated to be around 0.02. Therefore, a remarkable difference is present between pp and e^+e^- collision

systems. In Ref. [176] the $\Sigma_c^{0,+,++}$ feed-down fraction for Λ_c^+ with $2 < p_T < \text{GeV}/c$ was measured to be $\Lambda_c^+ \leftarrow \Sigma_c^{0,+,++}/\Lambda_c^+ = 0.38 \pm 0.06$ (stat) ± 0.06 (syst), a significantly larger value than the $\Sigma_c^{0,+,++}/\Lambda_c^+$ ratio measured by Belle and the ~ 0.13 expectation from PYTHIA 8 Monash tune simulations. This indicates a larger increase of the $\Sigma_c^{0,+,++}/D^0$ ratio than of the direct- Λ_c^+/D^0 ratio from e^+e^- to pp collisions. The larger feed-down from $\Sigma_c^{0,+,++}$ partially explains the difference between the Λ_c^+/D^0 ratios in pp and e^+e^- collisions. It suggests that the suppression of $\Sigma_c^{0,+,++}$ states observed in e^+e^- collisions, which in the Lund string-fragmentation picture is ascribed to the lower production yield of spin-1 than spin-0 diquarks in string breaking, is absent or reduced in pp collisions. In the models that provide a fair description of the Λ_c^+/D^0 ratio in pp collisions this suppression mechanism is absent or heavily reduced, and a sizeable contribution to Λ_c^+ production from strong decays of $\Sigma_c^{0,+,++}$ states is expected. As shown in Fig. 13, the QCD-based CR-BLC (for which the three variations defined in Ref. [33] are considered), SHM+RQM, and Catania models describe, within uncertainties, both the Λ_c^+/D^0 and $\Sigma_c^{0,+,++}/D^0$ ratios. In the SHM, only the hadron mass and spin degeneracy factor determine the hadron yields. In all these models the production of $\Sigma_c^{0,+,++}$ (2455) is expected to increase by significant factors in pp with respect to e^+e^- collisions and to become comparable or even larger than that of direct Λ_c^+ . In Fig. 14 it is illustrated how the current measurements can provide useful constraints for a better tuning of the PYTHIA 8 QCD-based CR-BLC parameters relating to the production of spin-1 compared to spin-0 charm-light diquarks. When the charm-light diquark is coupled to a quark to form a baryon, the coupling in $l = 0$ state of a diquark with spin=0 cannot result in baryons with spin=3/2, which are instead possible with spin=1 diquarks. Excited Λ_c^+ and Σ_c states with spin=3/2 decay preferentially to Λ_c^+ rather than to $\Sigma_c^{0,+,++}$ (2455) [49]. Therefore, increasing the probability of producing spin=1 charm-light diquarks changes the feed-down contribution to $\Sigma_c^{0,+,++}$ and Λ_c^+ , effectively resulting in a reduction of the $\Sigma_c^{0,+,++}/\Lambda_c^+$ ratio. Thus one can significantly improve the description of the measured feed-down contribution from $\Sigma_c^{0,+,++}$ to Λ_c^+ production in PYTHIA by increasing the probability of spin-1 charm-light diquark formation in junctions. In PYTHIA 8, this probability is regulated by the parameter `probQQ1toQQ0join`, which dictates the suppression of forming a junction diquark with spin-1 compared to spin-0, acting on top of spin-state counting that dictates a 3-to-1 enhancement. The parameter `probQQ1toQQ0join` allows for different suppression factors given the heaviest flavour involved in the junction diquark

formation is up/down, strange, charm or bottom. A value close to zero implies a large suppression of spin-1 junction diquarks, while `probQQ1toQQ0join=1` implies no suppression. Though the data uncertainties do not allow a fine tuning of the charm `probQQ1toQQ0join` parameter, values around 0.5 or higher seem preferable as seen in Fig. 14. Note this is in contrast to the parameter `probQQ1toQQ0` which determines the spin-1 to spin-0 probability for diquark-antidiquark production from standard string breaks, which has a default LEP-tuned value of 0.0275. This however is not entirely surprising as diquark-antidiquark pair creation must be light-flavoured, and thus `probQQ1toQQ0` will only effect light diquark production. Such a large suppression of spin-1 light diquarks can be justified by mass difference arguments and the smaller binding energy of spin-1 diquarks. Contrastingly in a heavy-light diquark that is formed in a junction, one would expect the spin splitting to almost decouple. Nonetheless there remains large ambiguity in `probQQ1toQQ0join` in the light-sector, and `probQQ1toQQ0join` values for all flavours were not well constrained for the default PYTHIA values nor the QCD-based CR tunes. Future measurements of the production of excited states, in particular of $\Lambda_c^+(2595)$, $\Lambda_c^+(2625)$ and $\Sigma_c^{0,+}(\text{2520})$ will be useful to constrain this parameter, as illustrated in Fig. 14 below.

The ALICE Collaboration extended the measurement of charm-baryon production to baryons with strange quarks among the constituent quarks, measuring the $\Xi_c^{+,0}$ cross section in pp collisions at $\sqrt{s} = 5.02$ TeV [179] and $\sqrt{s} = 13$ TeV [180] and the Ω_c^0 [177] cross section times branching ratio in pp collisions at $\sqrt{s} = 13$ TeV. The bottom left panel of Fig. 13 shows the $\Xi_c^{+,0}/D^0$ ratios measured as a function of p_T at midrapidity in pp collisions at $\sqrt{s} = 13$ TeV. The values observed are generally lower than those of the Λ_c^+/D^0 ratio, but the p_T dependence is similar. The PYTHIA 8 Monash tune significantly underestimates the data by a factor of 23–43 in the low- p_T region and by a factor of about 5 in the highest p_T interval. All three CR modes give a similar magnitude and p_T -dependence of $\Xi_c^{+,0}/D^0$ and predict a larger ratio with respect to the Monash tune. However, differently from what is observed for the Λ_c^+ and the $\Sigma_c^{0,+}$ baryons, they underestimate the $\Xi_c^{+,0}/D^0$ ratio by a factor 4–9 for $p_T < 4$ GeV/ c . At higher p_T the measured $\Xi_c^{+,0}/D^0$ ratio is closer to PYTHIA 8 calculations. As the CR-BLC models underpredict the $\Xi_c^{+,0}/D^0$ ratio despite well describing Λ_c^+/D^0 , the source of this discrepancy is primarily assumed to be the strange content of the $\Xi_c^{+,0}$ baryon, where we suspect strangeness enhancement effects particularly at low p_T . There have been some models such as Rope hadronization [47] which aim to implement a




FIG. 13: Λ_c^+/D^0 (top left), $\Sigma_c^{0,+,++}/D^0$ (top right) $\Xi_c^{+,0}/D^0$ (bottom left), and Ω_c^0/D^0 (bottom right) yield ratios measured by ALICE [173, 176, 177] as a function of p_T in pp collisions in comparison with model calculations [11, 33, 36, 38, 178].

strangeness enhancement mechanism, however the rope model thus far has not been able to describe both the $\Xi_c^{+,0}/D^0$ and Λ_c^+/D^0 ratios simultaneously (or equivalently stated, it cannot describe the $\Xi_c^{+,0}/\Lambda_c^+$ ratio). The SHM+RQM model [38], which captures the magnitude and p_T dependence of the Λ_c^+/D^0 and $\Sigma_c^{0,+,++}/D^0$ yield ratios, also underestimates the $\Xi_c^{+,0}/D^0$ ratio. The measured ratios are also compared to the QCM [35] and the Catania [36, 37] models that include hadronization via coalescence and reproduce well the Λ_c^+/D^0 and

$\Sigma_c^{0,+,++}/D^0$ ratios. They both tend to underestimate the data though, considering the uncertainties, the Catania model remains close to the measured values over the whole p_T interval. Another interesting observation is given by the fact that the $\Xi_c^0/\Sigma_c^{0,+,++}$ ratio shown in Ref [180] is described well by the default PYTHIA 8 Monash tune [11], which significantly underestimates both $\Xi_c^{+,0}/D^0$ and $\Sigma_c^{0,+,++}/D^0$ ratios. Though this could be accidental (the predicted value remains to be explained along with its dependence on the two almost identical particle masses, and the assumed feed-down contributions), it may also signal the removal of a similar suppression factor affecting both Ξ_c^0 and $\Sigma_c^{0,+,++}$ production in e^+e^- collisions. In particular, in most calculations [134], a similar mass is obtained or assumed for $S=1$ (ud,uu,dd) diquarks as contained in $\Sigma_c^{0,+,++}$ and $S=0$ (ds) diquarks as in Ξ_c^0 . As discussed for the $\Lambda_c^+ \leftarrow \Sigma_c^{0,+,++}/\Lambda_c^+$ ratio, this could suggest that light diquarks are more easily produced in pp than e^+e^- collisions via other processes than the Schwinger mechanism (e.g. colour reconnections or coalescence), or that in pp collisions charm-baryon formation does not proceed via the combination of a charm quark with a light diquark. As mentioned in Sect. [?], the coalescence mechanism can be factorized in terms of a formation of diquark recombining with a further quark. In the limit of negligible binding energy this would correspond to the coalescence model already discussed. However, this is different from the assumption of the existence of a thermal yield of diquarks with masses that are not simply the sum of the two quark masses. In this respect it is also argued in Ref. [181] that a further enhancement of $\Xi_c^{+,0}/D^0$ ratio could be due to the large attraction of the us and ds diquark channel with respect to the ud one which is suggested by a relativistic quark model with a potential having a large screened mass as extracted from recent LQCD data. Introducing such an additional coalescence component in the Catania model could strongly improve its agreement with experimental data [181], but within the current experimental data uncertainties no conclusion can be drawn. Clarifying the role of light and heavy diquarks will be important for understanding hadronization in pp as well as in heavy-ion collisions, where diquarks could also be effective degrees of freedom of the system close to the phase transition [96].

The Ω_c^0 baryon is composed of a charm quark and two strange quarks. As it has just been discussed, most of the models can describe the Λ_c^+ data better than $\Xi_c^{+,0}$ data. This signals a possible difficulty with charm-strange baryons, hence the measurement of Ω_c^0 production represent a crucial step to constrain models and understand whether strange quarks, or




FIG. 14: Left: comparison of the fraction of Λ_c^+ from $\Sigma_c^{0,+,++}(2455)$ decay measured as a function of p_T with expectations from PYTHIA 8. The vertical bars on the data points represent the total uncertainty, quadratic sum of statistical and systematic uncertainties.

For PYTHIA 8 with CR-BLC, the results obtained when the value of the charm probQQ1toQQ0join parameter, which regulates the probability that junction diquarks containing charm have spin=1 or spin=0, is increased for charm-light diquarks from the default value of 0.0275 to 1, are shown. Right: expectation for the

$$\Sigma_c^{0,+,++}(2520)/\Sigma_c^{0,+,++}(2455) \text{ ratio for the same cases.}$$

strange diquarks, play a peculiar role in charm-baryon formation in pp collisions. Moreover, following what discussed above and in Sect. III A concerning the $\Xi_c^0/\Sigma_c^{0,+,++}$ and $\Lambda_c^+/\Sigma_c^{0,+,++}$ ratios, the comparison of the relative abundances of $\Xi_c^{+,0}$ and Ω_c^0 in pp and e^+e^- collisions can provide further information about the role of diquarks because it can be sensitive to the different mass values of $S = 1$ (ss) and $S = 0$ (sd, su) diquarks [51]. The Ω_c^0/D^0 ratio was recently measured by the ALICE Collaboration [177] and is shown in the bottom right panel of Fig 13, although without an absolute normalization because of the lack of absolute measurements of the branching ratios of Ω_c^0 decays. The uncertainties do not allow conclusions about its possible dependence on p_T . The data are compared with model expectations that were obtained by scaling the Ω_c^0/D^0 ratio predicted by the models by an estimate of the BR of the $\Omega_c^0 \rightarrow \Omega^- \pi^+$ decay channel, $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) = 0.51\%_{-0.31\%}^{+2.19\%}$ [182].

The uncertainty band of the models represents the BR uncertainty, which is estimated considering other BR estimations reported in Refs. [182–187]. Only for the Catania model the specific uncertainty of the model itself are also included in the uncertainty band [36]. In the bottom panels, the ratios of the various models and of the data to the Catania prediction are shown. The expectations of the models differ significantly, even by orders of magnitude, demonstrating the sensitivity of the measured ratios to the implementation of the charm hadronization process in the models. The Monash [11] and CR-BLC [33] tunes of PYTHIA 8, as well as the QCM [35] model underestimate the data significantly. The Monash tune expects a $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) \times \Omega_c^0/D^0$ ratio increasing with p_T from about 4×10^{-7} to about 1×10^{-5} . The CR-BLC model enhances the ratio by a factor of 12 to 34 with respect to the Monash tune. The prediction of the QCM is larger than that of the CR-BLC model, but it is lower than the data by more than 1.8σ . The Catania model [36] is again consistent with the data. The Ω_c^0/D^0 ratio decreases with p_T in the measured p_T range in the CR-BLC, QCM, and Catania models, oppositely to what is expected by Monash. The $\Xi_c^{+,0}$ and Ω_c^0 measurements provide important constraints to models of charm quark hadronization in pp collisions, being in particular sensitive to the description of charm-strange baryon production in the colour reconnection approach, and to the possible contribution of coalescence to charm quark hadronization in pp collisions. It is interesting to note that in the Catania model, the contribution from fragmentation is subdominant for $\Xi_c^{+,0}$ and Ω_c^0 , and the main contribution comes from a pure coalescence mechanism, hence these baryon-to-meson ratios are very sensitive to the hadronization process and to the modelling of coalescence. Using the Ξ_c^0 [180] and Λ_c^+ [176] measurements, the ratios $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) \times \sigma(\Omega_c^0)/\sigma(\Lambda_c^+)$ and $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) \times \sigma(\Omega_c^0)/\sigma(\Xi_c^0)$ of the cross sections integrated in the Ω_c^0 measured p_T interval were calculated and are compared with the values measured in e^+e^- collisions at $\sqrt{s} = 10.52$ GeV by Belle, obtained from the cross sections reported in Table 1 of Ref. [103]. Though the limited p_T and rapidity ranges of the ALICE measurement do not allow for a direct comparison of the pp and e^+e^- data, the ratios measured by ALICE as reported in Tab. 1 of Ref. [177] are larger by a factor of $8.7 \pm 2.2(\text{stat.}) \pm 0.9(\text{syst.})$ and $4.7 \pm 1.3(\text{stat.}) \pm 0.5(\text{syst.})$ for the $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) \times \sigma(\Omega_c^0)/\sigma(\Lambda_c^+)$ and $\text{BR}(\Omega_c^0 \rightarrow \Omega^- \pi^+) \times \sigma(\Omega_c^0)/\sigma(\Xi_c^0)$, respectively. This difference represents further evidence that the hadronization process differs in pp and e^+e^- collisions and is sensitive to the density of quarks, colour charges, and system size.

The low- p_T charm baryon enhancement is reflected in the p_T -integrated yields and their ratios to the D^0 meson. The left panel of Fig. 15 shows for pp collisions at $\sqrt{s} = 5.02$ TeV the p_T -integrated production cross sections at midrapidity per unit of rapidity for various open- and hidden-charm mesons (D^+ , D_s^+ , D^{*+} , and J/ψ) [157, 188, 189] and baryons (Λ_c^+ and Ξ_c^0) [77, 179], taking the average of particles and antiparticles, and normalizing to the D^0 meson. The experimental data is compared with results of pp simulations done with PYTHIA 8 using both the Monash tune [11] and the tunes implementing CR-BLC [33]. For the open charm meson ratios, the PYTHIA 8 predictions obtained with the different tunes are fairly similar and describe the data within uncertainty. The value of the D^{*+}/D^0 ratio obtained with Monash2013 setting `StringFlav : mesonCvector = 1.5` is also reported. As anticipated in Sect. II A, values of this parameter around 1.5 or larger are preferable to better describe the data, as shown in the right panel of the same figure for the p_T -differential D^{*+}/D^0 ratio. However, this is not an artefact of the modelling of D^{*+} pp collision environments. A discrepancy is existent also when considering e^+e^- collisions data from LEP and is a consequence of the parameters `StringFlav:mesonCvector` and correspondingly `StringZ:rFactC` being mistuned. The default value of 0.88 for `StringFlav:mesonCvector` should instead be closer to ~ 1.5 . Contrary to the meson case, and as expected from what discussed about the low- p_T trend of the baryon-to-meson ratios shown in Fig. 13, significant differences between the model expectations and data are observed when considering the baryon-to- D^0 ratios. The Monash 2013 tune is observed to underestimate the Λ_c^+/D^0 and Ξ_c^0/D^0 ratios by nearly 8σ and 2.3σ , respectively. Comparatively, the CR tunes provide larger baryon-to-meson ratios with the Mode 2 tune well reproducing the Λ_c^+/D^0 ratio. Nonetheless, they still underestimate the Ξ_c^0/D^0 ratio by about 2σ , which again is unsurprising when looking at the p_T distributions in Fig. 13. For the $J/\psi/D^0$ ratio the CR tunes provide a better description than the Monash tune, however, all PYTHIA 8 tunes underestimate the measurement. One should note that in the simulations, as in the experimental measurement, the J/ψ cross section consists of the prompt and beauty feed-down contributions. From these results, one can conclude that the high baryon-to-meson ratios (Λ_c^+/D^0 , $\Sigma_c^{0,+,++}/D^0$, $\Xi_c^{+,0}/D^0$, and Ω_c^0/D^0), with magnitudes much larger than those of FF ratio measured in e^+e^- collisions, clearly indicate that the hadronisation process is not universal and that modelling it solely with FF and FFunc determined from e^+e^- data fails already in pp collisions. The right panel of Fig. 15 shows the same experimental data compared in

addition to the SHM+RQM and Catania models. For the SHM+RQM for a hadronisation temperature $T_h = 170$ MeV. Similarly to what is observed for the p_T differential ratios, the SHM+RQM model describes the Λ_c^+ measurements but underestimates the Ξ_c^0 one. On the other hand, the Catania model overpredicts the production of the Λ_c^+ baryon but captures the production of the Ξ_c^0 baryon. For the Catania model the D^{*+}/D^0 value shown is the one for the mesons coming from coalescence, because the fragmentation functions employed are inclusive and give only the total contribution to D meson including the D^* feed-down. The significantly large Λ_c^+/D^0 is due to the combination of both a lower D^0 and a larger Λ_c^+ yield with respect to experimental data. However, it has to be noticed that the value in the plot is the original prediction employing the width corresponding to the mean square radii of hadrons from the quark model, hence without any free parameter; a moderate modification of the width parameter would allow to get quite close to the data.




FIG. 15: p_T integrated production cross sections of the various charm meson and baryon species per unit of rapidity at midrapidity normalized to that of the D^0 meson measured by ALICE in pp collisions at $\sqrt{s} = 5.02$ TeV [190]. The measurements are compared with different tunes of PYTHIA 8 calculations. The grey marker shows the values of D^{*+}/D^0 ratio obtained with Monash 2013 PYTHIA8 tune after setting the parameter StringFlav:mesonCvector to 1.5, which, as shown in the right panel, allows to better describe the p_T -differential D^{*+}/D^0 ratio measured by ALICE in pp collisions at $\sqrt{s} = 13$ TeV [158] (see text for details).




FIG. 16: Left: same as in left panel of Fig. 15 but with additional comparison to the SHM+RQM [38] and Catania [36] models. Right: charm-quark fragmentation fractions into charm hadrons measured in pp collisions at $\sqrt{s} = 5.02$ TeV [190] and at $\sqrt{s} = 13$ TeV [158] in comparison with experimental measurements performed in e^+e^- collisions at LEP and at B factories, and in ep collisions at HERA [69].

The charm FF, $f(c \rightarrow H_c)$, measured by ALICE in pp collisions at $\sqrt{s} = 5.02$ TeV [190] and at $\sqrt{s} = 13$ TeV [158], are displayed in Fig. 16 together with values derived from experimental measurements performed in e^+e^- collisions at LEP and B factories and in ep collisions [69]. An increase by about a factor of 3.3 of the charm FF to the Λ_c^+ baryon from e^+e^- and ep to pp collisions, with a concomitant decrease by about a factor 1.4–1.2 for the FF to D mesons is observed. The significance of the difference is about 5σ for Λ_c^+ baryons and 6σ for D^0 mesons. In previous measurements in e^+e^- and ep collisions, no value for the charm FF to $\Xi_c^{+,0}$ was obtained. In the analysis performed in Ref. [69] to estimate charm FF, the Ξ_c^0 and Ξ_c^+ yields were assumed to be equal and estimated according to the assumption $f(c \rightarrow \Xi_c^+)/f(c \rightarrow \Lambda_c^+) = f(s \rightarrow \Xi^-)/f(s \rightarrow \Lambda^0) \sim 0.066$ [69]. The fraction $f(c \rightarrow \Xi_c^0)$ was measured for the first time in pp collisions by ALICE, which for the Ξ_c^0/Λ_c^+ FF ratio obtained the value $f(c \rightarrow \Xi_c^0)/f(c \rightarrow \Lambda_c^+) = 0.39 \pm 0.07(\text{stat})_{-0.07}^{+0.08}(\text{syst})$ [179]. The probability of a c quark to hadronize in a Ξ_c^0 baryon is measured to be comparable to the probability to hadronize in a D_s^+ meson, suggesting that the sum of the $c \rightarrow \Xi_c^0$ and $c \rightarrow \Xi_c^+$ fragmentation fractions could be larger than the $c \rightarrow D_s^+$ one. Recently, the ALICE

Collaboration measured the charm-quark fragmentation fractions in pp collisions at $\sqrt{s} = 13$ TeV [158]. In addition to the charm-quark fragmentation fractions into D^0 , D^+ , D_s^+ , D^{*+} , Λ_c^+ , and Ξ_c^0 hadrons, also the results for the fragmentation into J/Ψ mesons and Ξ_c^+ and $\Sigma_c^{0,+}$ baryons were reported. The results are compared with those in pp collisions at $\sqrt{s} = 5.02$ TeV and no significant energy dependence is observed within the uncertainties. Overall, charm quarks hadronize into baryons approximately 35-40% of the time. These results confirm that the baryon enhancement at the LHC with respect to e^+e^- collisions is caused by different hadronization mechanisms at play in the parton-rich environment produced in pp collisions. The difference between the fragmentation fractions measured at midrapidity in pp collisions at the LHC and those measured in e^+e^- collisions provide strong evidence that the parton-to-hadron transition is not a universal process that can be modelled only with universal (colliding-system independent) fragmentation functions.

The LHCb and CMS Collaborations, and earlier the CDF Collaboration, made similar observations in the beauty sector when computing the Λ_b^0 to $B^{0,-}$ yield ratios [13, 168, 169, 172, 191–195] in pp ($p\bar{p}$ for CDF) collisions at various centre-of-mass energies. As shown in the left panel of Fig. 17, the ratio is observed to strongly depend on p_T and approaches LEP value at high p_T , which can be estimated to be $\Lambda_b^0/B^0 = 0.22 \pm 0.03$ [171]. At low p_T it is significantly higher than in e^+e^- collisions, reaching approximately twice the value measured at LEP for both the CDF and LHCb experiments. It does not show variations with pseudorapidity, within the LHCb acceptance of pseudorapidity $2 < \eta < 5$. The ALICE Collaboration measured the production cross sections of D^0 and Λ_c^+ hadrons originating from beauty-hadron decays at midrapidity in pp collisions at a centre-of-mass energy $\sqrt{s} = 13$ TeV [196]. A trend consistent with the one of $\Lambda_b^0/B^{0,-}$ measured by LHCb at forward rapidity is observed. In the left panel of Fig. 17 the Λ_b^0/B^0 measured by the LHCb Collaboration [194] is compared with PYTHIA 8 calculations using different tunes. The cyan line represents the Monash tune computed for the rapidity window 2–4.5, while the blue solid line shows one of the QCD-based CR-BLC tunes in the same rapidity range. This comparison confirms that the experimental measurement is larger than what is expected by models based on fragmentation tuned on e^+e^- collisions. On the other hand, given the inclusion of junction string topologies and hence junction baryons in the CR-BLC PYTHIA 8 models, though the trend of producing an enhancement of Λ_b^0 at low p_T and reducing to LEP values at high p_T is predicted, the magnitude of the enhancement at low p_T is too large and overpredicts

the experimental data. Such a discrepancy remains an active question in junction string modelling. An additional point that is important to highlight is the comparison between the expectations of PYTHIA 8 with CR-BLC in different rapidity ranges shown in the same figure. Simulations of PYTHIA 8 with CR-BLC for $|y| < 0.5$ (dashed blue line) are compared to the forward rapidity one ($2 < |y| < 4.5$, solid blue line). The results indicate that the model does not expect any dependence on rapidity. Additionally, the expectations of a SHM approach with and without the set of b-hadron states predicted by the RQM to exist beyond the currently measured spectrum listed by the particle data group are also shown [50]. The substantial gap between the LHCb data and the model calculation obtained with the PDG scenario (dashed dark-red line) is largely overcome by the feeddown of the “missing” baryons included in the RQM calculation (solid red line), leading to a better description of the experimental data at intermediate p_T , while overpredicting the measurements at low and high p_T . It would also be interesting to see model calculations including coalescence, like the Catania model, to verify whether different baryon enhancements, both in the charm and beauty sector, might be expected in different rapidity windows. Future measurements of other beauty baryons (Ξ_b , Ω_b) are necessary to investigate a possible enhancement in pp collisions for strange-beauty baryons.

The LHCb Collaboration also published differential measurements of the asymmetry between Λ_b^0 and $\bar{\Lambda}_b^0$ baryon production rates in pp collisions at centre-of-mass energies of $\sqrt{s} = 7$ TeV and $\sqrt{s} = 8$ TeV. The production asymmetry is defined according to the quantity A_{prod} , which represent the relative difference between the production rates of Λ_b^0 and $\bar{\Lambda}_b^0$. The production asymmetry is measured both in intervals of rapidity in the range $2.15 < y < 4.10$ and transverse momentum in $2 < p_T < 27$ GeV/ c . The results are incompatible with symmetric production with a significance of 5.8σ assuming no CP violation in the decay. The asymmetry is increasing with rapidity and there is evidence for a trend with a significance of 4σ . The comparison between data and various PYTHIA 8 models is shown in the right panel of Fig. 17. Among the several tunes of PYTHIA, only that with CR-BLC approximation (red boxes) shows a good agreement with the measurement. The Monash tune (yellow boxes) and the gluon move CR (blue boxes) predict asymmetries that are too large, exhibiting the strongest deviation at low transverse momentum and for the widest rapidity range investigated [197]. In PYTHIA, a key source of low p_T Λ_b^0 production in pp collisions at large rapidity is the combination of a b quark with the beam remnants. Obviously, the




FIG. 17: Left panel: ratios Λ_b^0/B^0 as a function of p_T measured at forward rapidity in pp collisions at $\sqrt{s} = 13$ TeV by the LHCb Collaboration [194]. The data are compared to model calculations [11, 33, 50, 101] (see text for details). Right panel: comparison of the Λ_b^0 production asymmetry measured by the LHCb Collaboration at $\sqrt{s} = 7$ TeV with PYTHIA 8 predictions [11, 33].

same does not apply to the $\bar{\Lambda}_b^0$ as there are not antiquarks in proton beam remnants. The CR-BLC adds large amounts of low- p_T junctions, which form $\bar{\Lambda}_b^0$ and Λ_b^0 baryons in equal amounts, diluting the asymmetry.

In this context, it is also worth noting that the LHCb Collaboration has measured the D_s^+ production asymmetry in pp collisions. The D_s^+ meson does not contain any of the proton's valence quarks, which means that the production asymmetry is in this case not influenced by the valence quarks of the colliding protons. PYTHIA simulations have shown a strong dependence on both p_T and y , whereas the experimental measurements do not [198].

D. Measurements as a function of multiplicity

The observation of substantially different charm baryon-to-meson ratios in pp collisions compared to e^+e^- collisions evidences differences in the hadronization process in the two systems. Though at high- p_T the ratios seem to approach system-universal values, suggesting the presence of an energy scale delimiting the modification of the hadronization process,

the absence of clear differences between the Λ_c^+/D^0 ratios measured at LEP and B-factory energies and the similarity of the trends observed in pp collisions in the charm and beauty sectors makes it extremely difficult to reconcile pp and e^+e^- data ascribing the difference to a kinematic effect related to the energy of the initial-parton or of the jet, without implicating different properties of the systems. One is instinctively tempted to relate the observed differences to the typically larger number of quarks and gluons produced in hadronic collisions. The parton density is strictly connected to the “hadronic activity”, which is encoded in the measurable hadron multiplicity. Inevitably, the study of the evolution of the heavy-flavour baryon-to-meson ratios with particle multiplicity was expected to provide important information to better understand the modification of the hadronization process and to model it. As it will be discussed later in the section, it is important to stress that it is not just the number of hadrons produced that differentiates pp and e^+e^- collisions (at LEP energies the multiplicity can reach values not far from the average ones of pp collisions at the LHC) but rather the way in which hadrons can be formed. As discussed in Sect. II B 1 the concurrence of several initial scatterings, i.e. of MPI, allow for more and topologically different colour connections, which can impact the hadronization process. Also the hadronization via coalescence, which requires multiple quark wavefunctions to overlap in position and momentum space, is expected to progressively emerge as hadron-formation process with increasing number of quarks produced in the collision. Moreover, given the enhancement of multi-strange hadrons observed in high-multiplicity pp collisions [199], one naturally wonders whether the production of heavy-flavour hadrons containing a strange quark [199] also increases as particle multiplicity increases and whether, if present, this increase should be related to heavy-flavour baryon production.

The ALICE and LHCb experiments measured the evolution of the D_s^+/D^0 , B_s^0/B^0 , Λ_c^+/D^0 , and Λ_b^0/B^0 yield ratios from very low to high charged-particle multiplicity in pp collisions at $\sqrt{s} = 13$ TeV to provide additional experimental constraints on the hadronization mechanisms in a high density partonic environment [200, 201].

In the upper panels of Fig. 18, the D_s^+/D^0 ratio in the lowest (left) and highest (right) multiplicity classes measured by the ALICE experiment [200] are shown. The measurements do not indicate a significant multiplicity dependence of the ratio, which within the uncertainties is also independent of p_T in the measured p_T interval. This is consistent with a coalescence picture because they are both affected in a very similar way by the density of the medium,




FIG. 18: The D_s^+/D^0 (top) and Λ_c^+/D^0 (bottom) ratios measured at midrapidity by ALICE in pp collisions at $\sqrt{s} = 13$ TeV in the lowest (left) and highest (right) midrapidity multiplicity classes inspected [200]. The measurements are compared to PYTHIA 8 predictions with the Monash [11] and the CR-BLC [33] tunes, and the CE-SH model [202], calculated in similar multiplicity classes. Figure from Ref. [200].

while the baryon over meson ratio should show an increase with the density of the medium. On the other hand, the lower panels of Fig. 18 report the p_T -differential Λ_c^+/D^0 ratio, which shows evidence of a dependence on multiplicity such that higher multiplicities result in an enhancement of the Λ_c^+/D^0 ratio. When comparing the highest multiplicity interval to the lowest one, the effect has a significance of 5.3σ for $1 < p_T < 12$ GeV/c. It is worth noticing that the measured Λ_c^+/D^0 ratio in the lowest multiplicity class is still higher (in the measured p_T range) than the average of corresponding ratios measured in e^+e^- collisions at LEP. The ALICE Collaboration performed the measurements selecting the multiplicity using two different multiplicity estimators located at different pseudorapidity regions; one overlapping with the pseudorapidity window in which Λ_c^+ and D^0 are reconstructed, and one with a significant η gap. The increasing trend of the Λ_c^+/D^0 ratio is consistent between the

two measurements. This indicates that the enhancement from low to high multiplicity is not induced only by the possibly different correlation of Λ_c^+ and D^0 production with the “local” multiplicity of particles produced close to them in pseudorapidity. Such a correlation could arise either from a genuine correlation between hadronization process and the multiplicity, e.g. in case Λ_c^+ production were favoured compared to D^0 production when the “local” parton density is higher, or from a correlation dictated by different average local multiplicities accompanying Λ_c^+ and D^0 production independently from the hadronization process, e.g. if Λ_c^+ and D^0 are produced in jets with different number of constituents. Correlations induced by a bias on the multiplicity estimate related to signal reconstruction, like the contribution of a different number of decay particles to the multiplicity estimate, are instead removed by ALICE in the analysis.

The measured charm-hadron ratios in Fig. 18 for the lowest and highest multiplicity class are compared to model predictions from MC generators and a statistical hadronization model. The simulations with the PYTHIA 8 event generator were performed with the Monash and the CR-BLC tunes. The measured D_s^+/D^0 ratios at low and high multiplicity are compatible with PYTHIA 8 expectations both with Monash and CR-BLC tunes. As expected by the Λ_c^+/D^0 ratio results shown in Fig. 13, the Monash tune does not reproduce the Λ_c^+/D^0 ratio in either multiplicity interval, nor does it show a strong multiplicity dependence. By contrast, the CR-BLC tunes describe the Λ_c^+/D^0 decreasing trend with p_T , and are closer to the overall magnitude in both multiplicity ranges. All CR-BLC tunes show a clear dependence with multiplicity, qualitatively reproducing the trend observed in data, but the evolution predicted by the three “modes” is different, indicating that the data can be useful for tuning further the model.

The predictions of a canonical-ensemble statistical hadronization (CE-SH) model [202] describe the Λ_c^+/D^0 ratios, reproducing their multiplicity dependence. In the calculation, the underlying charm-baryon spectrum in the calculations is augmented to include additional excited baryon states predicted by RQM. The CE-SH model explains the multiplicity dependence as deriving from the reduced volume size of the formalism towards smaller multiplicity, where a decrease of the Λ_c^+/D^0 ratio is a consequence of the strict baryon-number conservation. Such behaviour is also expected for charm-strange mesons relative to non-strange charm mesons because of strangeness-number conservation. However, the resulting prediction reproduces the D_s^+/D^0 ratio only at low multiplicity, while it overestimates it in

the highest multiplicity interval. For the D_s^+/D^0 ratio only the PDG case is shown since the additional RQM states do not modify significantly the D-meson relative yields with respect to the PDG set.




FIG. 19: The left and middle panel display the ratio of cross sections $\sigma_{B_s^0}/\sigma_{B^0}$ versus the normalized multiplicity of all VELO tracks and backward VELO tracks, respectively. The right panel shows the comparison with PYTHIA 8 calculations for the $0 < p_T < 6$ GeV/ c interval. The horizontal bands show the values measured in e^+e^- collisions. Figure from Ref. [201].

The LHCb Collaboration measured the production rate of B_s^0 mesons relative to B^0 mesons in pp collisions at a centre-of-mass energy $\sqrt{s} = 13$ TeV over the forward rapidity interval $2 < y < 4.5$ as a function of the event charged particle multiplicity [201]. The multiplicity estimators used in the analysis are the total number of charged tracks reconstructed in the VELO detector ($N_{\text{VELO tracks}}$), and the subset of VELO tracks that point in the backward direction, away from the LHCb spectrometer ($N_{\text{back tracks}}$). The results reported in Fig. 19 show that the rate of B_s^0 production relative to B^0 might be enhanced with respect to the one measured in e^+e^- . The enhancement is observed when charged-particle multiplicity is measured in the full VELO detector, while it is not observed when the charged-particle multiplicity is based on N_{back} tracks. In collisions with relatively low charged-particle multiplicity, and for B mesons with $p_T > 6$ GeV/ c , the rate of B_s^0 production relative to B^0 production is consistent with that measured in e^+e^- collisions. The ratio of cross sections

calculated by the PYTHIA event generator with and without colour reconnection is compared with the experimental measurements for the p_T interval 0–6 GeV/ c in the right panel of Fig. 19. Both sets of PYTHIA calculations show a rise with multiplicity, which is more pronounced when colour reconnection is included. Note that the source of this rise in B_s^0/B^0 with respect to multiplicity in PYTHIA is not due to an explicit strangeness enhancement model (e.g. Rope hadronization [47] or close-packing [48]) but instead is already an existing consequence of the standard Lund fragmentation modelling, however the exact source of this multiplicity dependence has not yet been studied. Both PYTHIA models reproduce the data within uncertainties though both scenarios give values that are lower than the central values of the data at high multiplicity, possibly indicating a different slope of the rise of the B_s^0/B^0 ratio with multiplicity. The enhancement of the rate of B_s^0 production relative to B^0 production might be a consequence of a bias arising from the coinciding rapidity regions between the multiplicity estimator and the measurement of interest or it might signal that the effect seen is related to the “local” multiplicity of particles surrounding the B mesons. It would be interesting to further investigate these possibilities with Run 3 data and to perform similar measurements at midrapidity. On the other hand, the results could show evidence that the enhancement is present in collisions with high charged-particle multiplicity, while for relatively low charged-particle multiplicity, and for B mesons with $p_T > 6$ GeV/ c , the rate of B_s^0 production relative to B^0 production is consistent with what is measured in e^+e^- collisions.

The LHCb Collaboration recently released the measurements of the $\sigma_{\Lambda_b^0}/\sigma_{B^0}$ as a function of p_T and multiplicity [194]. The p_T -integrated $\sigma_{\Lambda_b^0}/\sigma_{B^0}$ ratio is shown as a function of relative multiplicity in Fig. 20. In the lowest multiplicity interval, the LHCb data approaches the baryon fraction measured in e^+e^- collisions at the LEP. The distinct rise of the baryon fraction with multiplicity reaches a plateau at ~ 0.5 for collisions that produce more than twice the average number of VELO tracks.

These last two measurements show that b-quark hadronization is different in e^+e^- and pp collisions, thus it is not an universal process. This may provide indication that quark coalescence plays an important role in forming beauty hadrons at the LHC, or that one should more carefully examine string models with multiplicity dependencies. The trend observed for the p_T -integrated $\sigma_{\Lambda_b^0}/\sigma_{B^0}$ ratio resembles a “turn-on” curve which may mark the transition from two different regimes, with the onset of a different hadronization mechanism




FIG. 20: Ratio of cross sections $\sigma_{\Lambda_b^0}/\sigma_{B^0}$ measured by LHCb in $2 < |y| < 4.5$ in intervals of the multiplicity of all VELO tracks, which is reported on the x axis after scaling it by the average multiplicity. The purple point indicates the value measured in e^+e^- collisions at LEP. Figure from [194].

in pp collisions becoming very quickly effective as soon as a minimal hadronic activity is present. It would be interesting to try to correlate the observed trend with the number of MPI. It must be noted that the evolution observed for the p_T -integrated $\sigma_{\Lambda_b^0}/\sigma_{B^0}$ ratio does not contrast with what previously discussed about the evolution with multiplicity of the p_T -differential Λ_c^+/D^0 ratio measured by ALICE at midrapidity. This will be further discussed in Sect. III F.

E. Proton–nucleus collisions

The influence of a hadronic environment on the hadronization process is evidenced by the observed modifications of heavy-flavour baryon-to-meson ratios from e^+e^- to pp collisions in conjunction with the observed dependence of these ratios on charged particle multiplicity in pp collisions as discussed in the previous section. From this alone we see that the study of increasing the collision system size is important, and pA collision systems provide a tantalising bridge between the small pp and large AA collision environments. Collisions of protons with nuclei are interesting for the study of heavy-flavour hadronization in particular for at least two reasons. The first is that they give access to high multiplicities without the need




FIG. 21: Left: Λ_c^+/D^0 ratio as a function of p_T in pp collisions (at low and high multiplicity and multiplicity integrated) and in p–Pb collisions [78, 173, 200]. Right: comparison of Λ_c^+/D^0 ratio in pp and p–Pb collisions with predictions from QCM model [173].

of selecting very rare events, unlike pp collisions whereby high-multiplicity events represent only a small fraction of the pp inelastic cross section. The second is the possible interplay of hadronization and collective effects, the presence of which in small collision systems emerged in the last decade, particularly from the study of particle azimuthal anisotropies and the observation of relatively large flow coefficients in high-multiplicity p–Pb collisions [208]. These effects resemble those observed in high-energy nucleus–nucleus collisions and ascribed to the formation of a QGP, which expands and cools down following hydrodynamic laws.

The first aspect can be better quantified by the following considerations. High-multiplicity pp events represent a small fraction of the pp inelastic cross section. For instance, the highest multiplicity class considered in ALICE measurement of Λ_c^+/D^0 ratio reported in Fig. 18 represents a fraction certainly smaller than 0.5% [200, 209] of all inelastic events³. Thus, it cannot be excluded that the multiplicity trends observed in these events derive from ‘peculiar’ features of the selected events rather than from a general dependence of the measured particle ratios from multiplicity. A quite natural next step is to measure these ratios in

³ This can be deduced, as a conservative upper limit, from the numbers reported in Table 1 and Table 4 of Ref. [200] and [209], respectively.




FIG. 22: Nuclear modification factor of Λ_c^+ baryons as a function of p_T measured by ALICE [173] and compared with predictions from POWLANG [203], QCM [92], and POWHEG + PYTHIA 6 + EPPS16 nPDF [10, 204–207]. See text for details.

collision systems in which similar or higher multiplicities are reached without selecting rare events. This opportunity is offered by collisions of nuclei or of protons with nuclei, in which significantly higher multiplicities are reached with respect to pp collisions. The multiplicity of charged particles at midrapidity increases with the number of nucleons participating to the collisions (N_{part}) [210–212]. In p–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, the average charged-particle multiplicity at midrapidity in non-single diffractive events is more than a factor of 3 higher than the multiplicity measured in non-single diffractive pp events [213]. The average multiplicity of the highest-multiplicity interval in which ALICE measured the Λ_c^+/D^0 ratio in pp collisions is about a factor of two higher and is reached in 0–5% more central p–Pb collisions. As shown in Fig. 21 (left panel), the Λ_c^+/D^0 ratio measured by ALICE in p–Pb collisions is higher than that measured in pp collisions at $\sqrt{s} = 13$ TeV without multiplicity selections in the range $3 < p_T < 12$ GeV/ c , and similar to that measured in high-multiplicity pp events. At lower p_T , there is a hint for a lower ratio in p–Pb collisions than in pp collisions. Preliminary results from CMS [214] suggest that the ratio does not evolve significantly with multiplicity in p–Pb collisions, contrary to what observed

for the Λ/K_S^0 ratio in the light-flavour sector [215]. This breaks the similarity of Λ_c^+/D^0 and Λ/K_S^0 ratios observed by ALICE in pp collisions, both multiplicity-integrated and as a function of multiplicity [200], and, within larger uncertainties, in multiplicity-integrated p–Pb collisions [77]. Overall, the data suggest that the modification with multiplicity of the p_T -differential Λ_c^+/D^0 ratio observed in pp collisions is not dictated by peculiar properties of the selected high-multiplicity events. If CMS preliminary data is confirmed, the p_T -differential Λ_c^+/D^0 ratio from low-multiplicity pp collisions up to high-multiplicity p–Pb collisions, would display a stronger evolution at low multiplicities followed by saturation. Constraining better the low-multiplicity region is a major goal for the future. New measurements with reduced uncertainty and extended to even lower multiplicities are necessary to profile the onset of the modification of the baryon-to-meson ratio from e^+e^- collisions to hadronic collisions. In the right panel of Fig. 21, the Λ_c^+/D^0 ratio measured in pp and p–Pb collisions are compared with QCM predictions, which are compatible with the data. In QCM, the ratio has a different p_T trend in p–Pb collisions and peaks at higher p_T than in pp collisions because of the larger assumed light-quark velocity, which is needed to reproduce the hardening of the light-flavour hadron spectra. The evolution of the p_T -differential Λ_c^+ spectrum from pp to p–Pb collisions is quantified in Fig. 22 in terms of the nuclear modification factor, R_{pPb} , which is calculated by dividing the p–Pb p_T -differential production cross section by the pp one scaled by the Pb mass number. A deviation of R_{pPb} from unity is observed and corresponds to a modification of the spectra in p–Pb with respect to pp collisions. The modification of the Λ_c^+ -baryon production spectrum in p–Pb collisions has been additionally confirmed by the computation of the mean transverse momentum, $\langle p_T \rangle$, which results larger in p–Pb with respect to pp [173]. For D mesons $R_{pPb} \approx 1$ [216]. Therefore, the $\Lambda_c^+ R_{pPb}$ is almost equivalent to the double ratio $(\Lambda_c^+/D^0)^{p-Pb}/(\Lambda_c^+/D^0)^{pp}$. The POWHEG+PYTHIA6+EPPS16 nPDF model is based on the POWHEG NLO calculation [204, 205] of charm quark production cross section matched with PYTHIA 6 [10] for parton shower and fragmentation. It uses CT14NLO [206] parton distribution functions (PDF) and the EPPS16 parameterization [207] of nuclear PDF for the the Pb nucleus. The latter term causes a departure of the expected R_{pPb} from unity at low p_T due to the suppression (“nuclear shadowing”) at small Bjorken- x of the gluon PDF. The model, which can describe D-meson data within uncertainties, cannot describe $\Lambda_c^+ R_{pPb}$, evidencing that the observed modification cannot be determined by the modification of PDF of nuclei with

respect to those of protons. For heavy-flavour hadrons at LHC energies, nuclear shadowing was considered the largest “cold-nuclear matter” effect, i.e. an effect not related to the formation of a quark-gluon plasma, that could modify the production cross sections in nuclear collisions to the simple geometrical scaling of cross sections in pp collisions. In the POWLANG calculation [203], charm quarks are transported through a “small-size” expanding QGP, which affects the p_T distributions of charm hadrons. However, the calculated R_{pPb} value is identical for all charm-hadron species as it does not consider any modifications of the relative hadron abundances due to quark coalescence. The presence of a QGP phase has a substantial impact on the predicted R_{pPb} but the model cannot describe either the D-mesons nor the Λ_c^+ R_{pPb} in the full p_T range. The QCM model instead describes the data within uncertainties.

Most recently, the ALICE Collaboration released measurements of the fragmentation fractions of charm quarks to different charm-hadron species, which are measured for the first time in p–Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV at midrapidity [217]. The fragmentation fractions for all charm-hadron species are found to be consistent for pp and p–Pb collisions at the same collision energy, indicating that there is no significant modification of the charm-quark hadronisation process due to the different hadronic collisions’ system sizes.

The LHCb collaboration measured the Λ_c^+ and Ξ_c^+ production and their ratios to D^0 at forward and backward rapidity in p–Pb collisions [218, 219]. When compared with the measurements at midrapidity [173, 220], the baryon-to-meson ratios are lower for $p_T < 8$ GeV/c, while at higher p_T the measurements are consistent within uncertainties. The origin of this tension is not yet fully understood, for a more detailed discussion on this open point see Sect. IV.

F. Nucleus–nucleus collisions

The study of heavy-quark hadronization in nucleus–nucleus collisions offers a unique window for addressing hadron formation in an extended system of quarks, which can be assumed to be in local thermodynamic equilibrium and to move collectively along with the system expansion. Indeed, since long it was suggested that in the QGP hadrons may form via recombination of existing quarks [65], with important implications for the hadron abundances and momentum distributions, expected to significantly differ from those resulting

from fragmentation and hadronization in a “vacuum-like” system, as that of an e^+e^- collision can be classified. Understanding the hadronization process in these collisions is also a necessary step to exploit heavy-quarks for the study of in-medium partonic energy loss and of the medium transport properties [221]. This was the initial goal motivating heavy-flavour hadron production measurements in heavy-ion collisions: even at LHC energies, the medium temperature is significantly lower than the charm-quark mass, so that charm and beauty quark thermal production is negligible compared to that in hard-scattering processes occurring in the early stage of the collision with cross sections known with relatively small uncertainty [156, 157, 190, 222, 223]. Interacting with the medium, constituents heavy quarks exchange energy but preserve their flavour identity. Thus they can be regarded as “calibrated” probes of the medium and used as markers to trace the quark diffusion and the partonic interactions in the QGP, resolving the medium constituents and allowing to build a connection between the microscopic “local” partonic interactions and the medium global properties, in particular, its transport ones. However, the uncertainties in the modelling of the hadronization process, which significantly influences the momentum distribution of the final-state hadrons, can reduce the capability of inspecting the dynamics in the partonic phase. On the other hand, a QGP offers a (expanding) thermal source of light quarks and gluons whose modelling, e.g. in coalescence models, might be simpler and less sensitive to event-by-event fluctuations than that of a pp collision system. Therefore, the measurement of the production of different heavy-flavour hadron species in heavy-ion collisions can simultaneously constrain the modelling of hadronization and parton dynamics in the medium.

Several measurements in Au–Au collisions at RHIC and Pb–Pb collisions at the LHC demonstrate that charm and beauty quarks interact strongly with the QGP constituents [159, 161, 224–252]. The R_{AA} values observed for both charm and beauty hadrons are significantly smaller than unity at intermediate p_T and larger for beauty than charm, indicating a significant energy loss of both quarks in the medium and evidencing the expected dependence of energy loss on the quark mass. At moderate/low p_T the v_2 of prompt D mesons is large, close to that observed for charged pions [237]. This can indicate that charm quarks are strongly coupled to the system and are pushed towards kinetic equilibrium via rescattering with the medium constituents. It can also signal coalescence as a hadronization process relevant to charm quarks through which charm hadrons partly inherit the flow of light quarks, a relevant aspect that could be more deeply investigated through heavy-light correlation of the

anisotropic flow v_n [84, 253]. At low p_T , where elastic processes are the most important ones, heavy quark transport in the medium can be described as a diffusion process [55, 254–256]. The main transport parameter is the spatial diffusion coefficient D_s , which is related to the kinetic equilibration time of a heavy-quark with mass m_Q , $\tau_Q = D_s m_Q / T$ [257, 258]. The comparison of R_{AA} and v_2 data with model predictions favour small values of heavy-quark D_s , in the range $1.5 < 2\pi D_s T_c < 4.5$ at the pseudocritical temperature $T_c = 155$ MeV, in line with other estimates [54, 242, 255, 259, 260]. This interval corresponds to relaxation times for charm quarks smaller than about 10 fm/ c , thus of the order of or shorter than the QGP lifetime, actually suggesting that charm quarks might get close to reaching kinetic equilibrium in the medium [55, 256]. A recent estimate that combines lattice QCD to the heavy quark effective theory in the limit $M \gg T$ [256] implies a very small thermalization time, at least in the $p \rightarrow 0$ limit; namely of about 1-1.5 fm/ c for charm quarks and 3-5 fm/ c for bottom which are significantly smaller than those extrapolated from the phenomenological analysis. This work has been developed in non-quenched QCD which is a very important advancement w.r.t. previous studies, however, it is still in the $M \rightarrow \infty$ limit. In Ref. [85, 261] it has been shown that within a quasi-particle model (QPM-Catania) one expects that D_s has a significant mass dependence from the charm quark mass to the limit $M \rightarrow \infty$, decreasing by about a factor 1.7. This could to a large extent compensate the discrepancy between the value of $2\pi T D_s$ from the lQCD driven estimate w.r.t. the one extrapolated from the phenomenology for charm quarks. However, an even more recent extension of the study in Ref. [256] has done a first extrapolation to finite mass finding a very small dependence of $2\pi T D_s$ on M_Q . This, if confirmed by further studies within lQCD and heavy quark effective field theory, opens the question on how to reconcile them with the phenomenological estimates. At this stage, we only mention that a preliminary study have indicated that an initial glasma phase may lead to infer smaller values of D_s [262], and more recently it has been suggested that also memory effect (non-Markovian dynamics) may affect the phenomenological extrapolation of D_s [263], especially for charm quarks. Therefore, with more precise data becoming available with the ALICE upgrade (especially at low p_T), it is likely that will be possible to achieve a significant advancement in the understanding of the heavy quark dynamics.

However, even within the uncertainties of the mass dependence of the diffusion or drag coefficient, it remains that because of the larger mass, beauty quarks are expected to diffuse

less than charm quarks and to have a significantly larger relaxation time that is at least a factor of two [85, 263] if not a factor of three larger (if D_S is nearly mass independent) as suggested by the ratio M_b/M_c . Energy loss is also expected to be smaller for beauty than charm quarks. In line with these expectations, experimental measurements of beauty hadrons or their decay products show higher R_{AA} and smaller v_2 with respect to charm or light-flavour hadrons [224, 264].




FIG. 23: Prompt D-meson R_{AA} in the 0–10% centrality class (left panel) and v_2 in the 30–50% centrality class (right panel) compared with the PHSD [90], POWLANG [265, 266], and Catania [37] predictions obtained with and without including hadronization via recombination. Figure adapted from Ref. [232].

The hadronization schemes used in transport models have a significant impact on the predicted values of R_{AA} and v_2 and on their dependence on p_T . The effect of hadronization via recombination on D-meson R_{AA} and v_2 is illustrated in Fig. 23 where ALICE measurements in Pb–Pb collisions in the centrality intervals 0–10% (R_{AA} , left panel) and 30–50% (v_2 , right panel) are compared with the expectations of the PHSD, POWLANG, and Catania models with and without the inclusion of recombination [232]. In a medium that is radially expanding with a common velocity, hadronization via quark recombination tends to equilibrate particle velocities towards the medium expansion velocity. The combined effect of recombination, diffusion, and energy loss on the R_{AA} is the appearance of a maximum

at momenta not much larger than the hadron mass. For what concerns the elliptic flow, the v_2 of heavy-flavour hadrons formed via recombination derives from a combination of the charm and light quarks flows. From the comparison of model expectations with and without hadronization via recombination, shown in the right panel of Fig. 23, it can be appreciated the effect of recombination on charm-meson v_2 in increasing v_2 and pushing its maximum at higher momenta. Recombination is an essential ingredient for reproducing the data [67, 101, 221, 255, 267].

All models that can reproduce the large observed v_2 of D mesons [237] predict that it partly derives from hadronization via coalescence. In order to single out the contribution of hadronization from the contribution of charm-quark diffusion in the generation of charm flow, the modification in Pb–Pb collisions with respect to pp collisions of the p_T -differential yield ratios of different heavy-flavour particle species must be studied. In particular, models based on statistical hadronization or coalescence were initially designed to describe hadron formation in AA collisions. They were expecting an increase of the production of heavy-flavour baryons relative to heavy-flavour mesons and of hadrons with strange quarks relative to non-strange ones in heavy-ion with respect to pp collisions, the latter originally thought to deliver systems with properties closer to e^+e^- collisions and in which “in-vacuum” fragmentation should have been the dominant hadronization mechanism. Such an expectation was motivated by the standard lore that only the large reservoir of partons and high energy densities of nucleus–nucleus collision systems could make it likely for quark coalescence to become a relevant process compared to the mechanism of fragmentation, which requires the creation of quarks from the vacuum. Hence, the typical signature of coalescence, that is, an enhancement of baryon-to-meson ratios, was not expected to occur in pp collisions. However, as discussed in the previous sections, the data indicates that, particularly in the heavy-flavor sector, pp collisions exhibit significant differences compared to smaller collision systems such as e^+e^- and $e^\pm p$. These differences result in modifications to the particle ratios, providing a sensitive test of changes in the hadronization dynamics. The coalescence plus fragmentation approach, such as the Catania model, suggests that even if pp collisions result in the formation of a QGP droplet, D meson production is likely still dominated by the fragmentation process. Meanwhile, the coalescence process becomes dominant for baryon production, significantly increasing it in pp collisions compared to e^+e^- collisions. This outcome, though initially unexpected, naturally follows from the application of coa-

lescence dynamics and effectively explains the large increase in the measured Λ_c^+/D^0 ratio. However, the enhancement in pp collisions can also be explained in the context of PYTHIA, but, also in this case, the main modification affects the baryon production that has to come from colour reconnections of quarks and gluons in topologies irrelevant in e^+e^- collisions but emerging with an increasing number of MPI, hence particularly in high-multiplicity events, in hadronic collisions. This also shows that already in pp (in particular for high-multiplicity events) more local recombination of quarks (minimizing string energy) becomes quite relevant for baryon production. The same coalescence modelling shows that in AA collisions the large-size reservoir of high-density quarks makes a further difference making the recombination the dominant mechanism for both heavy quark mesons and baryons.

The measurements of the production of prompt and non-prompt D_s^+ mesons [235, 268] and of B_s^0 mesons [269] provide first hints supporting the presence of an enhancement of the production of heavy-strange mesons with respect to non-strange ones. Figure 24 shows in the left panel the comparison of the prompt D_s^+/D^0 ratios measured by ALICE in central Pb–Pb collisions and in pp collisions. A hint of a higher ratio in Pb–Pb collisions is visible in $3 < p_T < 10$ GeV/ c . The Catania model reproduces the data within uncertainties, while the TAMU and POWLANG transport models as well as the GSI/Hd+BW statistical hadronization model, for which the hadron p_T spectrum is modelled according to a Blast Wave function, tend to overestimate the data in the low p_T region. Slightly higher D_s^+/D^0 values, closer to 0.4 and without a significance dependence on p_T in $1 < p_T < 8$ GeV/ c , were reported by STAR in semicentral and peripheral Au–Au collisions at $\sqrt{s_{NN}} = 200$ GeV [270]. In central Au–Au collisions, the ratio decreases below 0.3 for $p_T < 4$ GeV/ c and, within uncertainties, becomes compatible with PYTHIA expectation and pp data at LHC energies. New measurements with reduced uncertainty and lower p_T reach, as well as the measurement of $\Xi_c^{+,0}$ production (larger than D_s^+ one in pp collisions), are necessary for a final assessment and understanding on the enhancement of char-strange hadron production. In the right panel of Fig. 24, the B_s^0/B^+ ratio measured as a function of p_T by CMS in 0–90% central collisions [269] and normalized to the f_s/f_d ratio measured at $\sqrt{s} = 7$ TeV by LHCb in $2 < y < 4.5$ [271] is shown together with the ratio of non-prompt $D_s^+ R_{AA}$ to $D^0 R_{AA}$ measured by ALICE in the 0–10% centrality interval [224, 268]. In pp collisions about 50% of non-prompt D_s^+ derive from the decay of a B_s^0 meson. Together the data provide a hint for an enhancement of strange B-meson production relative to non-strange B-meson production,

in line with the expectation of the TAMU model [50].




FIG. 24: Left (from Ref. [14]): prompt D_s^+/D^0 ratio measured by ALICE in $|y| < 0.5$ in pp and 0–10% central Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV [157, 162, 235] compared to model expectations [36, 37, 39, 40, 96]. Right: red (black and grey) markers show the ratio of strange to non-strange non-prompt D mesons (B mesons) yield in 0–10% (0–90%) Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV measured by ALICE [224, 268] (CMS [269]) and normalised to the analogous ratio measured in pp collisions. In the B-meson case, the parametrization of the f_s/f_d ratio measured at $\sqrt{s} = 7$ TeV by LHCb in $2 < y < 4.5$ [271] is used as pp reference, considering the collision-energy and rapidity dependence of the ratio, as well as the parametrization uncertainty, as negligible compared to the Pb–Pb data uncertainty.

The data are compared to TAMU calculations [39, 272, 273].

The Λ_c^+ is the only heavy-flavour baryon whose production has been measured in nucleus–nucleus collisions. The left panel of Fig. 25 shows the evolution of the p_T -integrated Λ_c^+/D^0 ratio as a function of the charged-particle multiplicity at midrapidity measured by ALICE in pp, p–Pb, and Pb–Pb collisions and by STAR in Au–Au collisions [72]. The ratio is approximately 0.5, thus much higher than the ≈ 0.11 value measured in e^+e^- and ep collisions, and, within uncertainties, it does not show a dependence on multiplicity. The same ratio in pp (minimum bias) and in Pb–Pb collisions is expected by the Catania and TAMU models, which reproduce also quantitatively the data. Also the SHMc model does not ex-

pect a dependence on centrality in Pb–Pb collisions. However, it predicts a ratio around 0.2 and underestimates the data. It must be noted that this version of the SHMc does not include the augmented set of high-mass baryon states considered by TAMU. In the SHMc charm is not in chemical equilibrium and the abundance of charm hadron species depends on the charm fugacity factor, which however cancels in single-charm particle ratios, and by the chemical freezeout temperature, which results in being independent of centrality. Similarly, in the TAMU, though the hadronization process is modelled differently in pp and Pb–Pb collisions, particle ratios mainly depend on statistical factors. For the Catania model, the similarity between pp and Pb–Pb values derives from the similar description of the bulk of light-flavour quarks as a QGP medium with similar temperatures in the two systems and from the applied normalization condition that coalescence probability equals unity at $p_T^{\text{hadron}} = 0$. There is still a dependence on the volume of the hadronizing fireball and a subdominant dependence on the radial flow but the last has a weak effect on the p_T -integrated yield. In pp collisions, the PYTHIA 8 Monash tune is even lower than the e^+e^- expectation and largely independent of event multiplicity. Contrastingly, PYTHIA 8 with CR-BLC expects a significance increase of the ratio with multiplicity, deriving from the larger probability of forming junction colour connections in events with a higher number of MPI, which is not supported by the data. The region of very low multiplicities is not covered by measurements, thus leaving open the possibility that e^+e^- values are recovered when the hadronic activity in the event is very small, in line with what the Λ_b^0/B^0 ratio at forward rapidity, discussed in Sect. III D, suggests. It is worth mentioning, that the average multiplicity in e^+e^- collisions at LEP energies, where most particles are part of high-energy dijets, does not differ much from the average multiplicity in minimum bias pp collisions at LHC energies (see Fig. 19.6 of Ref. [49]). This suggests that the number of produced particles is not the only relevant parameter and rather the whole event topology and the impact of the underlying event and MPI in hadronic collisions, even at the lowest multiplicity, must be taken into account for explaining the differences observed with respect to e^+e^- collisions.

In the right panel of Fig. 25, the evolution of the p_T -differential Λ_c^+/D^0 ratio with centrality is shown, by comparing the measurements performed in pp collisions [77] and in different centralities in Pb–Pb collisions at the LHC [72, 174, 274] and in Au–Au collisions at RHIC [70]. Contrary to the p_T -integrated case, the p_T -differential Λ_c^+/D^0 ratio evolves substantially with centrality, as shown in the right panel of Fig. 25, in which the Pb–Pb




FIG. 25: Left (from [72]): baryon-to-meson Λ_c^+/D^0 cross-section ratio p_T -integrated for $p_T > 0$ as a function of charged-particle multiplicity at midrapidity measured by ALICE in pp, p-Pb, and Pb-Pb collisions [72, 200] and by STAR [70] in Au-Au collisions. Right (adapted from [175]): comparison of the p_T -differential Λ_c^+/D^0 cross-section ratios measured in pp collisions by ALICE [77], in Pb-Pb collisions by ALICE [72], CMS [73], and LHCb [274] in different centrality intervals, and in Au-Au collisions by STAR [70].

ALICE [72], CMS [73], and LHCb [274] results are reported and compared to ALICE pp data as well as to the measurement in Au-Au collisions by STAR [70]. At intermediate p_T , the ratio increases with centrality. In peripheral collisions, LHCb data at forward rapidity overlap with ALICE minimum-bias pp data at midrapidity. In 30–50% Pb-Pb collisions the ratio is higher, though the values are compatible with those measured in high-multiplicity pp and p-Pb data. In central collisions a “radial-flow”-like peak emerges, possibly shifted at lower p_T at RHIC with respect to LHC energies. The appearance of this peak can be due to hadronization via coalescence, possibly reinforced by space-momentum correlations (see Sect. II B 4). In Fig. 26 the Λ_c^+/D^0 ratio measured by ALICE in 0–10% (left panel) and 30–50% (middle panel) central Pb-Pb collisions is compared to model expectations. Despite the different values predicted by the models, the large experimental and theoretical uncertainties do not allow to discriminate between the SHMc [40], Catania [37], and TAMU [38] models. At $p_T > 20$ GeV/c the ratio is the same at all centralities and consistent with that measured in e^+e^- collisions, possibly signalling the transition at high-enough momentum




FIG. 26: Baryon-to-meson Λ_c^+/D^0 cross-section ratio as a function of p_T in 0-10% (left) and 30-50% (middle) Pb-Pb collisions, and in pp collisions (right), compared with expectations from the Catania, SHMc, and TAMU models and from the PYTHIA 8 event generator with the Monash and CR Mode 2 tunes. Figure from Ref. [72, 275].

to a regime in which “vacuum”-like fragmentation is an effective description leading to a “universal” value.

IV. PROSPECTS AND FUTURE DEVELOPMENTS

The measurements of heavy-flavour baryon production carried out in the last decade in hadronic collisions have somewhat unexpectedly broken the paradigm that fragmentation modelled on e^+e^- data could be sufficient in describing hadronization in small collision systems, and that nucleus-nucleus would be the collision system where one would search for new phenomena. Rather, a quite sharp distinction between hadronization in e^+e^- and any hadronic collision system emerged, accompanied by the need of continuity from pp to nucleus-nucleus collisions. Multiplicity, as an estimator of the event activity (hence MPI?) and system size, provides a reasonable guide for examining the evolution of the observables from small to large collision systems. While reasonable explanations and ideas about the origin of the transition from e^+e^- to pp collisions have been put forward, together with effective modelling capable to reproduce the trends shown by the measurements, a new theoretical paradigm for hadronization is still being shaped. Certainly, as extensively discussed in the previous sections, the measurements performed so far achieved some milestones delineating

features and trends that theoretical modelling of hadronization will have to consider. They can be recapped in the following list.

- The first is certainly the evidence that heavy-flavour baryon production is significantly larger in pp than in e^+e^- collisions. This implies that the assumption that hadronization can be modelled solely with universal fragmentation functions does not hold already in pp collisions.
- The second concerns the boundaries out of which fragmentation seems recovered as a good description of hadronization. The observed evolution of Λ_c^+/D^0 and $\Lambda_b^0/B^{0,-}$ with p_T and multiplicity suggests that this occurs at high momentum (above about 15-20 GeV/c) and at extremely low multiplicity.
- The third is that the enhancement from e^+e^- to pp of the baryon-to-meson ratio is significantly larger for charm-strange baryons (e.g. $\Xi_c^{+,0}$) than for Λ_c^+ , despite no significant difference is observed for the D_s^+/D^0 ratio. This highlights the problem to understand strange production.
- The observation for $\Sigma_c^{0,+,++}/D^0$ and the augmented feed-down to Λ_c^+ from $\Sigma_c^{0,+,++}$ decay. In general, one may interpret these observations as a suppression of $\Sigma_c^{0,+,++}$ and charm-strange baryon production in e^+e^- due to “local” dynamical constraints (e.g. diquark production in string breaking), which are absent or mitigated by the emergence of other processes in hadronic collisions.
- Finally, remarkable experimental data shows the contrast between the apparently flat evolution with multiplicity and collision centrality of the p_T -integrated Λ_c^+/D^0 ratio from pp to Pb–Pb collision systems, compared to the strong modification of the p_T -differential ratio.
- On the theoretical side, coalescence and statistical hadronization emerged as effective models to describe some of the measured yields in pp collisions. For an extensive model like PYTHIA, which aspire at describing the full event dynamics, the central role of MPI and colour reconnection in causing and shaping the observed effects appears as an unavoidable conclusion suggested by the measurements.

In this section, we discuss prospects and goals for the future, also touching some topics and open points connected to heavy-flavour hadronization that could not be deepened in the previous sections. These includes recent measurements that have not yet conducted to firm conclusions, either because still preliminary or because affected by large uncertainties, but that by exploring different observables are pointing to new effects and directions of search for the future. We also discuss new ideas and measurements, which have the potential to lead toward an understanding of the comparison between experimental measurements performed by different collaborations and the mismatch with some theoretical calculations.

Consolidation of emerging picture

Many of the measurements presented in this review show striking effects, often with results so far from the original expectation of the “baseline models” described in Sect. II A that even large experimental uncertainties did not prevent important conclusions. However, the natural first goal for the future should be to have new measurements of the observables already inspected with a reduction of the uncertainties and with an extension of the low and high p_T and multiplicity reach. In particular, profiling the low p_T and the p_T -integrated baryon-to-meson ratios for other particles than Λ_b^0 (in particular of Λ_c^+ , $\Xi_c^{+,0}$, and $\Sigma_c^{0,+,++}$) at low multiplicity in pp collisions is of uttermost importance to investigate the onset of the modification of hadronization from e^+e^- to hadronic collisions. Measurements of charm and strange baryons in nucleus–nucleus collisions would also be particularly significant to verify whether the production rate of $\Xi_c^{+,0}$ and Ω_c^0 relative to Λ_c^+ increases in a system in which strange quarks are expected to be abundantly produced given that light-flavour strange hadrons yields match the expectation from chemical equilibrium without canonical suppression. In the open beauty sector, the experimental study of hadronization in nucleus–nucleus collisions has substantially only started with the first measurements of strange and non-strange B mesons and non-prompt D mesons. Though very important for first assessments, the large uncertainties, the limited and not granular p_T coverage, and the reduced sensitivity implied by the decay kinematics for non-prompt signals, and the lack of measurements of beauty-baryon production, permit only qualitative comparison with model expectations. With next LHC runs, also thanks to the LHC detector upgrades, new measurements, including first ones of Λ_b^0 or non-prompt Λ_c^+ , should allow for firmer conclusions. In pp collisions, LHCb data already provided a rather detailed picture at

forward rapidity, but precise measurements down to low p_T are missing for both Λ_b^0 and B_s^0 at midrapidity. As described in what follows, determining the dependence on rapidity of heavy-flavour baryon-to-meson ratios must be an important objective of experimental searches. Finally, measurements of the production of strange and beauty baryons would also be very important, also given what was observed for the $\Xi_c^{+,0}/\Lambda_c^+$ ratio, but they are experimentally extremely challenging and likely difficult to achieve in the near future.

Rapidity puzzle

The comparison of the measurements performed by ALICE and LHCb at mid and forward rapidity, respectively, show tantalising signs of a possible rapidity dependence of the baryon-to-meson ratio in pp, p-Pb, and Pb-Pb collisions [72, 78, 180, 218–220, 274, 276] for both the Λ_c^+ and $\Xi_c^{+,0}$ baryons, as displayed in Fig. 27. However, the current measurements do not allow for conclusions, either because of the large uncertainties (including those on the BR in the $\Xi_c^{+,0}$ case) or because of inconsistencies in the accessed p_T intervals or in the definition and ranges used for multiplicity and centrality. It is envisioned that the LHC collaborations in the future will, as far as possible, perform measurements in the same centrality intervals and transverse momentum, facilitating easier comparisons and reducing potential ambiguities.

In the beauty sector, the LHCb experiment measured a baryon-to-meson cross-section ratio compatible between p-Pb and pp collisions [277] at both forward and backward rapidity. However, also in this case, the data uncertainties prevent to conclude whether p_T modifications of the baryon-to-meson ratio from pp to p-Pb collisions observed in charmed sector are present also in the beauty sector. In pp collisions ALICE measured at midrapidity the ratio of non-prompt Λ_b^0 to non-prompt D^0 , which is strictly connected to the $\Lambda_b^0/B^{0,-}$ ratio [196]. However, the comparison with LHCb data at forward rapidity is quite indirect, requiring a modelling of the p_T -differential cross section of beauty production tuned on LHCb data and of the decay kinematics, which unavoidably dilutes possible effects over a broader kinematic range. The CMS collaboration measured Λ_b^0 production at 7 TeV but only for $p_T > 10$ GeV/ c [195]. Measurements of the baryon-to-meson ratios at low p_T in the beauty sector at midrapidity via fully reconstructed B and Λ_b^0 decays are envisioned for the next runs at the LHC: they will be essential to investigate a possible rapidity dependence of these ratios.

From a theoretical point of view, it was already briefly mentioned that PYTHIA 8 does not predict any difference with rapidity in the charm or beauty baryon-to-meson ratio in pp collisions, and expects larger baryon-to-meson ratios at forward rapidity than those measured by the LHCb Collaboration. It would be extremely interesting to systematically investigate models that include coalescence to see if any rapidity dependence in the baryon-to-meson emerges and to understand if a possible effect would be driven by the medium density and/or by possible differences in the heavy-quark density, which would be important for multi-charm hadron states as well as for quarkonia and the B_c^+ meson, between mid- and forward/backward rapidity. However, within a coalescence approach, one would need an appropriate description of the evolution of both the bulk medium and the charm quark momentum distribution from central rapidities to forward ones. In fact, the fireball degree of thermalization and, in general, the time evolution at forward rapidity already for the bulk matter have been less investigated in hydrodynamics or transport theory, and even much less the dynamics of charm quarks. Before making predictions of the Λ_c^+/D^0 ratio one should check that $R_{AA}(p_T)$ and $v_2(p_T)$ of D mesons at forward rapidity can be correctly predicted, as done at midrapidity. This would give good confidence on the level of charm-quark equilibration at forward rapidity and would provide a reasonable knowledge of the charm-quark p_T distribution.

Furthermore, the study of the directed flow of D mesons in nucleus–nucleus collisions at RHIC and LHC has revealed that the bulk has a tilt with respect to the longitudinal direction and has, therefore, a displacement with respect to the charm quark at forward rapidity [278–280]. This could also imply a different impact of the corona effect, or more generally of the amount of non-thermalized heavy quarks that escape from the fireball. Summarizing, a solid prediction for Λ_c^+/D^0 within the coalescence approach should be based on a solid description of the bulk and charm distribution function in space and momentum as already done at midrapidity.




FIG. 27: Top left panel: the Λ_c^+/D^0 ratio measured in p–Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV at mid, forward, and backward rapidity [78, 218, 276]. Top right panel (from Refs. [219, 220]): comparison of the Ξ_c^0/D^0 ratio measured at midrapidity in p–Pb collisions at $\sqrt{s} = 5.02$ TeV with the measurements at forward and backward rapidity at $\sqrt{s_{NN}} = 8.16$ TeV. Bottom panel: the Λ_c^+/D^0 ratio measured in wide p_T intervals shown as a function of rapidity in central, semicentral collisions [72], and peripheral [274] Pb–Pb collisions. The vertical lines represent the total uncertainties. ALICE data derive from the extrapolation to $p_T > 0$ of the ratios measured in the interval $1 < p_T < 24$ GeV/c. In the LHCb case, the centrality interval indicated in Ref. [274] is $\langle N_{part} \rangle = 15.8 \pm 10$. The percentile range corresponding to this interval can be estimated to be approximately 65-90% based on Ref. [281, 282].

The role of diquarks

Coalescence models often calculate the formation of a baryon not as a $3 \rightarrow 1$ process but rather as a two-step process, in which first two quarks form a diquark and then the diquark combines with a third quark. However, this does not necessarily correspond to requiring the formation of diquarks as real bound states nor as effective degrees of freedom of the system. Whether this occurs or not is an open question. The suppression of the production of $\Sigma_c^{0,+}, ++$ states relative to Λ_c^+ ones in e^+e^- collisions and its removal in hadronic collisions is striking and appears to support the picture of diquark formation in string breaking.

While it is very hard to design what could be a “smoking gun” observation supporting the formation of diquarks is worth noticing that in [283] it was suggested that a measurement of Λ_c elliptic flow in Pb–Pb and its difference w.r.t. the D-meson one would allow to infer the relevance of diquark degrees of freedom in the QGP. This possibility is motivated by the comparison of the p_T dependence of the difference between $v_2(\Lambda_c)$ and $v_2(D^0)$ predicted in a coalescence approach and in the POWLANG mechanism. In the coalescence model the v_2 of Λ_c receives a contribution from two light quarks while the D meson only from one. In the POWLANG approach instead Λ_c^+ combines to a diquark evolving hydrodynamically with the bulk medium implying a milder difference w.r.t. D, in particular at intermediate p_T .

String-related investigations

There are several areas of interest in extending the current modelling of string hadronization. Some have already been mentioned above, including modelling of exotica and the heavy-ion limit of strings. Further areas of interest include considering colour reconnections in the initial state, the collective behaviour of strings, interactions between final state hadrons, studies into baryon production mechanisms, and even looking beyond Lund strings. Here we elaborate on just a few of these areas of interest.

One noticeable flaw as shown in Fig. 17 is the overprediction of the Λ_b^0/B^0 ratio by PYTHIA despite well predicting the Λ_c^+/D^0 ratio due to the inclusion of junction topologies. Exploration into other ratios involving these heavy flavour hadrons such as Λ_b^0/Λ_c^+ and B^0/D^0 would be particularly insightful into attempting to find the root of the discrepancy between model and experiment. Another set of observables that would be particularly interesting for studying junction modelling are baryon correlations. In the string model, baryons produced via standard diquark-antidiquark pair creation from string breaks would

be highly correlated. This correlation would be reduced given the popcorn model for diquark creation, which allows meson production between diquark-antidiquark pairs. Comparatively there is generally no expectation of a correlation between junction baryons and antijunction baryons.

As presented throughout this paper, there have been several already experimentally observed behaviours correlated to the size of the system, whether it be observables as a function of charged particle multiplicities or contrasting e^+e^- , pp and AA results. Many measurements have already shown clear indications of collective-like effects in pp collision environments, which prompts two key questions; are these effects present in e^+e^- collisions (and/or in $e^\pm p/e^\pm A$ ones), and how can we model such collective effects in the string picture? With regards to the former, many of these effects were not studied at LEP and hence there is little indication whether they are present in e^+e^- or not, thus it would be intriguing to study them at future high energy e^+e^- , $e^\pm p$, and $e^\pm A$ experiments [284].

Many collective effects in the string picture have already been studied in PYTHIA, including string tension modifications (e.g. Rope hadronization [47] and close-packing [48]), string interactions (e.g. string shoving [285, 286]) and final state hadron interactions (e.g. hadron rescattering [287]). Such models have already shown interesting effects and compelling agreement to data. For example, the string shoving model [285, 286] has already been shown to produce the near-sided ridge experimentally observed in pp collision events which is unexpected with the baseline string model. Studies of such models in AA environments will be particularly insightful to help determine whether a string model can reproduce other behaviours also typically considered QGP signatures such as flow. These models would also have particularly interesting effects on p_T spectra of hadrons, and further phenomenology studies would be useful to determine any signature behaviours of such models that experiments could attempt to identify. One can also consider interactions between final state hadrons via hadron rescattering [287], which would have effects particularly for high multiplicity events. For heavy flavour hadrons in particular, one would expect effects on the shape of the p_T spectra. It is interesting to note that such rescattering effects would also be interesting for studying the p/π ratio with respect to charged multiplicity in pp collision events, which PYTHIA currently overpredicts even without the inclusion of junctions.

Perhaps one of the most intriguing questions for the string model is whether a string in a densely packed string system hadronizes differently from a string in vacuum. There

are already indications that this is the case given enhancement of the light strange hadron-to-pion ratio as a function of charged multiplicity as seen by ALICE in Ref. [44]. Higher multiplicity events either correspond to the hadronization of longer strings or systems with a higher quantity of strings, and hence generally more densely packed string environments. There are already existing models such as Rope hadronization [47] and close-packing [48] which attempt to implement a strangeness enhancement mechanism by enhancing the string tension in more dense string systems. An increased string tension results in the reduction of the strangeness suppression via the Schwinger mechanism due to the strange quark mass. Both Rope hadronization and close-packing models have already been able to describe the general behaviour seen in the ALICE [44] data for the strange hadron-to-pion ratios as a function of multiplicity. Additionally, in pp collisions the majority of strings are aligned along the beam axis, which in turn would result in strangeness enhancement primarily for strings at low p_T , which would lead to strangeness enhancement for low p_T hadrons. One may be hopeful that this low p_T strangeness enhancement could describe the ratios involving heavy strange hadrons such as $\Xi_c^{+,0}$, however as mentioned in Sec. III C these strangeness enhancement mechanisms alone are unable to describe the level of strangeness enhancement needed to fit the $\Xi_c^{+,0}/\Lambda_c^+$ data whilst maintaining reasonable model parameters. Additional measurements involving strange b-hadrons would be vital in examining such mechanisms, so that one can make comparisons between distributions such as the Ξ_c/Λ_c and Ξ_b/Λ_b^0 ratios alongside the Ξ_c/D^0 and Ξ_b/B^0 ratios. These ratios would provide particularly insightful indications to the source of strangeness enhancement and whether the behaviour is different in the beauty and charm baryon sectors. Further data for ratios involving double strange heavy baryons such as Ω_c and Ω_b would also provide very useful insight. One could also explore the enhancement of strangeness around the junction itself which is not an unreasonable assumption as we know little about what the field around a junction itself should look like, and such a model would have significant impact as the majority of heavy flavour baryons are sourced from junctions. Likewise due to the sensitivity of heavy baryons on junction formation, further data for ratios involving Ξ_b and Ω_b may even help identify the source of the overprediction of the Λ_b^0/B^0 ratio using PYTHIA CR-BLC.

To study in further detail the hadronization of a string in vacuum compared to a densely packed string system, phenomenological studies would be insightful to examine hadron distributions for a single string compared to higher multiplets, given all the aforementioned

models, in order to check if there are any identifiable signatures experiments could attempt to find. To directly compare the fragmentation of a triplet vs. octet string, it would be insightful to examine hadron spectra in the tips of gluon jets compared to quark jets, LEP hairpin configurations, and perhaps even diffractive LHC events may allow for relatively clean environments to search for such behaviours.

Strings in heavy-ion collisions?

Through this review, models in PYTHIA useful for e^+e^- up to pp collisions were discussed. PYTHIA itself does not have the ability to perform pA and AA collisions. Instead, to simulate pA and AA collisions one can use the Angantyr model [288], which uses PYTHIA 8 as its base, taking inspiration from the Fritiof model [289, 290] and using the idea of wounded nucleons. A key feature of Angantyr is testing the assumption of continuing the usage of PYTHIA’s string fragmentation mechanisms to model the hadronization process also in pA and AA collisions, rather than assuming the formation of a QGP. This includes the implementation of the QCD-CR mechanisms described in Sect. II B 1, which allows CR between different nucleon-nucleon collisions [291, 292]. In principle one can also use Rope hadronization [47] and shoving [286] in conjunction with Angantyr, however the combination of Rope hadronization and Angantyr is yet to be validated to work properly, nor have the model parameters been tuned. Similarly, the string shoving model in Angantyr does not yet perform well for full collisions due technical handling difficulties of soft gluon modelling. Nonetheless toy configurations using the model have already shown that the model itself can generate v_2 , though further work on the string shoving implementation is required for more detailed studies. For a review of the current state of the above models in heavy-ion collisions, see [293]. Though Angantyr in its current state does not fully describe the collective behaviour of high string densities for full collision events, the existing implementation already provides insight into the non-collective background of such observables and provides an important comparison between the QGP and the string model for hadronization.

This also prompts the interesting question of whether there is a some quenching limit for strings. That is, within this type of modelling paradigm, at high enough string densities, do the string states cease to exist and instead do we get a transition into some deconfined QGP state? This then begs the question when would this transition occur, what would this transitional state look like, and how would one model it. These are largely unexplored

questions within the string picture, and the study of AA collisions with string hadronization using Angantyr provides the first step to exploring such questions.

Heavy-flavour jets and correlations

The study of beauty- and charm-tagged jets provides additional information for interpreting the modification of the baryon-to-meson ratios from e^+e^- to hadronic collisions, giving a handle to connect it to possible modification of heavy-quark fragmentation and jet properties. Measurements of jets tagged by the presence of a fully reconstructed heavy-flavour hadron can be particularly informative. This tagging technique, with respect to others based on the recognition of a displaced secondary vertex or on lepton tagging, has the advantage of providing the momentum vector of the heavy-flavour hadron and its correlation to the jet momentum. Though used since UA1 times, in recent years it was refined and exploited to study the production and sub-structure properties of D-meson tagged jets [164, 294–299], as well as for the first direct observation of the “dead-cone” effect [300]. These measurements allow testing the modelling of jet fragmentation, as well as of charm-production processes, in event generators like PYTHIA and HERWIG [17, 301, 302], possibly interfaced with POWHEG [204, 303, 304]. Relevant variables include the fraction of jet momentum carried by the charm hadron, calculated along the jet axis direction ($z_{\parallel}^{\text{ch}}$), and the transverse momenta and (pseudo)rapidities of hadrons measured with respect to the jet axis.

As extensively discussed in Ref. [297], the $z_{\parallel}^{\text{ch}}$ distribution of D-meson tagged jets measured by the ALICE Collaboration is quite well described by Monte Carlo event generators. Recently, ALICE reported a first measurement of the same distribution for Λ_c^+ -tagged jets. The comparison with D-meson tagged jet data done with the same jet and hadron kinematic selection is reported in Fig. 28. Though the uncertainties prevent firm conclusions, the data suggest that Λ_c^+ carry a smaller fraction of jet momentum along the jet axis with respect to D mesons. This trend contrasts with that expected by the default version of PYTHIA 8 (Monash tune), while it agrees with that from PYTHIA 8 CR-BLC. The trend expected by Monash reflects the tendency in jet fragmentation that heavier particles carry a larger fraction of jet momentum, which in a collinear fragmentation picture can be related to energy conservation. The data therefore suggest that either the Λ_c^+ production is favoured in jets with higher momentum and softer fragmentation, either intrinsically or because modified by the interplay with the underlying event, or that the Λ_c^+ momentum vector is less aligned

with the jet one, either as an intrinsic feature of charm-jet fragmentation to Λ_c^+ baryons (not expected however in Monash) or because of an angular decorrelation at hadronization time. A partly related study is that of the azimuthal correlation of Λ_c^+ baryons with charged particles produced in the event.

A first preliminary measurement, performed by ALICE [305], indicates that the yields of low- p_T associated particles are large, both in the near-side and in the opposite direction to the Λ_c^+ (away-side jet region), and resemble those observed only at much higher D-meson p_T ($p_T \gtrsim 8 \text{ GeV}/c$) in correlations of D mesons with charged particles. Naively one could expect that, except for the initial-parton energy correlation, the fragmentation (parton-shower) and hadronization of the near- and away-side jets should proceed almost independently. It is thus surprising that the larger near-side yield, which is consistent with the softer jet fragmentation suggested by the $z_{\parallel}^{\text{ch}}$ analysis, is accompanied by a difference in the away-side jet.

Taken together, the $z_{\parallel}^{\text{ch}}$ and azimuthal correlation data may suggest that, with respect to D mesons, low- p_T Λ_c^+ are produced on average in jets with higher p_T and softer fragmentation, with a sharing of the jet energy among several soft particles. Whether this could be due to an interplay with the underlying event is not clear, though possible, considering also the multiplicity dependence of Λ_c^+/D^0 ratio.

More precise measurements, possibly more differential in jet and hadron kinematics, and a detailed analysis of the jet radial profiles and substructure and of the correlation-function widths could in the future shed light on these intriguing observations. Similar measurements in the beauty sector would also be very useful.

On top of new measurements, it would be desirable in the future to understand what hadron-formation via coalescence implies for these observables. In the coalescence process, the Λ_c^+ at a given p_T gets on average more of its momentum from the light quarks with respect to the D meson (because two light quarks are involved for forming Λ_c^+). This can decorrelate the resulting hadron momentum vector from the jet axis. Therefore, though explicit calculations are missing, it would be in principle compatible with the observation to assume that in the jet a Λ_c^+ formed by coalescence of the charm quark with light quarks from the underlying event carries a smaller longitudinal momentum fraction (along the jet axis) relative to that carried by D mesons.

High-mass excited baryon states




FIG. 28: Comparison (top panel) and ratio (bottom panel) of the distributions of the Λ_c^+ and D^0 longitudinal track-based jet-momentum fraction ($z_{||}^{\text{ch}}$). Track-based jets, defined by their charged-particle constituents only, with $7 < p_T < 15$ GeV/c are tagged with fully reconstructed Λ_c^+ and D^0 with $3 < p_T < 15$ GeV/c. In the bottom panel the ratio is compared to expectations from PYTHIA 8 default tune (Monash) and PYTHIA 8 tune with colour-reconnection implemented beyond leading colour. Figure from Ref. [299]

Experimental search of not yet observed charm and beauty hadron resonances is of primary importance in the context of hadronization. It is needed to determine whether the additional baryon resonance states predicted by the RQM, which are largely supported by lattice-QCD computations of the vacuum spectroscopy, exist and to determine their spectral properties. As discussed extensively in this review, the existence of these states is a necessary assumption in many models to reproduce the Λ_c^+/D^0 yield ratio in pp and heavy-ion collisions, in particular for models based on statistical hadronization. Though it remains an open question why these high-mass resonance states have not been observed so far in e^+e^- collisions, proving their existence and measuring the branching ratio to relevant decay channels could be pursued at e^+e^- colliders, e.g. by the Belle II Collaboration, as well as

in pp collisions by the ATLAS, CMS, and LHCb Collaborations, leveraging the large LHC luminosities.

Actually, on top of verifying the number and spectral properties of yet unobserved states, a fundamental test for SHM would be given by a measurement of the production yields of excited mesons and baryons, both known and unknown ones. ALICE recently performed the first measurement of $D_{s1}^+(2536)$ and $D_{s2}^{*+}(2573)$ resonance yields in pp collisions, which provide further pieces of information to investigate the charm-quark hadronization [306]. Cross-section measurements of excited Λ_c^+ , $\Sigma_c^{0,+;++}$, $\Xi_c^{+,0}$ states should be feasible with the Run 3 data at the LHC.

B_c^+ meson

The B_c^+ meson contains a b and a c quark, making it (and its excited states) the only hadron observed so far that contains heavy quarks of two different flavours. The B_c^+ meson has a net flavour number, which in principle secludes it from the quarkonium family. However, one could support that the proximity of its quark content to the charmonium and bottomonium states (“hidden” heavy-flavour mesons) makes it an exotic heavy quarkonium.

The B_c^+ meson has a particularly low production cross section in pp collisions, because two heavy quark pairs ($b\bar{b}$ and $c\bar{c}$) need to be produced. The obvious mechanism is for both of these heavy-quark pairs to be produced in a single hard-scattering process, but since this is quite suppressed, additional production mechanisms may play a role such as multi-parton interactions in high-multiplicity pp collisions [307] and/or quark recombination in heavy-ion ones. That is, a b quark produced in a given hard scattering could recombine with a c quark from another parton-parton or nucleon-nucleon collision (presumably with some space-time suppression since the pair needs to be sufficiently close to form a B_c^+).

If this is a significant mechanism in heavy-ion collisions, the B_c^+ yields might be dramatically augmented compared to the expectations from N_{coll} -scaling, considering the small primary production expected from the pp cross section. The CMS Collaboration has measured for the first time the B_c^+ production in heavy-ion collisions and reported that the B_c^+ meson is shown to be less suppressed than quarkonia and most of the open heavy-flavour mesons, suggesting that effects of the hot and dense nuclear matter created in heavy-ion collisions contribute to its production [308]. However, the acceptance of the CMS detector only allows to reconstruct B_c^+ mesons of relatively high transverse momentum, typically p_T

$> 6 \text{ GeV}/c$, while the majority of the B_c^+ mesons produced by recombination should have a p_T lower than the acceptance threshold of CMS. This is because most of the charm quarks present in the QGP have low p_T and because the recombining quarks need to have a small relative momentum (typically not larger than the binding energy) to be able to recombine.

Hence, it would be extremely beneficial to measure low transverse momentum B_c^+ in heavy-ion collisions and in high-multiplicity pp ones. Recently, Egede et al. [307] predicted a large fraction of the produced yield in high-multiplicity pp collisions to come from MPI (albeit without accounting for possible space-time suppression effects so this should probably be taken as a maximum), and Rapp et al. [309] predict a similar trend in heavy-ion collisions from regenerated B_c^+ mesons. In this latter study they observed that the large regeneration contributions cause a markedly rising R_{AA} with centrality, reaching values of up to 4-6 in central collisions. In this model, the inclusive p_T -dependent R_{AA} for the B_c^+ is dominated by regeneration contributions for $p_T < 10\text{-}15 \text{ GeV}/c$ in semi-/central collisions, reaching values of around 10 at low p_T . It is pointed out in the publication that the results for the R_{AA} are rather sensitive to the B_c^+ production cross section in pp collisions. A more precise measurement of this quantity, and a significant reduction of the statistical and systematic uncertainties of B_c^+ in heavy-ion collisions will provide unprecedented insights into heavy-flavour in-medium and is a promising new probe to study the interplay between the suppression and enhancement mechanisms in the production of heavy-flavour mesons in the QGP.

Multi-charm hadron states and charm nuclei

Analogously to the B_c^+ case, another window to investigate colour-reconnection and coalescence are the measurements of multi-charm baryons and of charm nuclei. Measurements of multi-charm hadrons, such as the Ξ_{cc}^+ , Ξ_{cc}^{++} , Ω_{cc}^+ , Ω_{ccc}^{++} would provide a direct window on hadron formation from a deconfined quark–gluon plasma. In fact, the yields of multicharm baryons relative to the number of produced charm quarks are predicted to be significantly enhanced in AA relative to pp collisions [40, 74, 310–314]. Enhancements are expected by as much as a factor 10^2 for Ξ_{cc} baryon and even by as much as a factor 10^3 for the as yet undiscovered Ω_{ccc} baryon. Most recently, the SHMc and the Catania models [40, 74] provided predictions for the production of multi-charmed hadrons in Pb–Pb collisions and they explored the system size dependence through Kr–Kr, to Ar–Ar and O–O collisions.

The yields are predicted to be quite similar in the case of full thermalization of the charm quark, a condition that might not be achieved in light systems like O-O. The coalescence picture coupled to a realistic dynamical simulation for charm quarks reveals that Ω_{ccc}^{++} yield, and even more its p_T spectrum, would provide a sensitive probe of charm thermalization and its evolution with the system size of the colliding system [74]. Such studies are currently far beyond the experimental reach and a comprehensive program of measurements in the multi-charm sector is discussed to be carried out with the proposed future ALICE 3 detector [75].

The unique combination of high rates, wide acceptance, strong particle identification capabilities, and excellent secondary vertex determination of the proposed ALICE 3 detector, also provide a toolbox for the search for light nuclei with charm. At LHC energies, the most promising candidates are the c-deuteron, c-triton and c-³He. The existence of such weakly decaying bound states with lifetimes similar to those of other unbound charmed baryons is debated in the literature. In case these states are bound and under the assumption that their abundance in collisions of nuclei is described by the SHM, the yields are large enough to bring their experimental discovery within reach in the next decades and to additionally test different hadronization models.

Exotica

The $\chi_{c1}(3872)$ is an exotic particle that was first observed by the Belle Collaboration [315], and then confirmed and studied by other experiments at electron-positron [316] and hadron colliders [317–321]. The nature of this particle is still not fully understood and interpretations in terms of conventional charmonium (a bound state of charm-anticharm quarks), D-meson molecule, tetraquark, or an admixture these states have been proposed [322]. Heavy-ion collisions, as well as high multiplicity pp collisions, offer a unique window into the properties of this poorly understood hadron. In these systems, promptly produced $\chi_{c1}(3872)$ hadrons can interact with other particles in the nucleus and/or those produced in the collision. The influence of these interactions on the observed $\chi_{c1}(3872)$ yields provides information that can help discriminating between the various models of its structure, as well as give insight into the dynamics of the bulk of the particles produced in these collisions. The LHCb Collaboration has measured a significant decrease in the ratio of prompt $\chi_{c1}(3872)$ to $\psi(2S)$ cross sections in pp collisions with increasing charged-particle multiplicity [323].

These data were interpreted in terms of breakup of the $\chi_{c1}(3872)$ hadron due to interactions with comoving particles produced in the event, for both compact and molecular models of $\chi_{c1}(3872)$ structure [324, 325]. A relatively-compact tetraquark is preferred in this case, but it is currently discussed how conclusive this comparison is [326–329]. The LHCb Collaboration has also recently performed the same measurement in p–Pb collisions [330]. In this collision system the ratio is measured to be higher than the one measured in pp collisions. It must be noted that the evolution of $\psi(2S)$ production with particle multiplicity is not fully understood yet. This complicates the interpretation of $\chi_{c1}(3872)$ data, when $\psi(2S)$ is used as a reference. The CMS collaboration has measured the $\sigma_{\chi_{c1}(3872)}/\sigma_{\psi(2S)}$ ratio in Pb–Pb collisions at high p_T , and found that the ratio is further enhanced relative to pp and p–Pb collisions, although the uncertainties and the significantly different p_T intervals of the measurements preclude drawing firm conclusions [331]. Calculations based on quark coalescence show that production rates of $\chi_{c1}(3872)$ hadrons in AA collisions are sensitive to its structure. In these models, the production of compact tetraquarks is expected to be enhanced over hadronic molecules [332, 333]. However, a recent transport calculation reaches the opposite conclusion [326]. Late-stage interactions in the hadron gas phase of a heavy-ion collision can also modify the yields [334]. It is currently unknown where the crossover between the suppressing effect of breakup and the enhancing effect of coalescence may occur. The increase of the ratio of cross sections $\sigma_{\chi_{c1}(3872)}/\sigma_{\psi(2S)}$ from pp to p–Pb to Pb–Pb collisions may indicate that the exotic $\chi_{c1}(3872)$ hadron experiences different dynamics in the medium than those relevant for a “conventional” charmonium state like $\psi(2S)$. If the experiments could in the future cover similar p_T intervals in the different collision systems and multiplicities/centralities, possibly better assessing the lower p_T region, these measurements will provide new constraints to determine the internal $\chi_{c1}(3872)$ structure as well as to model parton transport and hadronization in nuclear collisions. In this context, it will also be important to precisely measure the production cross section of other exotic states, like the T_{cc}^+ .

A related possible future implementation in PYTHIA is the inclusion of exotica. Not only does QCD-CR allow beyond LC topologies such as junctions, but it also allows for more complicated structures called junction networks. These junction networks are string configurations that consist of multiple junctions within the structure and provide a natural way within the string picture to represent tetraquarks, pentaquarks, etc. For example, the

simplest of these structures are junction-antijunction configurations which consist of two colour-charged endpoints and two anticolour-charged endpoints as shown in Fig. 29. When these junction-antijunction configurations are encountered as high mass systems, PYTHIA currently handles these structures by making breaks on the string piece connecting the junction to the antijunction, and then fragmenting each junction system separately. However, should a junction-antijunction system have a low invariant mass, one could propose that the system does not fragment and instead can be treated as a tetraquark. The same argument holds for larger junction networks. The inclusion of exotica is not yet implemented in PYTHIA and it would not be straightforward to implement the required significant modifications to the existing code, however junction networks are already present and could provide a sensible starting point for modelling such structures.




FIG. 29: Junction-antijunction formation in the string model. The left images show the initial string configuration in the LC limit, and the right images depict the possible alternative configuration given the respective colour reconnection models.

Collectivity in small systems

Positive v_2 values have been observed for both open charm [336–338] and J/ψ [335, 339] also in high-multiplicity p–Pb collisions, as well as in high-multiplicity pp collisions [340]. As shown in Fig. 30, in high-multiplicity p–Pb collisions D^0 and J/ψ v_2 reach similar maximum values, which are about a factor of two smaller than the maximum v_2 of light hadrons [341] and significantly smaller than the maximum observed in semi-central Pb–Pb collisions for D mesons. Though the maximum J/ψ v_2 values are similar in high-multiplicity p–Pb collisions and semi-central Pb–Pb collisions, in the latter case positive values, close to open-charm and light-flavour ones, are observed up to higher p_T . The origin of flow in small collisions systems are still debated, even for light-flavour particles [342]. Hadronization via recombination could induce a positive v_2 for open-charm hadrons even in the case of a small/negligible v_2 of charm




FIG. 30: Elliptic flow of prompt J/ψ at forward+backward rapidity ($-2.86 < y_{\text{cm}} < -1.86$ or $0.94 < y_{\text{cm}} < 1.94$), and of D^0 , Λ and K_s^0 at midrapidity shown as a function of p_T in high-multiplicity p-Pb collisions at $\sqrt{s} = 8.16\text{TeV}$ [335, 336].

quarks [65]. This is of course not the case for charmonia. The absence of clear experimental evidences of charm energy loss, makes the observation of open charm and charmonia flow particularly interesting to understand the interplay of initial-state and final-state effects for the generation of azimuthal anisotropy in momentum space. A possible dynamic not yet firmly identified could lead to an $R_{AA}(p_T)$ close to unity together with a sizeable $v_2(p_T)$ is the super-diffusion in the initial stage glasma phase that would lead to an increase of the $R_{AA}(p_T)$ [262, 343, 344] followed by a moderate energy loss that generate a sizeable elliptic flow.

ACKNOWLEDGEMENTS

J.A. and P.S. acknowledge support from The Royal Society and the Wolfson Foundation (UK), from the Australian Research Council Discovery Project DP230103014, and from the Monash-Warwick Alliance for Particle Physics. V.G. acknowledge support PRIN2022 under

fundings EU Next Generation (project code 2022SM5YAS).

- [1] D. J. Schwarz, The first second of the universe, *Annalen Phys.* **12**, 220 (2003), [arXiv:astro-ph/0303574](#).
- [2] P. Castorina, V. Greco, and S. Plumari, QCD equation of state and cosmological parameters in the early universe, *Phys. Rev. D* **92**, 063530 (2015), [arXiv:1505.07655 \[hep-ph\]](#).
- [3] M. Cacciari, M. Greco, and P. Nason, The P(T) spectrum in heavy flavor hadroproduction, *JHEP* **05**, 007, [arXiv:hep-ph/9803400](#).
- [4] M. Cacciari, S. Frixione, N. Houdeau, M. L. Mangano, P. Nason, and G. Ridolfi, Theoretical predictions for charm and bottom production at the LHC, *JHEP* **10**, 137, [arXiv:1205.6344 \[hep-ph\]](#).
- [5] B. A. Kniehl, G. Kramer, I. Schienbein, and H. Spiesberger, Inclusive D^{*+-} production in p anti- p collisions with massive charm quarks, *Phys. Rev. D* **71**, 014018 (2005), [arXiv:hep-ph/0410289](#).
- [6] B. A. Kniehl, G. Kramer, I. Schienbein, and H. Spiesberger, Collinear subtractions in hadroproduction of heavy quarks, *Eur. Phys. J.* **C41**, 199 (2005), [arXiv:hep-ph/0502194 \[hep-ph\]](#).
- [7] B. Kniehl, G. Kramer, I. Schienbein, and H. Spiesberger, Inclusive Charmed-Meson Production at the CERN LHC, *Eur. Phys. J. C* **72**, 2082 (2012), [arXiv:1202.0439 \[hep-ph\]](#).
- [8] I. Helenius and H. Paukkunen, Revisiting the D-meson hadroproduction in general-mass variable flavour number scheme, *JHEP* **05**, 196, [arXiv:1804.03557 \[hep-ph\]](#).
- [9] E. Braaten, K.-M. Cheung, S. Fleming, and T. C. Yuan, Perturbative QCD fragmentation functions as a model for heavy quark fragmentation, *Phys. Rev. D* **51**, 4819 (1995), [arXiv:hep-ph/9409316](#).
- [10] T. Sjöstrand, S. Mrenna, and P. Z. Skands, PYTHIA 6.4 Physics and Manual, *JHEP* **05**, 026, [arXiv:hep-ph/0603175 \[hep-ph\]](#).
- [11] P. Skands, S. Carrazza, and J. Rojo, Tuning PYTHIA 8.1: the Monash 2013 Tune, *Eur. Phys. J. C* **74**, 3024 (2014), [arXiv:1404.5630 \[hep-ph\]](#).
- [12] M. Bahr *et al.*, Herwig++ Physics and Manual, *Eur. Phys. J. C* **58**, 639 (2008), [arXiv:0803.0883 \[hep-ph\]](#).

- [13] T. Aaltonen *et al.* (CDF), Measurement of Ratios of Fragmentation Fractions for Bottom Hadrons in $p\bar{p}$ Collisions at $\sqrt{s} = 1.96$ -TeV, *Phys. Rev. D* **77**, 072003 (2008), [arXiv:0801.4375 \[hep-ex\]](#).
- [14] The ALICE experiment – A journey through QCD, (2022), [arXiv:2211.04384 \[nucl-ex\]](#).
- [15] D. d’Enterria and C. Loizides, Progress in the Glauber Model at Collider Energies, *Ann. Rev. Nucl. Part. Sci.* **71**, 315 (2021), [arXiv:2011.14909 \[hep-ph\]](#).
- [16] C. Bierlich *et al.*, A comprehensive guide to the physics and usage of PYTHIA 8.3 10.21468/SciPostPhysCodeb.8 (2022), [arXiv:2203.11601 \[hep-ph\]](#).
- [17] J. Bellm *et al.*, Herwig 7.0/Herwig++ 3.0 release note, *Eur. Phys. J. C* **76**, 196 (2016), [arXiv:1512.01178 \[hep-ph\]](#).
- [18] B. Andersson, G. Gustafson, G. Ingelman, and T. Sjöstrand, Parton Fragmentation and String Dynamics, *Phys. Rept.* **97**, 31 (1983).
- [19] E. Eichten, K. Gottfried, T. Kinoshita, K. D. Lane, and T.-M. Yan, Charmonium: The Model, *Phys. Rev. D* **17**, 3090 (1978), [Erratum: *Phys.Rev.D* 21, 313 (1980)].
- [20] G. S. Bali and K. Schilling, Static quark - anti-quark potential: Scaling behavior and finite size effects in SU(3) lattice gauge theory, *Phys. Rev. D* **46**, 2636 (1992).
- [21] B. Andersson, S. Mohanty, and F. Söderberg, The Lund fragmentation process for a multigluon string according to the area law, *Eur. Phys. J. C* **21**, 631 (2001), [arXiv:hep-ph/0106185](#).
- [22] J. S. Schwinger, On gauge invariance and vacuum polarization, *Phys. Rev.* **82**, 664 (1951).
- [23] C. Bierlich, S. Chakraborty, G. Gustafson, and L. Lönnblad, Hyperfine splitting effects in string hadronization, *Eur. Phys. J. C* **82**, 228 (2022), [arXiv:2201.06316 \[hep-ph\]](#).
- [24] K. Hamacher and M. Weierstall (DELPHI), The Next round of hadronic generator tuning heavily based on identified particle data, (1995), [arXiv:hep-ex/9511011](#).
- [25] R. Barate *et al.* (ALEPH), Studies of quantum chromodynamics with the ALEPH detector, *Phys. Rept.* **294**, 1 (1998).
- [26] S. Amoroso, S. Caron, A. Jueid, R. Ruiz de Austri, and P. Skands, Estimating QCD uncertainties in Monte Carlo event generators for gamma-ray dark matter searches, *JCAP* **05**, 007, [arXiv:1812.07424 \[hep-ph\]](#).
- [27] J. Bellm and L. Gellersen, High dimensional parameter tuning for event generators, *Eur. Phys. J. C* **80**, 54 (2020), [arXiv:1908.10811 \[hep-ph\]](#).

- [28] A. Jueid, J. Kip, R. R. de Austri, and P. Skands, The Strong Force meets the Dark Sector: a robust estimate of QCD uncertainties for anti-matter dark matter searches, (2023), [arXiv:2303.11363 \[hep-ph\]](#).
- [29] M. G. Bowler, $e^+ e^-$ Production of Heavy Quarks in the String Model, *Z. Phys. C* **11**, 169 (1981).
- [30] B. R. Webber, Fragmentation and hadronization, *Int. J. Mod. Phys. A* **15S1**, 577 (2000), [arXiv:hep-ph/9912292](#).
- [31] S. Gieseke, P. Kirchgaerber, and S. Platzer, Baryon production from cluster hadronisation, *Eur. Phys. J. C* **78**, 99 (2018), [arXiv:1710.10906 \[hep-ph\]](#).
- [32] J. Bellm, C. B. Duncan, S. Gieseke, M. Myska, and A. Siódmok, Spacetime colour reconnection in Herwig 7, *Eur. Phys. J. C* **79**, 1003 (2019), [arXiv:1909.08850 \[hep-ph\]](#).
- [33] J. R. Christiansen and P. Z. Skands, String Formation Beyond Leading Colour, *JHEP* **08**, 003, [arXiv:1505.01681 \[hep-ph\]](#).
- [34] Y. Oh, C. M. Ko, S. H. Lee, and S. Yasui, Heavy baryon/meson ratios in relativistic heavy ion collisions, *Phys. Rev. C* **79**, 044905 (2009), [arXiv:0901.1382 \[nucl-th\]](#).
- [35] J. Song, H.-h. Li, and F.-l. Shao, New feature of low p_T charm quark hadronization in pp collisions at $\sqrt{s} = 7$ TeV, *Eur. Phys. J. C* **78**, 344 (2018), [arXiv:1801.09402 \[hep-ph\]](#).
- [36] V. Minissale, S. Plumari, and V. Greco, Charm hadrons in pp collisions at LHC energy within a coalescence plus fragmentation approach, *Phys. Lett. B* **821**, 136622 (2021), [arXiv:2012.12001 \[hep-ph\]](#).
- [37] S. Plumari, V. Minissale, S. K. Das, G. Coci, and V. Greco, Charmed Hadrons from Coalescence plus Fragmentation in relativistic nucleus-nucleus collisions at RHIC and LHC, *Eur. Phys. J. C* **78**, 348 (2018), [arXiv:1712.00730 \[hep-ph\]](#).
- [38] M. He and R. Rapp, Charm-Baryon Production in Proton-Proton Collisions, *Phys. Lett. B* **795**, 117 (2019), [arXiv:1902.08889 \[nucl-th\]](#).
- [39] M. He and R. Rapp, Hadronization and Charm-Hadron Ratios in Heavy-Ion Collisions, *Phys. Rev. Lett.* **124**, 042301 (2020), [arXiv:1905.09216 \[nucl-th\]](#).
- [40] A. Andronic, P. Braun-Munzinger, M. K. Köhler, A. Mazeliauskas, K. Redlich, J. Stachel, and V. Viskovic, The multiple-charm hierarchy in the statistical hadronization model, *JHEP* **07**, 035, [arXiv:2104.12754 \[hep-ph\]](#).
- [41] B. Andersson, *The Lund model*, Vol. 7 (Cambridge University Press, 2005).

- [42] B. Andersson, G. Gustafson, and T. Sjöstrand, Baryon Production in Jet Fragmentation and Υ Decay, *Phys. Scripta* **32**, 574 (1985).
- [43] P. Eden and G. Gustafson, Baryon production in the string fragmentation picture, *Z. Phys. C* **75**, 41 (1997), [arXiv:hep-ph/9606454](#).
- [44] J. Adam *et al.* (ALICE), Enhanced production of multi-strange hadrons in high-multiplicity proton-proton collisions, *Nature Phys.* **13**, 535 (2017), [arXiv:1606.07424 \[nucl-ex\]](#).
- [45] S. Acharya *et al.* (ALICE), Multiplicity dependence of (multi-)strange hadron production in proton-proton collisions at $\sqrt{s} = 13$ TeV, *Eur. Phys. J. C* **80**, 167 (2020), [arXiv:1908.01861 \[nucl-ex\]](#).
- [46] C. Bierlich, Hadronisation Models and Colour Reconnection, *PoS DIS2016*, 051 (2016), [arXiv:1606.09456 \[hep-ph\]](#).
- [47] C. Bierlich, Rope Hadronization and Strange Particle Production, *EPJ Web Conf.* **171**, 14003 (2018), [arXiv:1710.04464 \[nucl-th\]](#).
- [48] N. Fischer and T. Sjöstrand, Thermodynamical String Fragmentation, *JHEP* **01**, 140, [arXiv:1610.09818 \[hep-ph\]](#).
- [49] R. L. Workman and Others (Particle Data Group), Review of Particle Physics, *PTEP* **2022**, 083C01 (2022).
- [50] M. He and R. Rapp, Bottom Hadrochemistry in High-Energy Hadronic Collisions, *Phys. Rev. Lett.* **131**, 012301 (2023), [arXiv:2209.13419 \[hep-ph\]](#).
- [51] D. Ebert, R. Faustov, and V. Galkin, Spectroscopy and Regge trajectories of heavy baryons in the relativistic quark-diquark picture, *Phys. Rev. D* **84**, 014025 (2011), [arXiv:1105.0583 \[hep-ph\]](#).
- [52] M. Padmanath, R. G. Edwards, N. Mathur, and M. J. Peardon, Spectroscopy of charmed baryons from lattice QCD, *PoS LATTICE2014*, 084 (2015), [arXiv:1410.8791 \[hep-lat\]](#).
- [53] A. Andronic, P. Braun-Munzinger, H. Brunßen, J. Crkovská, J. Stachel, V. Vislavicius, and M. Völkl, Transverse dynamics of charmed hadrons in ultra-relativistic nuclear collisions, (2023), [arXiv:2308.14821 \[hep-ph\]](#).
- [54] F. Capellino, A. Dubla, S. Floerchinger, E. Grossi, A. Kirchner, and S. Masciocchi, Fluid-dynamics of charm quarks in the quark–gluon plasma, (2023), [arXiv:2307.14449 \[hep-ph\]](#).
- [55] F. Capellino, A. Beraudo, A. Dubla, S. Floerchinger, S. Masciocchi, J. Pawłowski, and I. Seluzhenkov, Fluid-dynamic approach to heavy-quark diffusion in the quark-gluon plasma,

- [Phys. Rev. D **106**, 034021 \(2022\)](#), [arXiv:2205.07692 \[nucl-th\]](#).
- [56] V. Greco, C. M. Ko, and P. Levai, Parton coalescence at RHIC, [Phys. Rev. C **68**, 034904 \(2003\)](#), [arXiv:nucl-th/0305024](#).
- [57] V. Greco, C. M. Ko, and P. Levai, Parton coalescence and anti-proton / pion anomaly at RHIC, [Phys. Rev. Lett. **90**, 202302 \(2003\)](#), [arXiv:nucl-th/0301093](#).
- [58] R. J. Fries, B. Muller, C. Nonaka, and S. A. Bass, Hadron production in heavy ion collisions: Fragmentation and recombination from a dense parton phase, [Phys. Rev. C **68**, 044902 \(2003\)](#), [arXiv:nucl-th/0306027](#).
- [59] R. J. Fries, B. Muller, C. Nonaka, and S. A. Bass, Hadronization in heavy ion collisions: Recombination and fragmentation of partons, [Phys. Rev. Lett. **90**, 202303 \(2003\)](#), [arXiv:nucl-th/0301087](#).
- [60] D. Molnar and S. A. Voloshin, Elliptic flow at large transverse momenta from quark coalescence, [Phys. Rev. Lett. **91**, 092301 \(2003\)](#), [arXiv:nucl-th/0302014](#).
- [61] R. J. Fries, V. Greco, and P. Sorensen, Coalescence Models For Hadron Formation From Quark Gluon Plasma, [Ann. Rev. Nucl. Part. Sci. **58**, 177 \(2008\)](#), [arXiv:0807.4939 \[nucl-th\]](#).
- [62] V. Greco and C. M. Ko, Effect of resonance decays on hadron elliptic flows, [Phys. Rev. C **70**, 024901 \(2004\)](#), [arXiv:nucl-th/0402020](#).
- [63] L. Ravagli and R. Rapp, Quark Coalescence based on a Transport Equation, [Phys. Lett. B **655**, 126 \(2007\)](#), [arXiv:0705.0021 \[hep-ph\]](#).
- [64] V. Minissale, F. Scardina, and V. Greco, Hadrons from coalescence plus fragmentation in AA collisions at energies available at the BNL Relativistic Heavy Ion Collider to the CERN Large Hadron Collider, [Phys. Rev. C **92**, 054904 \(2015\)](#), [arXiv:1502.06213 \[nucl-th\]](#).
- [65] V. Greco, C. M. Ko, and R. Rapp, Quark coalescence for charmed mesons in ultrarelativistic heavy ion collisions, [Phys. Lett. B **595**, 202 \(2004\)](#), [arXiv:nucl-th/0312100 \[nucl-th\]](#).
- [66] S. K. Das, F. Scardina, S. Plumari, and V. Greco, Toward a solution to the R_{AA} and v_2 puzzle for heavy quarks, [Phys. Lett. B **747**, 260 \(2015\)](#), [arXiv:1502.03757 \[nucl-th\]](#).
- [67] F. Scardina, S. K. Das, V. Minissale, S. Plumari, and V. Greco, Estimating the charm quark diffusion coefficient and thermalization time from D meson spectra at energies available at the BNL Relativistic Heavy Ion Collider and the CERN Large Hadron Collider, [Phys. Rev. C **96**, 044905 \(2017\)](#), [arXiv:1707.05452 \[nucl-th\]](#).

- [68] Z.-w. Lin and D. Molnar, Quark coalescence and elliptic flow of charm hadrons, *Phys. Rev. C* **68**, 044901 (2003), [arXiv:nucl-th/0304045](#).
- [69] M. Lisovyi, A. Verbytskyi, and O. Zenaiev, Combined analysis of charm-quark fragmentation-fraction measurements, *Eur. Phys. J. C* **76**, 397 (2016), [arXiv:1509.01061 \[hep-ex\]](#).
- [70] J. Adam *et al.* (STAR), First measurement of Λ_c baryon production in Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys. Rev. Lett.* **124**, 172301 (2020), [arXiv:1910.14628 \[nucl-ex\]](#).
- [71] S. Acharya *et al.* (ALICE), Λ_c^+ production in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **793**, 212 (2019), [arXiv:1809.10922 \[nucl-ex\]](#).
- [72] S. Acharya *et al.* (ALICE), Constraining hadronization mechanisms with Λ_c^+/D^0 production ratios in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **839**, 137796 (2023), [arXiv:2112.08156 \[nucl-ex\]](#).
- [73] A. Tumasyan *et al.* (CMS), Study of charm hadronization with prompt Λ_c^+ baryons in proton-proton and lead-lead collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **01**, 128, [arXiv:2307.11186 \[nucl-ex\]](#).
- [74] V. Minissale, S. Plumari, Y. Sun, and V. Greco, Multi-charmed and singled charmed hadrons from coalescence: yields and ratios in different collision systems at LHC, *Eur. Phys. J. C* **84**, 228 (2024), [arXiv:2305.03687 \[hep-ph\]](#).
- [75] Letter of intent for ALICE 3: A next-generation heavy-ion experiment at the LHC, (2022), [arXiv:2211.02491 \[physics.ins-det\]](#).
- [76] V. Khachatryan *et al.* (CMS), Measurement of long-range near-side two-particle angular correlations in pp collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. Lett.* **116**, 172302 (2016), [arXiv:1510.03068 \[nucl-ex\]](#).
- [77] S. Acharya *et al.* (ALICE), Λ_c^+ Production and Baryon-to-Meson Ratios in pp and p-Pb Collisions at $\sqrt{s_{NN}}=5.02$ TeV at the LHC, *Phys. Rev. Lett.* **127**, 202301 (2021), [arXiv:2011.06078 \[nucl-ex\]](#).
- [78] S. Acharya *et al.* (ALICE), Λ_c^+ production in pp and in p-Pb collisions at $\sqrt{s_{NN}}=5.02$ TeV, *Phys. Rev. C* **104**, 054905 (2021), [arXiv:2011.06079 \[nucl-ex\]](#).
- [79] R. D. Weller and P. Romatschke, One fluid to rule them all: viscous hydrodynamic description of event-by-event central p+p, p+Pb and Pb+Pb collisions at $\sqrt{s} = 5.02$ TeV, *Phys. Lett. B* **774**, 351 (2017), [arXiv:1701.07145 \[nucl-th\]](#).

- [80] M. Greif, C. Greiner, B. Schenke, S. Schlichting, and Z. Xu, Importance of initial and final state effects for azimuthal correlations in p+Pb collisions, *Phys. Rev. D* **96**, 091504 (2017), [arXiv:1708.02076 \[hep-ph\]](#).
- [81] Y. Sun, S. Plumari, and V. Greco, Study of collective anisotropies v_2 and v_3 and their fluctuations in pA collisions at LHC within a relativistic transport approach, *Eur. Phys. J. C* **80**, 16 (2020), [arXiv:1907.11287 \[nucl-th\]](#).
- [82] W. Zhao, C. M. Ko, Y.-X. Liu, G.-Y. Qin, and H. Song, Probing the Partonic Degrees of Freedom in High-Multiplicity $p - Pb$ collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **125**, 072301 (2020), [arXiv:1911.00826 \[nucl-th\]](#).
- [83] F. Retiere and M. A. Lisa, Observable implications of geometrical and dynamical aspects of freeze out in heavy ion collisions, *Phys. Rev. C* **70**, 044907 (2004), [arXiv:nucl-th/0312024](#).
- [84] M. L. Sambataro, Y. Sun, V. Minissale, S. Plumari, and V. Greco, Event-shape engineering analysis of D meson in ultrarelativistic heavy-ion collisions, *Eur. Phys. J. C* **82**, 833 (2022), [arXiv:2206.03160 \[hep-ph\]](#).
- [85] M. L. Sambataro, V. Minissale, S. Plumari, and V. Greco, B meson production in Pb+Pb at 5.02 ATeV at LHC: Estimating the diffusion coefficient in the infinite mass limit, *Phys. Lett. B* **849**, 138480 (2024), [arXiv:2304.02953 \[hep-ph\]](#).
- [86] C.-W. Hwang, Charge radii of light and heavy mesons, *Eur. Phys. J. C* **23**, 585 (2002), [arXiv:hep-ph/0112237](#).
- [87] C. Albertus, J. E. Amaro, E. Hernandez, and J. Nieves, Charmed and bottom baryons: A Variational approach based on heavy quark symmetry, *Nucl. Phys. A* **740**, 333 (2004), [arXiv:nucl-th/0311100](#).
- [88] S. Cao, K.-J. Sun, S.-Q. Li, S. Y. F. Liu, W.-J. Xing, G.-Y. Qin, and C. M. Ko, Charmed hadron chemistry in relativistic heavy-ion collisions, *Phys. Lett. B* **807**, 135561 (2020), [arXiv:1911.00456 \[nucl-th\]](#).
- [89] W. Cassing and E. L. Bratkovskaya, Parton transport and hadronization from the dynamical quasiparticle point of view, *Phys. Rev. C* **78**, 034919 (2008), [arXiv:0808.0022 \[hep-ph\]](#).
- [90] T. Song, H. Berrehrh, D. Cabrera, J. M. Torres-Rincon, L. Tolos, W. Cassing, and E. Bratkovskaya, Tomography of the Quark-Gluon-Plasma by Charm Quarks, *Phys. Rev. C* **92**, 014910 (2015), [arXiv:1503.03039 \[nucl-th\]](#).

- [91] T. Song, J. Aichelin, J. Zhao, P. B. Gossiaux, and E. Bratkovskaya, Bottomonium production in pp and heavy-ion collisions, *Phys. Rev. C* **108**, 054908 (2023), [arXiv:2305.10750 \[nucl-th\]](#).
- [92] H.-H. Li, F.-L. Shao, J. Song, and R.-Q. Wang, Production of single-charm hadrons by quark combination mechanism in p -Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. C* **97**, 064915 (2018), [arXiv:1712.08921 \[hep-ph\]](#).
- [93] R. Rapp and E. V. Shuryak, D meson production from recombination in hadronic collisions, *Phys. Rev. D* **67**, 074036 (2003), [arXiv:hep-ph/0301245](#).
- [94] J. Zhao *et al.*, Hadronization of Heavy Quarks, (2023), [arXiv:2311.10621 \[hep-ph\]](#).
- [95] W. Alberico, A. Beraudo, A. De Pace, A. Molinari, M. Monteno, *et al.*, Heavy flavors in AA collisions: production, transport and final spectra, *Eur.Phys.J. C* **73**, 2481 (2013), [arXiv:1305.7421 \[hep-ph\]](#).
- [96] A. Beraudo, A. De Pace, M. Monteno, M. Nardi, and F. Prino, In-medium hadronization of heavy quarks and its effect on charmed meson and baryon distributions in heavy-ion collisions, *Eur. Phys. J. C* **82**, 607 (2022), [arXiv:2202.08732 \[hep-ph\]](#).
- [97] A. Beraudo, A. De Pace, D. Pablos, F. Prino, M. Monteno, and M. Nardi, Heavy-flavor transport and hadronization in pp collisions, *Phys. Rev. D* **109**, L011501 (2024), [arXiv:2306.02152 \[hep-ph\]](#).
- [98] T. Pierog, I. Karpenko, J. M. Katzy, E. Yatsenko, and K. Werner, EPOS LHC: Test of collective hadronization with data measured at the CERN Large Hadron Collider, *Phys. Rev. C* **92**, 034906 (2015), [arXiv:1306.0121 \[hep-ph\]](#).
- [99] K. Werner, Core-corona procedure and microcanonical hadronization to understand strangeness enhancement in proton-proton and heavy ion collisions in the EPOS4 framework, *Phys. Rev. C* **109**, 014910 (2024), [arXiv:2306.10277 \[hep-ph\]](#).
- [100] K. Werner, Core-corona separation in ultra-relativistic heavy ion collisions, *Phys. Rev. Lett.* **98**, 152301 (2007), [arXiv:0704.1270 \[nucl-th\]](#).
- [101] J. Zhao, J. Aichelin, P. B. Gossiaux, and K. Werner, Heavy flavor as a probe of hot QCD matter produced in proton-proton collisions, *Phys. Rev. D* **109**, 054011 (2024), [arXiv:2310.08684 \[hep-ph\]](#).
- [102] J. Zhao, J. Aichelin, P. B. Gossiaux, V. Ozvenchuk, and K. Werner, Heavy flavour hadron production in relativistic heavy ion collisions at RHIC and LHC in EPOS4HQ, (2024), [arXiv:2401.17096 \[hep-ph\]](#).

- [103] M. Niiyama *et al.* (Belle), Production cross sections of hyperons and charmed baryons from e^+e^- annihilation near $\sqrt{s} = 10.52$ GeV, *Phys. Rev. D* **97**, 072005 (2018), [arXiv:1706.06791 \[hep-ex\]](#).
- [104] Y. L. Dokshitzer, V. A. Khoze, A. H. Mueller, and S. I. Troian, *Basics of perturbative QCD* (1991).
- [105] R. Barate *et al.* (ALEPH), Study of charm production in Z decays, *Eur. Phys. J. C* **16**, 597 (2000), [arXiv:hep-ex/9909032](#).
- [106] G. Alexander *et al.* (OPAL), A Study of charm hadron production in $Z^0 \rightarrow c$ anti- c and $Z^0 \rightarrow b$ anti- b decays at LEP, *Z. Phys. C* **72**, 1 (1996).
- [107] P. Abreu *et al.* (DELPHI), Measurements of the Z partial decay width into c anti- c and multiplicity of charm quarks per b decay, *Eur. Phys. J. C* **12**, 225 (2000).
- [108] L. Gladilin, Fragmentation fractions of c and b quarks into charmed hadrons at LEP, *Eur. Phys. J. C* **75**, 19 (2015), [arXiv:1404.3888 \[hep-ex\]](#).
- [109] T. Sjöstrand, High-energy physics event generation with PYTHIA 5.7 and JETSET 7.4, *Comput. Phys. Commun.* **82**, 74 (1994).
- [110] D. Bortoletto *et al.* (CLEO), Charm Production in Nonresonant e^+e^- Annihilations at $\sqrt{s} = 10.55$ GeV, *Phys. Rev. D* **37**, 1719 (1988), [Erratum: *Phys.Rev.D* 39, 1471 (1989)].
- [111] P. Avery *et al.* (CLEO), Inclusive production of the charmed baryon $\Lambda(c)$ from e^+e^- annihilations at $\sqrt{s} = 10.55$ -GeV, *Phys. Rev. D* **43**, 3599 (1991).
- [112] H. Albrecht *et al.* (ARGUS), Inclusive production of D^0 , D^+ and D^{*+} (2010) mesons in B decays and nonresonant e^+e^- annihilation at 10.6-GeV, *Z. Phys. C* **52**, 353 (1991).
- [113] H. Albrecht *et al.* (ARGUS), Production of $D(s)^+$ mesons in B decays and determination of $f(D(s))$, *Z. Phys. C* **54**, 1 (1992).
- [114] H. Albrecht *et al.* (ARGUS), Observation of the Charmed Baryon $\Lambda(c)$ in e^+e^- Annihilation at 10-GeV, *Phys. Lett. B* **207**, 109 (1988).
- [115] R. Seuster *et al.* (Belle), Charm hadrons from fragmentation and B decays in e^+e^- annihilation at $\sqrt{s} = 10.6$ -GeV, *Phys. Rev. D* **73**, 032002 (2006), [arXiv:hep-ex/0506068](#).
- [116] B. Aubert *et al.* (BaBar), Measurement of D_s^+ and D_s^{*+} production in B meson decays and from continuum e^+e^- annihilation at $\sqrt{s} = 10.6$ GeV, *Phys. Rev. D* **65**, 091104 (2002), [arXiv:hep-ex/0201041](#).

- [117] B. Aubert *et al.* (BaBar), Inclusive Lambda(c)+ Production in e+ e- Annihilations at $\sqrt{s} = 10.54\text{-GeV}$ and in Upsilon(4S) Decays, *Phys. Rev. D* **75**, 012003 (2007), [arXiv:hep-ex/0609004](#).
- [118] K. Ackerstaff *et al.* (OPAL), Measurement of $f(c \rightarrow D^* + X)$, $f(b \rightarrow D^* + X)$ and Gamma (c anti-c) / Gamma (hadronic) using D^{*+} mesons, *Eur. Phys. J. C* **1**, 439 (1998), [arXiv:hep-ex/9708021](#).
- [119] P. Abreu *et al.* (DELPHI), Determination of $P(c \rightarrow D^{*+})$ and $BR(c \rightarrow \text{lepton}^+)$ at LEP-1, *Eur. Phys. J. C* **12**, 209 (2000).
- [120] H. Abramowicz *et al.* (ZEUS), Measurement of charm fragmentation fractions in photoproduction at HERA, *JHEP* **09**, 058, [arXiv:1306.4862 \[hep-ex\]](#).
- [121] S. Chekanov *et al.* (ZEUS), Measurement of charm fragmentation ratios and fractions in photoproduction at HERA, *Eur. Phys. J. C* **44**, 351 (2005), [arXiv:hep-ex/0508019](#).
- [122] S. Chekanov *et al.* (ZEUS), Measurement of D mesons production in deep inelastic scattering at HERA, *JHEP* **07**, 074, [arXiv:0704.3562 \[hep-ex\]](#).
- [123] H. Abramowicz *et al.* (ZEUS), Measurement of D^+ and Λ_c^+ production in deep inelastic scattering at HERA, *JHEP* **11**, 009, [arXiv:1007.1945 \[hep-ex\]](#).
- [124] A. Aktas *et al.* (H1), Inclusive production of D^+ , D^0 , $D^+(s)$ and D^{*+} mesons in deep inelastic scattering at HERA, *Eur. Phys. J. C* **38**, 447 (2005), [arXiv:hep-ex/0408149](#).
- [125] G. Abbiendi *et al.* (OPAL), Measurement of the production rate of charm quark pairs from gluons in hadronic Z^0 decays, *Eur. Phys. J. C* **13**, 1 (2000), [arXiv:hep-ex/9908001](#).
- [126] M. Acciarri *et al.* (L3), Measurement of the probability of gluon splitting into charmed quarks in hadronic Z decays, *Phys. Lett. B* **476**, 243 (2000), [arXiv:hep-ex/9911016](#).
- [127] A. Heister *et al.* (ALEPH), A measurement of the gluon splitting rate into c anti-c pairs in hadronic Z decays, *Phys. Lett. B* **561**, 213 (2003), [arXiv:hep-ex/0302003](#).
- [128] S. Chekanov *et al.* (ZEUS), Measurement of charm fragmentation ratios and fractions in photoproduction at HERA, *Eur. Phys. J. C* **44**, 351 (2005), [arXiv:hep-ex/0508019](#).
- [129] H. Abramowicz *et al.* (ZEUS), Measurement of charm fragmentation fractions in photoproduction at HERA, *JHEP* **09**, 058, [arXiv:1306.4862 \[hep-ex\]](#).
- [130] Y. Kato and T. Iijima, Open charm hadron spectroscopy at B-factories, *Prog. Part. Nucl. Phys.* **105**, 61 (2019), [arXiv:1810.03748 \[hep-ex\]](#).

- [131] E. Klempt and J.-M. Richard, Baryon spectroscopy, *Rev. Mod. Phys.* **82**, 1095 (2010), [arXiv:0901.2055 \[hep-ph\]](#).
- [132] P. Koppenburg (LHCb collaboration), List of hadrons observed at the LHC (2021), see [2022 update online](#).
- [133] T. Yoshida, E. Hiyama, A. Hosaka, M. Oka, and K. Sadato, Spectrum of heavy baryons in the quark model, *Phys. Rev. D* **92**, 114029 (2015), [arXiv:1510.01067 \[hep-ph\]](#).
- [134] M. Y. Barabanov *et al.*, Diquark correlations in hadron physics: Origin, impact and evidence, *Prog. Part. Nucl. Phys.* **116**, 103835 (2021), [arXiv:2008.07630 \[hep-ph\]](#).
- [135] S. L. Olsen, T. Skwarnicki, and D. Zieminska, Nonstandard heavy mesons and baryons: Experimental evidence, *Rev. Mod. Phys.* **90**, 015003 (2018), [arXiv:1708.04012 \[hep-ph\]](#).
- [136] R. L. Jaffe, Exotica, *Phys. Rept.* **409**, 1 (2005), [arXiv:hep-ph/0409065](#).
- [137] E. Norrbin and T. Sjöstrand, Drag effects in charm photoproduction, in *Workshop on Monte Carlo Generators for HERA Physics (Plenary Starting Meeting)* (1999) pp. 506–511, [arXiv:hep-ph/9905493](#).
- [138] M. Adamovich *et al.* (WA82), Study of D⁺ and D⁻ Feynman's x distributions in pi⁻ nucleus interactions at the SPS, *Phys. Lett. B* **305**, 402 (1993).
- [139] G. A. Alves *et al.* (E769), Enhanced leading production of D⁺⁻ and D^{*+-} in 250-GeV pi⁺⁻ - nucleon interactions, *Phys. Rev. Lett.* **72**, 812 (1994), [Erratum: *Phys.Rev.Lett.* 72, 1946 (1994)].
- [140] M. I. Adamovich *et al.* (WA89), Charge asymmetries for D, D(s) and Lambda(c) production in Sigma⁻ nucleus interactions at 340-GeV/c, *Eur. Phys. J. C* **8**, 593 (1999), [arXiv:hep-ex/9803021](#).
- [141] E. M. Aitala *et al.* (E791), Asymmetries between the production of D⁺ and D⁻ mesons from 500-GeV/c pi⁻ - nucleon interactions as a function of x_F and p_t², *Phys. Lett. B* **371**, 157 (1996), [arXiv:hep-ex/9601001](#).
- [142] E. M. Aitala *et al.* (E791), Asymmetries between the production of D_s⁻ and D_s⁺ mesons from 500-GeV/c pi⁻ nucleon interactions as functions of x(F) and p - transverse², *Phys. Lett. B* **411**, 230 (1997), [arXiv:hep-ex/9708040](#).
- [143] F. G. Garcia *et al.* (SELEX), Hadronic Production of Lambda_c from 600-GeV/c pi⁻, Sigma⁻ and p Beams, *Phys. Lett. B* **528**, 49 (2002), [arXiv:hep-ex/0109017](#).

- [144] V. M. Abazov *et al.* (D0), Measurement of the Forward-Backward Asymmetry in Λ_b^0 and $\bar{\Lambda}_b^0$ Baryon Production in $p\bar{p}$ Collisions at $\sqrt{s}=1.96$ TeV, *Phys. Rev. D* **91**, 072008 (2015), [arXiv:1503.03917 \[hep-ex\]](#).
- [145] M. L. Mangano, Heavy quark production in hadronic collisions, *Nuovo Cim. A* **109**, 683 (1996), [arXiv:hep-ph/9508260](#).
- [146] S. Frixione, M. L. Mangano, P. Nason, and G. Ridolfi, Heavy quark production, *Adv. Ser. Direct. High Energy Phys.* **15**, 609 (1998), [arXiv:hep-ph/9702287](#).
- [147] R. Vogt and S. J. Brodsky, QCD and intrinsic heavy quark predictions for leading charm and beauty hadroproduction, *Nucl. Phys. B* **438**, 261 (1995), [arXiv:hep-ph/9405236](#).
- [148] E. Norrbin and T. Sjöstrand, Production mechanisms of charm hadrons in the string model, *Phys. Lett. B* **442**, 407 (1998), [arXiv:hep-ph/9809266](#).
- [149] E. Norrbin and T. Sjöstrand, Production and hadronization of heavy quarks, *Eur. Phys. J. C* **17**, 137 (2000), [arXiv:hep-ph/0005110](#).
- [150] E. Braaten, Y. Jia, and T. Mehen, The Leading particle effect from heavy quark recombination, *Phys. Rev. Lett.* **89**, 122002 (2002), [arXiv:hep-ph/0205149](#).
- [151] A. Andronic *et al.*, Heavy-flavour and quarkonium production in the LHC era: from proton-proton to heavy-ion collisions, *Eur. Phys. J. C* **76**, 107 (2016), [arXiv:1506.03981 \[nucl-ex\]](#).
- [152] M. Cacciari, P. Nason, and R. Vogt, QCD predictions for charm and bottom production at RHIC, *Phys. Rev. Lett.* **95**, 122001 (2005), [arXiv:hep-ph/0502203](#).
- [153] D. Acosta *et al.* (CDF), Measurement of prompt charm meson production cross sections in $p\bar{p}$ collisions at $\sqrt{s} = 1.96$ TeV, *Phys. Rev. Lett.* **91**, 241804 (2003), [arXiv:hep-ex/0307080](#).
- [154] D. Acosta *et al.* (CDF), Measurement of the J/ψ meson and b -hadron production cross sections in $p\bar{p}$ collisions at $\sqrt{s} = 1960$ GeV, *Phys. Rev. D* **71**, 032001 (2005), [arXiv:hep-ex/0412071](#).
- [155] A. Abulencia *et al.* (CDF), Measurement of the B^+ production cross-section in p anti- p collisions at $s^{*(1/2)} = 1960$ -GeV, *Phys. Rev. D* **75**, 012010 (2007), [arXiv:hep-ex/0612015](#).
- [156] R. Aaij *et al.* (LHCb), Measurements of prompt charm production cross-sections in pp collisions at $\sqrt{s} = 13$ TeV, *JHEP* **03**, 159, [Erratum: *JHEP* 09, 013 (2016), Erratum: *JHEP* 05, 074 (2017)], [arXiv:1510.01707 \[hep-ex\]](#).
- [157] S. Acharya *et al.* (ALICE), Measurement of beauty and charm production in pp collisions at $\sqrt{s} = 5.02$ TeV via non-prompt and prompt D mesons, *JHEP* **05**, 220, [arXiv:2102.13601](#)

- [nucl-ex].
- [158] S. Acharya *et al.* (ALICE), Charm production and fragmentation fractions at midrapidity in pp collisions at $\sqrt{s} = 13$ TeV, *JHEP* **12**, 086, arXiv:2308.04877 [hep-ex].
- [159] A. M. Sirunyan *et al.* (CMS), Measurement of the B^\pm Meson Nuclear Modification Factor in Pb-Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **119**, 152301 (2017), arXiv:1705.04727 [hep-ex].
- [160] V. Khachatryan *et al.* (CMS), Prompt and Non-Prompt J/ψ Production in pp Collisions at $\sqrt{s} = 7$ TeV, *Eur. Phys. J. C* **71**, 1575 (2011), arXiv:1011.4193 [hep-ex].
- [161] A. M. Sirunyan *et al.* (CMS), Nuclear modification factor of D^0 mesons in PbPb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **782**, 474 (2018), arXiv:1708.04962 [nucl-ex].
- [162] S. Acharya *et al.* (ALICE), Measurement of D^0 , D^+ , D^{*+} and D_s^+ production in pp collisions at $\sqrt{s} = 5.02$ TeV with ALICE, *Eur. Phys. J. C* **79**, 388 (2019), arXiv:1901.07979 [nucl-ex].
- [163] R. Aaij *et al.* (LHCb), Measurements of prompt charm production cross-sections in pp collisions at $\sqrt{s} = 5$ TeV, *JHEP* **06**, 147, arXiv:1610.02230 [hep-ex].
- [164] G. Aad *et al.* (ATLAS), Measurement of $D^{*\pm}$, D^\pm and D_s^\pm meson production cross sections in pp collisions at $\sqrt{s} = 7$ TeV with the ATLAS detector, *Nucl. Phys. B* **907**, 717 (2016), arXiv:1512.02913 [hep-ex].
- [165] A. M. Sirunyan *et al.* (CMS), Nuclear modification factor of D^0 mesons in PbPb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **782**, 474 (2018), arXiv:1708.04962 [nucl-ex].
- [166] B. Abelev *et al.* (ALICE), D_s^+ meson production at central rapidity in proton–proton collisions at $\sqrt{s} = 7$ TeV, *Phys. Lett. B* **718**, 279 (2012), arXiv:1208.1948 [hep-ex].
- [167] G. Aad *et al.* (ATLAS), Measurement of $D^{*\pm}$, D^\pm and D_s^\pm meson production cross sections in pp collisions at $\sqrt{s} = 7$ TeV with the ATLAS detector, *Nucl. Phys. B* **907**, 717 (2016), arXiv:1512.02913 [hep-ex].
- [168] R. Aaij *et al.* (LHCb), Measurement of b -hadron production fractions in 7 TeV pp collisions, *Phys. Rev. D* **85**, 032008 (2012), arXiv:1111.2357 [hep-ex].
- [169] R. Aaij *et al.* (LHCb), Measurement of b hadron fractions in 13 TeV pp collisions, *Phys. Rev. D* **100**, 031102 (2019), arXiv:1902.06794 [hep-ex].
- [170] G. Aad *et al.* (ATLAS), Determination of the ratio of b -quark fragmentation fractions f_s/f_d in pp collisions at $\sqrt{s} = 7$ TeV with the ATLAS detector, *Phys. Rev. Lett.* **115**, 262001 (2015), arXiv:1507.08925 [hep-ex].

- [171] Y. S. Amhis *et al.* (HFLAV), Averages of b-hadron, c-hadron, and τ -lepton properties as of 2018, *Eur. Phys. J. C* **81**, 226 (2021), [arXiv:1909.12524 \[hep-ex\]](#).
- [172] A. Tumasyan *et al.* (CMS), Measurement of the dependence of the hadron production fraction ratio f_s/f_u and f_d/f_u on B meson kinematic variables in proton-proton collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. Lett.* **131**, 121901 (2023), [arXiv:2212.02309 \[hep-ex\]](#).
- [173] S. Acharya *et al.* (ALICE), First measurement of Λ_c^+ production down to $p_T=0$ in pp and p-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. C* **107**, 064901 (2023), [arXiv:2211.14032 \[nucl-ex\]](#).
- [174] A. M. Sirunyan *et al.* (CMS), Production of Λ_c^+ baryons in proton-proton and lead-lead collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **803**, 135328 (2020), [arXiv:1906.03322 \[hep-ex\]](#).
- [175] A. Rossi, Hadronization mechanism (via heavy-flavor hadrons): Experiment, *PoS Hard-Probes2023*, 022 (2024), [arXiv:2308.10202 \[hep-ex\]](#).
- [176] S. Acharya *et al.* (ALICE), Measurement of Prompt D^0 , Λ_c^+ , and $\Sigma_c^{0,++}(2455)$ Production in Proton-Proton Collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. Lett.* **128**, 012001 (2022), [arXiv:2106.08278 \[hep-ex\]](#).
- [177] S. Acharya *et al.* (ALICE), First measurement of Ω_c^0 production in pp collisions at $s=13$ TeV, *Phys. Lett. B* **846**, 137625 (2023), [arXiv:2205.13993 \[nucl-ex\]](#).
- [178] H. Li, F. Shao, and J. Song, Production of light-flavor and single-charmed hadrons in pp collisions at \sqrt{s} five in an equal-velocity quark combination model, *Chin. Phys. C* **45**, 113105 (2021), [arXiv:2103.14900 \[hep-ph\]](#).
- [179] S. Acharya *et al.* (ALICE), Measurement of the production cross section of prompt Ξ_c^0 baryons at midrapidity in pp collisions at $\sqrt{s} = 5.02$ TeV, *JHEP* **10**, 159, [arXiv:2105.05616 \[nucl-ex\]](#).
- [180] S. Acharya *et al.* (ALICE), Measurement of the Cross Sections of Ξ_c^0 and Ξ_c^+ Baryons and of the Branching-Fraction Ratio $BR(\Xi_c^0 \rightarrow \Xi^- e^+ \nu_e)/BR(\Xi_c^0 \rightarrow \Xi^- \pi^+)$ in pp collisions at 13 TeV, *Phys. Rev. Lett.* **127**, 272001 (2021), [arXiv:2105.05187 \[nucl-ex\]](#).
- [181] H. Yun, S. Noh, S. Lim, T. Song, J. Hong, A. Park, S. H. Lee, and B. Dönigus, Diquarks and the production of charmed baryons, [arXiv:2308.06760 \[hep-ph\]](#).
- [182] Y.-K. Hsiao, L. Yang, C.-C. Lih, and S.-Y. Tsai, Charmed Ω_c weak decays into Ω in the light-front quark model, *Eur. Phys. J. C* **80**, 1066 (2020), [arXiv:2009.12752 \[hep-ph\]](#).
- [183] T. Gutsche, M. A. Ivanov, J. G. Körner, and V. E. Lyubovitskij, Nonleptonic two-body decays of single heavy baryons Λ_Q , Ξ_Q , and Ω_Q ($Q = b, c$) induced by W emission in the

- covariant confined quark model, *Phys. Rev. D* **98**, 074011 (2018), [arXiv:1806.11549 \[hep-ph\]](#).
- [184] H.-Y. Cheng, Nonleptonic weak decays of bottom baryons, *Phys. Rev. D* **56**, 2799 (1997), [Erratum: *Phys.Rev.D* 99, 079901 (2019)], [arXiv:hep-ph/9612223](#).
- [185] S. Hu, G. Meng, and F. Xu, Hadronic weak decays of the charmed baryon Ω_c , *Phys. Rev. D* **101**, 094033 (2020), [arXiv:2003.04705 \[hep-ph\]](#).
- [186] E. Solovieva *et al.*, Study of Ω_c^0 and Ω_c^{*0} Baryons at Belle, *Phys. Lett. B* **672**, 1 (2009), [arXiv:0808.3677 \[hep-ex\]](#).
- [187] K.-L. Wang, Q.-F. Lü, J.-J. Xie, and X.-H. Zhong, Toward discovering the excited Ω baryons through nonleptonic weak decays of Ω_c , *Phys. Rev. D* **107**, 034015 (2023), [arXiv:2203.04458 \[hep-ph\]](#).
- [188] S. Acharya *et al.* (ALICE), Measurement of D^0 , D^+ , D^{*+} and D_s^+ production in pp collisions at $\sqrt{s} = 5.02$ TeV with ALICE, *Eur. Phys. J. C* **79**, 388 (2019), [arXiv:1901.07979 \[nucl-ex\]](#).
- [189] S. Acharya *et al.* (ALICE), Inclusive J/ψ production at mid-rapidity in pp collisions at $\sqrt{s} = 5.02$ TeV, *JHEP* **10**, 084, [arXiv:1905.07211 \[nucl-ex\]](#).
- [190] S. Acharya *et al.* (ALICE), Charm-quark fragmentation fractions and production cross section at midrapidity in pp collisions at the LHC, *Phys. Rev. D* **105**, L011103 (2022), [arXiv:2105.06335 \[nucl-ex\]](#).
- [191] R. Aaij *et al.* (LHCb), Study of the production of Λ_b^0 and \bar{B}^0 hadrons in pp collisions and first measurement of the $\Lambda_b^0 \rightarrow J/\psi p K^-$ branching fraction, *Chin. Phys. C* **40**, 011001 (2016), [arXiv:1509.00292 \[hep-ex\]](#).
- [192] R. Aaij *et al.* (LHCb), Study of the kinematic dependences of Λ_b^0 production in pp collisions and a measurement of the $\Lambda_b^0 \rightarrow \Lambda_c^+ \pi^-$ branching fraction, *JHEP* **08**, 143, [arXiv:1405.6842 \[hep-ex\]](#).
- [193] R. Aaij *et al.* (LHCb), Measurement of f_s/f_u Variation with Proton-Proton Collision Energy and B -Meson Kinematics, *Phys. Rev. Lett.* **124**, 122002 (2020), [arXiv:1910.09934 \[hep-ex\]](#).
- [194] R. Aaij *et al.* (LHCb), Enhanced Production of Λ_b^0 Baryons in High-Multiplicity pp Collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. Lett.* **132**, 081901 (2024), [arXiv:2310.12278 \[hep-ex\]](#).
- [195] S. Chatrchyan *et al.* (CMS), Measurement of the Λ_b Cross Section and the $\bar{\Lambda}_b$ to Λ_b Ratio with $J/\Psi\Lambda$ Decays in pp Collisions at $\sqrt{s} = 7$ TeV, *Phys. Lett. B* **714**, 136 (2012), [arXiv:1205.0594 \[hep-ex\]](#).

- [196] S. Acharya *et al.* (ALICE), Study of flavor dependence of the baryon-to-meson ratio in proton-proton collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. D* **108**, 112003 (2023), [arXiv:2308.04873 \[hep-ex\]](#).
- [197] R. Aaij *et al.* (LHCb), Observation of a $\Lambda_b^0 - \bar{\Lambda}_b^0$ production asymmetry in proton-proton collisions at $\sqrt{s} = 7$ and 8 TeV, *JHEP* **10**, 060, [arXiv:2107.09593 \[hep-ex\]](#).
- [198] R. Aaij *et al.* (LHCb), Measurement of D_s^\pm production asymmetry in pp collisions at $\sqrt{s} = 7$ and 8 TeV, *JHEP* **08**, 008, [arXiv:1805.09869 \[hep-ex\]](#).
- [199] J. Adam *et al.* (ALICE), Enhanced production of multi-strange hadrons in high-multiplicity proton-proton collisions, *Nature Phys.* **13**, 535 (2017), [arXiv:1606.07424 \[nucl-ex\]](#).
- [200] S. Acharya *et al.* (ALICE), Observation of a multiplicity dependence in the p_T -differential charm baryon-to-meson ratios in proton-proton collisions at $\sqrt{s} = 13$ TeV, *Phys. Lett. B* **829**, 137065 (2022), [arXiv:2111.11948 \[nucl-ex\]](#).
- [201] R. Aaij *et al.* (LHCb), Evidence for modification of b quark hadronization in high-multiplicity pp collisions at $\sqrt{s} = 13$ TeV, *Phys. Rev. Lett.* **131**, 061901 (2023), [arXiv:2204.13042 \[hep-ex\]](#).
- [202] Y. Chen and M. He, Charged-particle multiplicity dependence of charm-baryon-to-meson ratio in high-energy proton-proton collisions, *Phys. Lett. B* **815**, 136144 (2021), [arXiv:2011.14328 \[hep-ph\]](#).
- [203] A. Beraudo, A. De Pace, M. Monteno, M. Nardi, and F. Prino, Heavy-flavour production in high-energy d-Au and p-Pb collisions, *JHEP* **03**, 123, [arXiv:1512.05186 \[hep-ph\]](#).
- [204] S. Alioli, P. Nason, C. Oleari, and E. Re, A general framework for implementing NLO calculations in shower Monte Carlo programs: the POWHEG BOX, *JHEP* **06**, 043, [arXiv:1002.2581 \[hep-ph\]](#).
- [205] S. Frixione, P. Nason, and G. Ridolfi, A Positive-weight next-to-leading-order Monte Carlo for heavy flavour hadroproduction, *JHEP* **09**, 126, [arXiv:0707.3088 \[hep-ph\]](#).
- [206] S. Dulat, T.-J. Hou, J. Gao, M. Guzzi, J. Huston, P. Nadolsky, J. Pumplin, C. Schmidt, D. Stump, and C. Yuan, New parton distribution functions from a global analysis of quantum chromodynamics, *Phys. Rev. D* **93**, 033006 (2016), [arXiv:1506.07443 \[hep-ph\]](#).
- [207] K. J. Eskola, P. Paakkinen, H. Paukkunen, and C. A. Salgado, EPPS16: Nuclear parton distributions with LHC data, *Eur. Phys. J. C* **77**, 163 (2017), [arXiv:1612.05741 \[hep-ph\]](#).
- [208] J. L. Nagle and W. A. Zajc, Small System Collectivity in Relativistic Hadronic and Nuclear Collisions, *Ann. Rev. Nucl. Part. Sci.* **68**, 211 (2018), [arXiv:1801.03477 \[nucl-ex\]](#).

- [209] S. Acharya *et al.* (ALICE), Charged-particle production as a function of multiplicity and transverse sphericity in pp collisions at $\sqrt{s} = 5.02$ and 13 TeV, *Eur. Phys. J. C* **79**, 857 (2019), [arXiv:1905.07208 \[nucl-ex\]](#).
- [210] J. Adam *et al.* (ALICE), Centrality dependence of particle production in p-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. C* **91**, 064905 (2015), [arXiv:1412.6828 \[nucl-ex\]](#).
- [211] S. Acharya *et al.* (ALICE), Charged-particle pseudorapidity density at mid-rapidity in p-Pb collisions at $\sqrt{s_{NN}} = 8.16$ TeV, *Eur. Phys. J. C* **79**, 307 (2019), [arXiv:1812.01312 \[nucl-ex\]](#).
- [212] J. Adam *et al.* (ALICE), Centrality Dependence of the Charged-Particle Multiplicity Density at Midrapidity in Pb-Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **116**, 222302 (2016), [arXiv:1512.06104 \[nucl-ex\]](#).
- [213] S. Acharya *et al.* (ALICE), Pseudorapidity densities of charged particles with transverse momentum thresholds in pp collisions at $\sqrt{s} = 5.02$ and 13 TeV, *Phys. Rev. D* **108**, 072008 (2023), [arXiv:2211.15364 \[nucl-ex\]](#).
- [214] *Multiplicity dependence of charm baryon and meson production in pPb collisions at 8.16 TeV*, Tech. Rep. (CERN, Geneva, 2023).
- [215] S. Acharya *et al.* (ALICE), Multiplicity dependence of (multi-)strange hadron production in proton-proton collisions at $\sqrt{s} = 13$ TeV, *Eur. Phys. J. C* **80**, 167 (2020), [arXiv:1908.01861 \[nucl-ex\]](#).
- [216] S. Acharya *et al.* (ALICE), Measurement of prompt D^0 , D^+ , D^{*+} , and D_S^+ production in p-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **12**, 092, [arXiv:1906.03425 \[nucl-ex\]](#).
- [217] S. Acharya *et al.* (ALICE), Charm fragmentation fractions and $c\bar{c}$ cross section in p-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV (2024), [arXiv:2405.14571 \[nucl-ex\]](#).
- [218] R. Aaij *et al.* (LHCb), Prompt Λ_c^+ production in pPb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **02**, 102, [arXiv:1809.01404 \[hep-ex\]](#).
- [219] R. Aaij *et al.* (LHCb), Measurement of Ξ_c^+ production in p-Pb collisions at $\sqrt{s_{NN}} = 8.16$ TeV at LHCb, *Phys. Rev. C* **109**, 044901 (2024), [arXiv:2305.06711 \[hep-ex\]](#).
- [220] S. Acharya *et al.* (ALICE), Measurement of the production cross section of prompt Ξ_c^0 baryons in p-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV (2024), [arXiv:2405.14538 \[nucl-ex\]](#).
- [221] A. Beraudo *et al.*, Extraction of Heavy-Flavor Transport Coefficients in QCD Matter, *Nucl. Phys. A* **979**, 21 (2018), [arXiv:1803.03824 \[nucl-th\]](#).

- [222] R. Aaij *et al.* (LHCb), Measurement of the b -quark production cross-section in 7 and 13 TeV pp collisions, *Phys. Rev. Lett.* **118**, 052002 (2017), [Erratum: *Phys.Rev.Lett.* 119, 169901 (2017)], [arXiv:1612.05140 \[hep-ex\]](#).
- [223] S. Acharya *et al.* (ALICE), Production of muons from heavy-flavour hadron decays in pp collisions at $\sqrt{s} = 5.02$ TeV, *JHEP* **09**, 008, [arXiv:1905.07207 \[nucl-ex\]](#).
- [224] S. Acharya *et al.* (ALICE), Measurement of beauty production via non-prompt D^0 mesons in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **12**, 126, [arXiv:2202.00815 \[nucl-ex\]](#).
- [225] S. Acharya *et al.* (ALICE), Measurements of low- p_T electrons from semileptonic heavy-flavour hadron decays at mid-rapidity in pp and Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **10**, 061, [arXiv:1805.04379 \[nucl-ex\]](#).
- [226] S. Acharya *et al.* (ALICE), Measurement of D^0 , D^+ , D^{*+} and D_s^+ production in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **10**, 174, [arXiv:1804.09083 \[nucl-ex\]](#).
- [227] B. Abelev *et al.* (ALICE), Suppression of high transverse momentum D mesons in central Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **1209**, 112, [arXiv:1203.2160 \[nucl-ex\]](#).
- [228] B. Abelev *et al.* (ALICE), Production of muons from heavy flavour decays at forward rapidity in pp and Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *Phys.Rev.Lett.* **109**, 112301 (2012), [arXiv:1205.6443 \[hep-ex\]](#).
- [229] J. Adam *et al.* (ALICE), Measurement of D_s^+ production and nuclear modification factor in Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **03**, 082, [arXiv:1509.07287 \[nucl-ex\]](#).
- [230] J. Adam *et al.* (ALICE), Transverse momentum dependence of D-meson production in Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **03**, 081, [arXiv:1509.06888 \[nucl-ex\]](#).
- [231] J. Adam *et al.* (ALICE), Measurement of electrons from beauty-hadron decays in p -Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV and Pb-Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **07**, 052, [arXiv:1609.03898 \[nucl-ex\]](#).
- [232] S. Acharya *et al.* (ALICE), Prompt D^0 , D^+ , and D^{*+} production in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **01**, 174, [arXiv:2110.09420 \[nucl-ex\]](#).
- [233] S. Acharya *et al.* (ALICE), D -meson azimuthal anisotropy in midcentral Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **120**, 102301 (2018), [arXiv:1707.01005 \[nucl-ex\]](#).
- [234] S. Acharya *et al.* (ALICE), Event-shape engineering for the D-meson elliptic flow in mid-central Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **02**, 150, [arXiv:1809.09371 \[nucl-ex\]](#).

- [235] S. Acharya *et al.* (ALICE), Measurement of prompt D_s^+ -meson production and azimuthal anisotropy in Pb–Pb collisions at $\sqrt{s_{NN}}=5.02\text{TeV}$, *Phys. Lett. B* **827**, 136986 (2022), [arXiv:2110.10006 \[nucl-ex\]](#).
- [236] S. Acharya *et al.* (ALICE), J/ψ elliptic and triangular flow in Pb-Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *JHEP* **10**, 141, [arXiv:2005.14518 \[nucl-ex\]](#).
- [237] S. Acharya *et al.* (ALICE), Transverse-momentum and event-shape dependence of D-meson flow harmonics in Pb–Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **813**, 136054 (2021), [arXiv:2005.11131 \[nucl-ex\]](#).
- [238] S. Acharya *et al.* (ALICE), Elliptic Flow of Electrons from Beauty-Hadron Decays in Pb-Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **126**, 162001 (2021), [arXiv:2005.11130 \[nucl-ex\]](#).
- [239] L. Adamczyk *et al.* (STAR), Observation of D^0 Meson Nuclear Modifications in Au+Au Collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys.Rev.Lett.* **113**, 142301 (2014), [arXiv:1404.6185 \[nucl-ex\]](#).
- [240] B. I. Abelev *et al.* (STAR), Transverse momentum and centrality dependence of high- p_T non-photon electron suppression in Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys. Rev. Lett.* **98**, 192301 (2007), [Erratum: *Phys. Rev. Lett.*106,159902(2011)], [arXiv:nucl-ex/0607012 \[nucl-ex\]](#).
- [241] A. Adare *et al.* (PHENIX), Nuclear-Modification Factor for Open-Heavy-Flavor Production at Forward Rapidity in Cu+Cu Collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys.Rev.* **C86**, 024909 (2012), [arXiv:1204.0754 \[nucl-ex\]](#).
- [242] A. Adare *et al.* (PHENIX), Heavy Quark Production in $p + p$ and Energy Loss and Flow of Heavy Quarks in Au+Au Collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys. Rev. C* **84**, 044905 (2011), [arXiv:1005.1627 \[nucl-ex\]](#).
- [243] S. Adler *et al.* (PHENIX), Nuclear modification of electron spectra and implications for heavy quark energy loss in Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV, *Phys.Rev.Lett.* **96**, 032301 (2006), [arXiv:nucl-ex/0510047 \[nucl-ex\]](#).
- [244] V. Khachatryan *et al.* (CMS), Study of B Meson Production in p+Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV Using Exclusive Hadronic Decays, *Phys. Rev. Lett.* **116**, 032301 (2016), [arXiv:1508.06678 \[nucl-ex\]](#).

- [245] S. Chatrchyan *et al.* (CMS), Suppression of non-prompt J/ψ , prompt J/ψ , and $Y(1S)$ in PbPb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *JHEP* **05**, 063, arXiv:1201.5069 [nucl-ex].
- [246] V. Khachatryan *et al.* (CMS), Suppression and azimuthal anisotropy of prompt and non-prompt J/ψ production in PbPb collisions at $\sqrt{s_{NN}} = 2.76$ TeV, *Eur. Phys. J. C* **77**, 252 (2017), arXiv:1610.00613 [nucl-ex].
- [247] A. M. Sirunyan *et al.* (CMS), Studies of Beauty Suppression via Nonprompt D^0 Mesons in Pb-Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **123**, 022001 (2019), arXiv:1810.11102 [hep-ex].
- [248] A. Tumasyan *et al.* (CMS, (CMS Collaboration)*), Probing Charm Quark Dynamics via Multiparticle Correlations in Pb-Pb Collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Rev. Lett.* **129**, 022001 (2022), arXiv:2112.12236 [hep-ex].
- [249] A. M. Sirunyan *et al.* (CMS), Measurement of prompt D^0 and \bar{D}^0 meson azimuthal anisotropy and search for strong electric fields in PbPb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Phys. Lett. B* **816**, 136253 (2021), arXiv:2009.12628 [hep-ex].
- [250] M. Aaboud *et al.* (ATLAS), Measurement of the suppression and azimuthal anisotropy of muons from heavy-flavor decays in Pb+Pb collisions at $\sqrt{s_{NN}} = 2.76$ TeV with the ATLAS detector, *Phys. Rev. C* **98**, 044905 (2018), arXiv:1805.05220 [nucl-ex].
- [251] M. Aaboud *et al.* (ATLAS), Prompt and non-prompt J/ψ and $\psi(2S)$ suppression at high transverse momentum in 5.02 TeV Pb+Pb collisions with the ATLAS experiment, *Eur. Phys. J. C* **78**, 762 (2018), arXiv:1805.04077 [nucl-ex].
- [252] G. Aad *et al.* (ATLAS), Measurement of the nuclear modification factor for muons from charm and bottom hadrons in Pb+Pb collisions at 5.02 TeV with the ATLAS detector, *Phys. Lett. B* **829**, 137077 (2022), arXiv:2109.00411 [nucl-ex].
- [253] S. Plumari, G. Coci, V. Minissale, S. K. Das, Y. Sun, and V. Greco, Heavy - light flavor correlations of anisotropic flows at LHC energies within event-by-event transport approach, *Phys. Lett. B* **805**, 135460 (2020), arXiv:1912.09350 [hep-ph].
- [254] H. van Hees, V. Greco, and R. Rapp, Heavy-quark probes of the quark-gluon plasma at RHIC, *Phys. Rev. C* **73**, 034913 (2006), arXiv:nucl-th/0508055 [nucl-th].
- [255] X. Dong and V. Greco, Heavy quark production and properties of Quark-Gluon Plasma, *Prog. Part. Nucl. Phys.* **104**, 97 (2019).

- [256] L. Altenkort, O. Kaczmarek, R. Larsen, S. Mukherjee, P. Petreczky, H.-T. Shu, and S. Sten-debach (HotQCD), Heavy Quark Diffusion from 2+1 Flavor Lattice QCD with 320 MeV Pion Mass, *Phys. Rev. Lett.* **130**, 231902 (2023), [arXiv:2302.08501 \[hep-lat\]](#).
- [257] G. D. Moore and D. Teaney, How much do heavy quarks thermalize in a heavy ion collision?, *Phys. Rev. C* **71**, 064904 (2005), [arXiv:hep-ph/0412346](#).
- [258] P. Petreczky and D. Teaney, Heavy quark diffusion from the lattice, *Phys. Rev. D* **73**, 014508 (2006), [arXiv:hep-ph/0507318](#).
- [259] Y. Xu, J. E. Bernhard, S. A. Bass, M. Nahrgang, and S. Cao, Data-driven analysis for the temperature and momentum dependence of the heavy-quark diffusion coefficient in relativistic heavy-ion collisions, *Phys. Rev. C* **97**, 014907 (2018), [arXiv:1710.00807 \[nucl-th\]](#).
- [260] L. Adamczyk *et al.* (STAR), Measurement of D^0 Azimuthal Anisotropy at Midrapidity in Au+Au Collisions at $\sqrt{s_{NN}}=200$ GeV, *Phys. Rev. Lett.* **118**, 212301 (2017), [arXiv:1701.06060 \[nucl-ex\]](#).
- [261] M. L. Sambaturo, V. Greco, G. Parisi, and S. Plumari, Quasi particle model vs lattice QCD thermodynamics: extension to $N_f = 2 + 1 + 1$ flavors and momentum dependent quark masses, (2024), [arXiv:2404.17459 \[hep-ph\]](#).
- [262] Y. Sun, G. Coci, S. K. Das, S. Plumari, M. Ruggieri, and V. Greco, Impact of Glasma on heavy quark observables in nucleus-nucleus collisions at LHC, *Phys. Lett. B* **798**, 134933 (2019), [arXiv:1902.06254 \[nucl-th\]](#).
- [263] Pooja, S. K. Das, V. Greco, and M. Ruggieri, Thermalization and isotropization of heavy quarks in a non-Markovian medium in high-energy nuclear collisions, *Phys. Rev. D* **108**, 054026 (2023), [arXiv:2306.13749 \[hep-ph\]](#).
- [264] S. Acharya *et al.* (ALICE), Measurement of non-prompt D^0 -meson elliptic flow in Pb–Pb collisions at $\sqrt{s_{NN}} = 5.02$ TeV, *Eur. Phys. J. C* **83**, 1123 (2023), [arXiv:2307.14084 \[nucl-ex\]](#).
- [265] A. Beraudo, A. De Pace, M. Monteno, M. Nardi, and F. Prino, Heavy flavors in heavy-ion collisions: quenching, flow and correlations, *Eur. Phys. J.* **C75**, 121 (2015), [arXiv:1410.6082 \[hep-ph\]](#).
- [266] A. Beraudo, A. De Pace, M. Monteno, M. Nardi, and F. Prino, Development of heavy-flavour flow-harmonics in high-energy nuclear collisions, *JHEP* **02**, 043, [arXiv:1712.00588 \[hep-ph\]](#).
- [267] V. Greco, Heavy Flavor Production, Flow and Energy Loss, *Nucl. Phys. A* **967**, 200 (2017).

- [268] S. Acharya *et al.* (ALICE), Measurement of beauty-strange meson production in Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV via non-prompt D_s^+ mesons, *Phys. Lett. B* **846**, 137561 (2023), [arXiv:2204.10386 \[nucl-ex\]](#).
- [269] A. Tumasyan *et al.* (CMS), Observation of B_s^0 mesons and measurement of the B_s^0/B^+ yield ratio in Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *Phys. Lett. B* **829**, 137062 (2022), [arXiv:2109.01908 \[hep-ex\]](#).
- [270] J. Adam *et al.* (STAR), Observation of D_s^\pm/D^0 enhancement in Au+Au collisions at $\sqrt{s_{\text{NN}}} = 200$ GeV, *Phys. Rev. Lett.* **127**, 092301 (2021), [arXiv:2101.11793 \[hep-ex\]](#).
- [271] R. Aaij *et al.* (LHCb), Precise measurement of the f_s/f_d ratio of fragmentation fractions and of B_s^0 decay branching fractions, *Phys. Rev. D* **104**, 032005 (2021), [arXiv:2103.06810 \[hep-ex\]](#).
- [272] M. He, R. J. Fries, and R. Rapp, Heavy Flavor at the Large Hadron Collider in a Strong Coupling Approach, *Phys.Lett.* **B735**, 445 (2014), [arXiv:1401.3817 \[nucl-th\]](#).
- [273] A. M. Sirunyan *et al.* (CMS), Measurement of B_s^0 meson production in pp and PbPb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *Phys. Lett. B* **796**, 168 (2019), [arXiv:1810.03022 \[hep-ex\]](#).
- [274] R. Aaij *et al.* (LHCb), Measurement of the Λ_c^+ to D^0 production ratio in peripheral Pb–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *JHEP* **06**, 132, [arXiv:2210.06939 \[hep-ex\]](#).
- [275] Upgrade of the ALICE Inner Tracking System during LS3: study of physics performance (2023).
- [276] S. Acharya *et al.* (ALICE), Λ_c^+ production in pp collisions at $\sqrt{s} = 7$ TeV and in p–Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *JHEP* **04**, 108, [arXiv:1712.09581 \[nucl-ex\]](#).
- [277] R. Aaij *et al.* (LHCb), Measurement of B^+ , B^0 and Λ_b^0 production in p Pb collisions at $\sqrt{s_{\text{NN}}} = 8.16$ TeV, *Phys. Rev. D* **99**, 052011 (2019), [arXiv:1902.05599 \[hep-ex\]](#).
- [278] S. Acharya *et al.* (ALICE), Probing the effects of strong electromagnetic fields with charge-dependent directed flow in Pb–Pb collisions at the LHC, *Phys. Rev. Lett.* **125**, 022301 (2020), [arXiv:1910.14406 \[nucl-ex\]](#).
- [279] J. Adam *et al.* (STAR), First Observation of the Directed Flow of D^0 and $\overline{D^0}$ in Au+Au Collisions at $\sqrt{s_{\text{NN}}} = 200$ GeV, *Phys. Rev. Lett.* **123**, 162301 (2019), [arXiv:1905.02052 \[nucl-ex\]](#).
- [280] L. Oliva, S. Plumari, and V. Greco, Directed flow of D mesons at RHIC and LHC: non-perturbative dynamics, longitudinal bulk matter asymmetry and electromagnetic fields,

- [JHEP 05, 034](#), [arXiv:2009.11066 \[hep-ph\]](#).
- [281] C. Gu (LHCb), Modification of heavy quark hadronization in high-multiplicity collisions at LHCb, [PoS HardProbes2023, 103 \(2024\)](#).
- [282] R. Aaij *et al.* (LHCb), Centrality determination in heavy-ion collisions with the LHCb detector, [JINST 17 \(05\), P05009](#), [arXiv:2111.01607 \[nucl-ex\]](#).
- [283] J. Altmann *et al.*, QCD challenges from pp to AA collisions: 4th edition, [Eur. Phys. J. C 84, 421 \(2024\)](#), [arXiv:2401.09930 \[hep-ex\]](#).
- [284] R. Abdul Khalek *et al.*, Science Requirements and Detector Concepts for the Electron-Ion Collider: EIC Yellow Report, [Nucl. Phys. A 1026, 122447 \(2022\)](#), [arXiv:2103.05419 \[physics.ins-det\]](#).
- [285] C. Bierlich, G. Gustafson, and L. Lönnblad, A shoving model for collectivity in hadronic collisions, (2016), [arXiv:1612.05132 \[hep-ph\]](#).
- [286] C. Bierlich, S. Chakraborty, G. Gustafson, and L. Lönnblad, Setting the string shoving picture in a new frame, [JHEP 03, 270](#), [arXiv:2010.07595 \[hep-ph\]](#).
- [287] S. Ferreres-Solé and T. Sjöstrand, The space–time structure of hadronization in the Lund model, [Eur. Phys. J. C 78, 983 \(2018\)](#), [arXiv:1808.04619 \[hep-ph\]](#).
- [288] C. Bierlich, G. Gustafson, L. Lönnblad, and H. Shah, The Angantyr model for Heavy-Ion Collisions in PYTHIA8, [JHEP 10, 134](#), [arXiv:1806.10820 \[hep-ph\]](#).
- [289] B. Andersson, G. Gustafson, and B. Nilsson-Almqvist, A Model for Low p(t) Hadronic Reactions, with Generalizations to Hadron - Nucleus and Nucleus-Nucleus Collisions, [Nucl. Phys. B 281, 289 \(1987\)](#).
- [290] H. Pi, An Event generator for interactions between hadrons and nuclei: FRITIOF version 7.0, [Comput. Phys. Commun. 71, 173 \(1992\)](#).
- [291] L. Lönnblad and H. Shah, A spatially constrained QCD colour reconnection in pp, pA, and AA collisions in the Pythia8/Angantyr model, [Eur. Phys. J. C 83, 575 \(2023\)](#), [Erratum: [Eur.Phys.J.C 83, 639 \(2023\)](#)], [arXiv:2303.11747 \[hep-ph\]](#).
- [292] C. Bierlich, G. Gustafson, L. Lönnblad, and H. Shah, The dynamic hadronization of charm quarks in heavy-ion collisions, [Eur. Phys. J. C 84, 231 \(2024\)](#), [arXiv:2309.12452 \[hep-ph\]](#).
- [293] C. Bierlich, String Interactions as a Source of Collective Behaviour, [Universe 10, 46 \(2024\)](#), [arXiv:2401.07585 \[hep-ph\]](#).

- [294] C. Albajar *et al.* (UA1), A Study of the D^* content of jets at the CERN $p\bar{p}$ collider, *Phys. Lett. B* **244**, 566 (1990).
- [295] B. I. Abelev *et al.* (STAR), Measurement of D^* Mesons in Jets from p+p Collisions at $\sqrt{s} = 200$ -GeV, *Phys. Rev. D* **79**, 112006 (2009), [arXiv:0901.0740 \[hep-ex\]](#).
- [296] F. Abe *et al.* (CDF), A measurement of D^* production in jets from $\bar{p}p$ collisions at $\sqrt{s} = 1.8$ TeV, *Phys. Rev. Lett.* **64**, 348 (1990).
- [297] S. Acharya *et al.* (ALICE), Measurement of the production of charm jets tagged with D^0 mesons in pp collisions at $\sqrt{s} = 5.02$ and 13 TeV, *JHEP* **06**, 133, [arXiv:2204.10167 \[nucl-ex\]](#).
- [298] S. Acharya *et al.* (ALICE), Measurements of Groomed-Jet Substructure of Charm Jets Tagged by D^0 Mesons in Proton-Proton Collisions at $s=13$ TeV, *Phys. Rev. Lett.* **131**, 192301 (2023), [arXiv:2208.04857 \[nucl-ex\]](#).
- [299] S. Acharya *et al.* (ALICE), Measurement of the fraction of jet longitudinal momentum carried by Λ_c^+ baryons in pp collisions, *Phys. Rev. D* **109**, 072005 (2024), [arXiv:2301.13798 \[nucl-ex\]](#).
- [300] S. Acharya *et al.* (ALICE), Direct observation of the dead-cone effect in quantum chromodynamics, *Nature* **605**, 440 (2022), [Erratum: *Nature* 607, E22 (2022)], [arXiv:2106.05713 \[nucl-ex\]](#).
- [301] G. Corcella, I. G. Knowles, G. Marchesini, S. Moretti, K. Odagiri, P. Richardson, M. H. Seymour, and B. R. Webber, HERWIG 6: An Event generator for hadron emission reactions with interfering gluons (including supersymmetric processes), *JHEP* **01**, 010, [arXiv:hep-ph/0011363](#).
- [302] G. Corcella, I. G. Knowles, G. Marchesini, S. Moretti, K. Odagiri, P. Richardson, M. H. Seymour, and B. R. Webber, HERWIG 6.5 release note, (2002), [arXiv:hep-ph/0210213](#).
- [303] S. Frixione, P. Nason, and C. Oleari, Matching NLO QCD computations with Parton Shower simulations: the POWHEG method, *JHEP* **11**, 070, [arXiv:0709.2092 \[hep-ph\]](#).
- [304] P. Nason, A New method for combining NLO QCD with shower Monte Carlo algorithms, *JHEP* **11**, 040, [arXiv:hep-ph/0409146](#).
- [305] A. Palasciano (ALICE), First measurements of in-jet fragmentation and correlations of charmed mesons and baryons in pp collisions with ALICE, *PoS HardProbes2023*, 144 (2024), [arXiv:2310.15133 \[hep-ex\]](#).

- [306] M. Faggin (ALICE), Studies on the hadronization of charm and beauty quarks, in *57th Rencontres de Moriond on QCD and High Energy Interactions* (2023) [arXiv:2305.10086 \[hep-ex\]](#).
- [307] U. Egede, T. Hadavizadeh, M. Singla, P. Skands, and M. Vesterinen, The role of multiparton interactions in doubly-heavy hadron production, *Eur. Phys. J. C* **82**, 773 (2022), [arXiv:2205.15681 \[hep-ph\]](#).
- [308] A. Tumasyan *et al.* (CMS), Observation of the B_c^+ Meson in Pb-Pb and pp Collisions at $\sqrt{s_{NN}}=5.02$ TeV and Measurement of its Nuclear Modification Factor, *Phys. Rev. Lett.* **128**, 252301 (2022), [arXiv:2201.02659 \[hep-ex\]](#).
- [309] B. Wu, Z. Tang, M. He, and R. Rapp, Recombination of Bc mesons in ultrarelativistic heavy-ion collisions, *Phys. Rev. C* **109**, 014906 (2024), [arXiv:2302.11511 \[nucl-th\]](#).
- [310] S. Cho and S. H. Lee, Production of multicharmed hadrons by recombination in heavy ion collisions, *Phys. Rev. C* **101**, 024902 (2020), [arXiv:1907.12786 \[nucl-th\]](#).
- [311] H. He, Y. Liu, and P. Zhuang, Ω_{ccc} production in high energy nuclear collisions, *Phys. Lett. B* **746**, 59 (2015), [arXiv:1409.1009 \[hep-ph\]](#).
- [312] F. Becattini, Production of multiply heavy flavored baryons from quark gluon plasma in relativistic heavy ion collisions, *Phys. Rev. Lett.* **95**, 022301 (2005), [arXiv:hep-ph/0503239](#).
- [313] J. Zhao, H. He, and P. Zhuang, Searching for Ξ_{cc}^+ in Relativistic Heavy Ion Collisions, *Phys. Lett. B* **771**, 349 (2017), [arXiv:1603.04524 \[nucl-th\]](#).
- [314] X. Yao and B. Müller, Doubly charmed baryon production in heavy ion collisions, *Phys. Rev. D* **97**, 074003 (2018), [arXiv:1801.02652 \[hep-ph\]](#).
- [315] S. K. Choi *et al.* (Belle), Observation of a narrow charmonium-like state in exclusive $B^\pm \rightarrow K^\pm \pi^+ \pi^- J/\psi$ decays, *Phys. Rev. Lett.* **91**, 262001 (2003), [arXiv:hep-ex/0309032](#).
- [316] M. Ablikim *et al.* (BESIII), Observation of $e^+e^- \rightarrow \gamma X(3872)$ at BESIII, *Phys. Rev. Lett.* **112**, 092001 (2014), [arXiv:1310.4101 \[hep-ex\]](#).
- [317] D. Acosta *et al.* (CDF), Observation of the narrow state $X(3872) \rightarrow J/\psi \pi^+ \pi^-$ in $\bar{p}p$ collisions at $\sqrt{s} = 1.96$ TeV, *Phys. Rev. Lett.* **93**, 072001 (2004), [arXiv:hep-ex/0312021](#).
- [318] V. M. Abazov *et al.* (D0), Observation and properties of the $X(3872)$ decaying to $J/\psi \pi^+ \pi^-$ in $p\bar{p}$ collisions at $\sqrt{s} = 1.96$ TeV, *Phys. Rev. Lett.* **93**, 162002 (2004), [arXiv:hep-ex/0405004](#).
- [319] R. Aaij *et al.* (LHCb), Observation of $X(3872)$ production in pp collisions at $\sqrt{s} = 7$ TeV, *Eur. Phys. J. C* **72**, 1972 (2012), [arXiv:1112.5310 \[hep-ex\]](#).

- [320] S. Chatrchyan *et al.* (CMS), Measurement of the $X(3872)$ Production Cross Section Via Decays to $J/\psi\pi^+\pi^-$ in pp collisions at $\sqrt{s} = 7$ TeV, *JHEP* **04**, 154, [arXiv:1302.3968 \[hep-ex\]](#).
- [321] M. Aaboud *et al.* (ATLAS), Measurements of $\psi(2S)$ and $X(3872) \rightarrow J/\psi\pi^+\pi^-$ production in pp collisions at $\sqrt{s} = 8$ TeV with the ATLAS detector, *JHEP* **01**, 117, [arXiv:1610.09303 \[hep-ex\]](#).
- [322] H.-X. Chen, W. Chen, X. Liu, Y.-R. Liu, and S.-L. Zhu, An updated review of the new hadron states, *Rept. Prog. Phys.* **86**, 026201 (2023), [arXiv:2204.02649 \[hep-ph\]](#).
- [323] R. Aaij *et al.* (LHCb), Observation of Multiplicity Dependent Prompt $\chi_{c1}(3872)$ and $\psi(2S)$ Production in pp Collisions, *Phys. Rev. Lett.* **126**, 092001 (2021), [arXiv:2009.06619 \[hep-ex\]](#).
- [324] A. Esposito, E. G. Ferreira, A. Pilloni, A. D. Polosa, and C. A. Salgado, The nature of $X(3872)$ from high-multiplicity pp collisions, *Eur. Phys. J. C* **81**, 669 (2021), [arXiv:2006.15044 \[hep-ph\]](#).
- [325] E. Braaten, L.-P. He, K. Ingles, and J. Jiang, Production of $X(3872)$ at High Multiplicity, *Phys. Rev. D* **103**, L071901 (2021), [arXiv:2012.13499 \[hep-ph\]](#).
- [326] B. Wu, X. Du, M. Sibila, and R. Rapp, $X(3872)$ transport in heavy-ion collisions, *Eur. Phys. J. A* **57**, 122 (2021), [Erratum: *Eur.Phys.J.A* 57, 314 (2021)], [arXiv:2006.09945 \[nucl-th\]](#).
- [327] S. H. Lee, S. Noh, D. Park, and H.-O. Yoon, Exotic Particles and heavy ion collisions, *EPJ Web Conf.* **276**, 06015 (2023).
- [328] A. Esposito, L. Maiani, A. Pilloni, A. D. Polosa, and V. Riquer, From the line shape of the $X(3872)$ to its structure, *Phys. Rev. D* **105**, L031503 (2022), [arXiv:2108.11413 \[hep-ph\]](#).
- [329] B. Grinstein, L. Maiani, and A. D. Polosa, Radiative decays of $X(3872)$ discriminate between the molecular and compact interpretations, *Phys. Rev. D* **109**, 074009 (2024), [arXiv:2401.11623 \[hep-ph\]](#).
- [330] R. Aaij *et al.* (LHCb), Modification of $\chi_{c1}(3872)$ and $\psi(2S)$ production in pPb collisions at $\sqrt{s_{NN}} = 8.16$ TeV (2024), [arXiv:2402.14975 \[hep-ex\]](#).
- [331] A. M. Sirunyan *et al.* (CMS), Evidence for $X(3872)$ in Pb-Pb Collisions and Studies of its Prompt Production at $\sqrt{s_{NN}}=5.02$ TeV, *Phys. Rev. Lett.* **128**, 032001 (2022), [arXiv:2102.13048 \[hep-ex\]](#).
- [332] S. Cho *et al.* (ExHIC), Multi-quark hadrons from Heavy Ion Collisions, *Phys. Rev. Lett.* **106**, 212001 (2011), [arXiv:1011.0852 \[nucl-th\]](#).

- [333] S. Cho *et al.* (ExHIC), Studying Exotic Hadrons in Heavy Ion Collisions, *Phys. Rev. C* **84**, 064910 (2011), [arXiv:1107.1302 \[nucl-th\]](#).
- [334] L. M. Abreu, K. P. Khemchandani, A. Martinez Torres, F. S. Navarra, and M. Nielsen, $X(3872)$ production and absorption in a hot hadron gas, *Phys. Lett. B* **761**, 303 (2016), [arXiv:1604.07716 \[hep-ph\]](#).
- [335] A. M. Sirunyan *et al.* (CMS), Observation of prompt J/ψ meson elliptic flow in high-multiplicity pPb collisions at $\sqrt{s_{\text{NN}}} = 8.16$ TeV, *Phys. Lett. B* **791**, 172 (2019), [arXiv:1810.01473 \[hep-ex\]](#).
- [336] A. M. Sirunyan *et al.* (CMS), Elliptic flow of charm and strange hadrons in high-multiplicity pPb collisions at $\sqrt{s_{\text{NN}}} = 8.16$ TeV, *Phys. Rev. Lett.* **121**, 082301 (2018), [arXiv:1804.09767 \[hep-ex\]](#).
- [337] S. Acharya *et al.* (ALICE), Azimuthal Anisotropy of Heavy-Flavor Decay Electrons in p -Pb Collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *Phys. Rev. Lett.* **122**, 072301 (2019), [arXiv:1805.04367 \[nucl-ex\]](#).
- [338] S. Acharya *et al.* (ALICE), Measurements of azimuthal anisotropies at forward and backward rapidity with muons in high-multiplicity p -Pb collisions at $s_{\text{NN}}=8.16$ TeV, *Phys. Lett. B* **846**, 137782 (2023), [arXiv:2210.08980 \[nucl-ex\]](#).
- [339] S. Acharya *et al.* (ALICE), Search for collectivity with azimuthal J/ψ -hadron correlations in high multiplicity p -Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ and 8.16 TeV, *Phys. Lett. B* **780**, 7 (2018), [arXiv:1709.06807 \[nucl-ex\]](#).
- [340] G. Aad *et al.* (ATLAS), Measurement of azimuthal anisotropy of muons from charm and bottom hadrons in pp collisions at $\sqrt{s} = 13$ TeV with the ATLAS detector, *Phys. Rev. Lett.* **124**, 082301 (2020), [arXiv:1909.01650 \[nucl-ex\]](#).
- [341] B. B. Abelev *et al.* (ALICE), Long-range angular correlations of π , K and p in p -Pb collisions at $\sqrt{s_{\text{NN}}} = 5.02$ TeV, *Phys. Lett. B* **726**, 164 (2013), [arXiv:1307.3237 \[nucl-ex\]](#).
- [342] J. Noronha, B. Schenke, C. Shen, and W. Zhao, Progress and Challenges in Small Systems (2024) [arXiv:2401.09208 \[nucl-th\]](#).
- [343] J. H. Liu, S. Plumari, S. K. Das, V. Greco, and M. Ruggieri, Diffusion of heavy quarks in the early stage of high-energy nuclear collisions at energies available at the BNL Relativistic Heavy Ion Collider and at the CERN Large Hadron Collider, *Phys. Rev. C* **102**, 044902 (2020), [arXiv:1911.02480 \[nucl-th\]](#).

- [344] D. Avramescu, V. Băran, V. Greco, A. Ipp, D. I. Müller, and M. Ruggieri, Simulating jets and heavy quarks in the glasma using the colored particle-in-cell method, [Phys. Rev. D](#) **107**, 114021 (2023), [arXiv:2303.05599 \[hep-ph\]](#).