
Decision-Focused Surrogate Modeling for Mixed-Integer Linear Optimization

Shivi Dixit, Rishabh Gupta, Qi Zhang

Department of Chemical Engineering and Materials Science
University of Minnesota, Twin Cities
qizh@umn.edu

Abstract

Mixed-integer optimization is at the core of many online decision-making systems that demand frequent updates of decisions in real time. However, due to their combinatorial nature, mixed-integer linear programs (MILPs) can be difficult to solve, rendering them often unsuitable for time-critical online applications. To address this challenge, we develop a data-driven approach for constructing surrogate optimization models in the form of linear programs (LPs) that can be solved much more efficiently than the corresponding MILPs. We train these surrogate LPs in a decision-focused manner such that for different model inputs, they achieve the same or close to the same optimal solutions as the original MILPs. One key advantage of the proposed method is that it allows the incorporation of all of the original MILP's linear constraints, which significantly increases the likelihood of obtaining feasible predicted solutions. Results from two computational case studies indicate that this decision-focused surrogate modeling approach is highly data-efficient and provides very accurate predictions of the optimal solutions. In these examples, it outperforms more commonly used neural-network-based optimization proxies.

1 Introduction

Effectively operating complex systems in online environments, where input parameters are constantly changing, requires efficient decision making in real time. Many online decision-making frameworks involve the solving of mathematical optimization problems; however, often the computational complexity of the given optimization problem presents a major challenge such that the long solution time renders it ineffective in real-time applications. A common approach to tackling this challenge is to perform the online optimization with a *surrogate model*, which is an approximation of the original model that can be solved more efficiently (5).

Surrogate modeling for optimization typically involves three steps: (i) identify the complicating constraints in the original optimization model, (ii) generate surrogate models for the complicating constraint functions, and (iii) replace the complicating constraints with the surrogates to obtain a surrogate optimization model that can be solved more efficiently. This approach is especially effective in applications where the computational complexity of the problem is only due to a small part of the model such that one can keep most of the original constraints. Here, a major underlying assumption is that a surrogate model that provides a good approximation of the complicating constraints will also, once incorporated into the optimization problem, lead to solutions that are close to the true optimal solutions. However, this assumption often does not hold. The original optimization problem and the surrogate optimization problem may achieve very different optimal solutions despite having a highly accurate (but not perfect) embedded surrogate model.

Recently, Gupta and Zhang (15) have developed a new surrogate modeling framework that explicitly aims to construct surrogate models that minimize the *decision prediction error* defined as the

difference between the optimal solutions of the original and the surrogate optimization problems; it is hence referred to as *decision-focused surrogate modeling* (DFSM). DFSM has been applied to construct convex DFSOMs for nonconvex nonlinear programs that are difficult to solve to global optimality Gupta and Zhang (15); however, these problems only involve continuous variables. In this work, we extend the DFSM framework to MILPs, which arise in many real-time decision-making problems such as online production scheduling and hybrid model predictive control. Due to their combinatorial nature, MILPs can take long times to solve. Here, we propose to construct DFSOMs in the form of LPs that are computationally significantly more efficient and achieve optimal solutions close to the ones of the original MILPs.

2 Related work

In this section, we provide a brief review of related works. Note that we do not review the vast literature on surrogate modeling as the methods described therein are of less relevance to us given our specific focus on MILPs and decision-focused modeling approaches.

2.1 ML-based optimization proxies

The line of research that is most closely related to this work is the one on constructing optimization proxies using machine learning (ML). Here, the goal is to learn a direct mapping of the input parameters of an optimization problem to its optimal solution. In that sense, it has the same objective as DFSM, namely to obtain a model that predicts optimal solutions close to the true ones. It uses the same offline generated data consisting of different model inputs and the corresponding true optimal solutions. The main difference is that while DFSM trains a model in the form of a surrogate optimization problem, optimization proxies are ML models, most commonly neural networks (NNs) (30; 26; 18; 21).

Optimization proxies take advantage of the expressive power of deep NNs; however, in deep learning, it is difficult to enforce constraints on the predictions, which often leads to predicted solutions that are infeasible in the original optimization problem. In their work on constructing NN-based optimization proxies for the AC optimal power flow (OPF) problem, Zamzam and Baker (35) ensure feasibility by generating a training set of strictly feasible solutions through a modified AC OPF formulation and by using the natural bounds of the sigmoid activation function to enforce generation and voltage limits. When also addressing the AC OPF problem, Fioretto et al. (13) consider constraints in their deep learning framework by augmenting the loss function with penalty terms derived from the Lagrangian dual of the original optimization problem and applying a subgradient method to update the Lagrange multipliers. This approach has also been applied to the security-constrained OPF problem (33) and job shop scheduling (20). Most of these and similar approaches increase the likelihood of obtaining feasible predictions but cannot guarantee it; hence, in most cases, a feasibility restoration step is added to obtain a feasible solution. One common approach to correcting an infeasible prediction is to project it onto a suitable set such that the projection is a feasible solution (6; 27).

2.2 Decision-focused learning

We now describe a framework that is closely related to the DFSM approach but is not motivated by the need for fast online optimization. Instead, it addresses the following problem: In traditional data-driven optimization, we often follow a two-stage predict-then-optimize approach, i.e. we first predict unknown input parameters from data with external features and then solve the optimization problem with those predicted inputs. Here, the learning step focuses on minimizing the parameter estimation error; however, this does not necessarily lead to the best decisions (evaluated with the true parameter values) in the optimization step. In contrast, *decision-focused learning* (34), also known as *smart predict-then-optimize* (10) or *predict-and-optimize* (23), integrates the two steps to explicitly account for the quality of the optimization solution in the learning of the model parameters.

Elmachtoub and Grigas (10) consider decision-focused learning for optimization problems with a linear objective function and a closed convex feasible region. They develop a convex surrogate loss function that is Fisher consistent with respect to the original loss function and allows the use of stochastic gradient descent to efficiently solve the problem. The same algorithm has also been applied to combinatorial problems (23). Decision-focused learning has further motivated research

on differentiable optimization in deep learning (1), which allows NNs to comprise differentiable layers that represent full optimization problems. Using this approach, quadratic programs (8), linear programs (34), and mixed-integer linear programs (11) have been considered in the training of decision-focused NNs. This approach is applied by Ferber et al. (12) to address a problem of similar nature as our DFSM problem, namely to learn linear surrogate objective functions for discrete optimization problems with linear constraints but nonlinear objective functions.

2.3 ML-enhanced mixed-integer optimization

There is a rapidly growing body of literature on using ML to speed up the solution of mixed-integer optimization problems (3). Our work as well as the ML-based optimization proxies reviewed in Section 2.1 fall into this broad category. Other strategies include using ML to learn more effective primal heuristics (2; 29), branching rules (22; 19), the set of active constraints at the optimal solution (4), and how to warm-start MILPs (17). More closely related to our work are the contributions on learning how to improve the generation of cutting planes (7; 32; 16). However, while these methods add cuts as part of a branch-and-cut algorithm, our approach learns parametric cuts that can be added immediately to the LP relaxation for a given model input, as discussed in more detail in Section 3.

3 DFSM for MILPs

We consider MILPs, which we aim to solve efficiently in an online setting, given in the following general form:

$$\begin{aligned} & \underset{x}{\text{minimize}} && c(u)^\top x \\ & \text{subject to} && A(u)x \leq b(u) \\ & && x \in \mathbb{R}^m \times \mathbb{Z}^{n-m}, \end{aligned} \tag{1}$$

where x is a vector of continuous and discrete variables. The cost vector, constraint matrix, and right-hand-side vector are denoted by $c(u)$, $A(u)$, and $b(u)$, respectively, which generally all depend on the input parameters u .

In general, the complicating constraints in an MILP are the integrality constraints on the discrete variables. Here, the key idea is to replace them with simple linear inequalities. This is motivated by a fundamental property of MILPs that can be stated as follows (28): Given a mixed-integer polyhedral set $\mathcal{S} = \{x \in \mathbb{R}^m \times \mathbb{Z}^{n-m} : Ax \leq b\}$, there exist \bar{A} and \bar{b} such that the convex hull of \mathcal{S} is $\text{conv}(\mathcal{S}) = \{x \in \mathbb{R}^n : Ax \leq b, \bar{A}x \leq \bar{b}\}$, as illustrated in Figure 1. Then, loosely speaking, an MILP with a cost vector c and \mathcal{S} as its feasible region will have the same optimal value as an LP with the same cost vector and constrained by $Ax \leq b$ and $\bar{A}x \leq \bar{b}$. Moreover, if that MILP has a unique optimal solution, the corresponding LP will have the same optimal solution, i.e. $\arg \min_x \{c^\top x : x \in \mathcal{S}\} = \arg \min_x \{c^\top x : x \in \text{conv}(\mathcal{S})\}$.

One does not have to recover the full convex hull to obtain an LP that achieves the same optimal solution as the MILP. As illustrated in Figure 1, for the given cost vector c , the LP with $\mathcal{S}' = \{x \in \mathbb{R}^n : Ax \leq b, \hat{A}x \leq \hat{b}\}$ as its feasible region, where $\hat{A}x \leq \hat{b}$ are a smaller set of constraints, will equally lead to the same optimal solution. This idea forms the basis for traditional exact cutting-plane approaches, where linear inequalities are successively added to the linear relaxation of the MILP until the optimal solution is found (25). The downside of a cutting-plane algorithm (or one implemented in a branch-and-cut scheme) is that for every new instance of the MILP, new cutting planes need to be generated in the same iterative fashion, which can be too time-intensive for real-time applications.




Figure 1: Illustrative example in which for the given cost vector c , the MILP with integer variables x_1 and x_2 and constraints $Ax \leq b$ has the same optimal solution as the LPs with $\text{conv}(\mathcal{S})$ and \mathcal{S}' as their feasible regions.

In our DFSM approach, we propose to learn LPs with added linear inequalities parameterized by the input parameters u as surrogate optimization models for the corresponding MILPs. As such, this approach can be interpreted as learning parametric cutting planes that are generated a priori and change automatically with each new instance given by new values for the input parameters u .

3.1 General formulation

Given an MILP of the form (1), the surrogate LP that we aim to construct can be written as follows:

$$\underset{x \in \mathbb{R}^n}{\text{minimize}} \quad c(u)^\top x \quad (2a)$$

$$\text{subject to} \quad A(u)x \leq b(u) \quad (2b)$$

$$\hat{A}(u, \theta)x \leq \hat{b}(u, \theta), \quad (2c)$$

where (2b) are the original inequality constraints of problem (1), and (2c) are the new set of linear constraints that we want to learn. The elements of both the constraint matrix \hat{A} and right-hand-side vector \hat{b} are functions of the input parameters u . These functional relationships are parameterized by the parameters θ and can in principle be of arbitrary complexity. In this work, we use low-order polynomials, which have proven to be sufficiently accurate in our case studies and also provide some computational advantages (see Section 3.2). In this case, θ are the coefficients of the polynomial terms. In Appendix A.1, we present an illustrative example that highlights how such parametric inequalities can help the surrogate LP recover the optimal solutions of the original MILP.

The DFSM problem for learning a DFSOM of the form (2) can be formulated as follows:

$$\underset{\theta \in \Theta, \hat{x}}{\text{minimize}} \quad \sum_{i \in \mathcal{I}} \|x_i^* - \hat{x}_i\|_1 \quad (3a)$$

$$\text{subject to} \quad \hat{x}_i \in \arg \min_{x \in \mathbb{R}^n} \{c^\top x : A(\bar{u}_i)x \leq b(\bar{u}_i), \hat{A}(\bar{u}_i, \theta)x \leq \hat{b}(\bar{u}_i, \theta)\} \quad \forall i \in \mathcal{I}, \quad (3b)$$

where $\mathcal{I} = \{(\bar{u}_i, x_i^*)\}_{i=1}^N$ constitutes the training dataset with x_i^* being the optimal solution to the original MILP (1) for input \bar{u}_i . As shown in (3a), we use the ℓ_1 -norm to measure the decision error, and the objective is to choose θ from some appropriate set Θ such that the sum of decision errors across all training data points is minimized. Problem (3) is a bilevel optimization problem with N lower-level problems. As shown in (3b), each lower-level problem represents the surrogate LP for a particular input \bar{u}_i , and \hat{x}_i is constrained to be an optimal solution to that LP.

3.2 Solution strategy

To solve problem (3), we first reformulate it into a single-level optimization problem by replacing the lower-level problems with their KKT optimality conditions, which results in the following formulation:

$$\underset{\theta \in \Theta, \hat{x}, \lambda, \mu}{\text{minimize}} \quad \sum_{i \in \mathcal{I}} \|x_i^* - \hat{x}_i\|_1 \quad (4a)$$

$$\text{subject to} \quad c + A(\bar{u}_i)^\top \lambda_i + \hat{A}(\bar{u}_i, \theta)^\top \mu_i = 0 \quad \forall i \in \mathcal{I} \quad (4b)$$

$$A(\bar{u}_i)\hat{x}_i - b(\bar{u}_i) \leq 0 \quad \forall i \in \mathcal{I} \quad (4c)$$

$$\hat{A}(\bar{u}_i, \theta)\hat{x}_i - \hat{b}(\bar{u}_i, \theta) \leq 0 \quad \forall i \in \mathcal{I} \quad (4d)$$

$$D(\lambda_i)(A(\bar{u}_i)\hat{x}_i - b(\bar{u}_i)) = 0 \quad \forall i \in \mathcal{I} \quad (4e)$$

$$D(\mu_i)(\hat{A}(\bar{u}_i, \theta)\hat{x}_i - \hat{b}(\bar{u}_i, \theta)) = 0 \quad \forall i \in \mathcal{I} \quad (4f)$$

$$\lambda_{ir} \geq 0, \mu_{ij} \geq 0, \hat{x}_i \in \mathbb{R}^n \quad \forall i \in \mathcal{I}, r \in \mathcal{R}, j \in \mathcal{V}, \quad (4g)$$

where (4b) are the stationarity conditions, (4c)-(4d) are the primal feasibility conditions, (4e)-(4f) are the complementary slackness conditions, and (4g) are the dual feasibility conditions. The dual variables are denoted by λ and μ . In (4e)-(4f), $D(\cdot)$ denotes a diagonal matrix formed from a given vector, \mathcal{R} represents the set of original constraints in the MILP, and \mathcal{V} represents the set of additional constraints in the DFSOM.

Problem (4) is a nonconvex NLP that violates constraint qualification (due to, for example, the complementary slackness conditions), which means that standard NLP solvers cannot guarantee

convergence to the optimal solution when directly applied to this problem. Here, we adopt the solution strategy proposed by Gupta and Zhang (14) for data-driven inverse optimization problems, which turn out to have the same structure as the DFSM problem. We apply an exact penalty reformulation that is achieved by penalizing the violation of constraints (4b)-(4f) in the objective function using the ℓ_1 -norm. We can then iteratively update the penalty parameter until no more constraint violation is observed at which point the algorithm is guaranteed to have converged to a local solution of problem (4). The penalty reformulation takes the form of a multiconvex optimization problem in terms of the three sets of variables θ , \hat{x} , and (λ, μ) , i.e. the problem is convex with respect to each of these three sets of variables. This structure can be exploited using a block coordinate descent (BCD) algorithm that allows an efficient decomposition of the problem, which has been crucial in solving large instances of the DFSM problem. For more details on the solution algorithm, see Appendix A.2.

4 Computational case studies

We conduct two computational case studies to assess the efficacy of the proposed DFSM approach. Both examples are representative of common real-time optimization problems involving both continuous and discrete decisions. All optimization problems were implemented in Julia v1.7.2 using the modeling environment JuMP v0.22.3 (9). We applied Gurobi v10.3 to solve all LPs and MILPs, and all NLPs were solved using IPOPT v0.9.1. All DFSM instances were solved utilizing 24 cores and 60 GB memory on the Mesabi cluster of the Minnesota Supercomputing Institute (MSI) equipped with Intel Haswell E5-2680v3 processors.

4.1 Hybrid vehicle control

We first consider a hybrid vehicle control problem adapted from Takapoui et al. (31). Given a hybrid vehicle with a battery, an electric generator, and an engine, the objective is to minimize the fuel consumption cost over a given time horizon while also maintaining a high terminal battery level. This problem can be formulated as the following MILP:

$$\begin{aligned} & \underset{E, P^{\text{batt}}, P^{\text{eng}}, z}{\text{minimize}} && \sum_{t=0}^{T-1} (\alpha_t P_t^{\text{eng}} + \beta z_t) + \eta(E^{\text{max}} - E_T) \end{aligned} \quad (5a)$$

$$\text{subject to} \quad E_0 = E_{\text{init}} \quad (5b)$$

$$0 \leq E_t \leq E^{\text{max}} \quad \forall t = 0, \dots, T \quad (5c)$$

$$E_{t+1} = E_t - \tau P_t^{\text{batt}} \quad \forall t = 0, \dots, T-1 \quad (5d)$$

$$0 \leq P_t^{\text{eng}} \leq z_t P^{\text{max}}/S \quad \forall t = 0, \dots, T-1 \quad (5e)$$

$$P_t^{\text{batt}} + P_t^{\text{eng}} \geq D_t \quad \forall t = 0, \dots, T-1 \quad (5f)$$

$$z_t \in \{0, 1, \dots, S\} \quad \forall t = 0, \dots, T-1. \quad (5g)$$

Here, the decision variables are given for each time period t , starting with the energy status of the battery E_t , then the power to or from the battery P_t^{batt} , the power from the engine P_t^{eng} , and the engine switch status z_t . The input parameters are the power demand D_t over the T time periods and the initial battery state E_{init} . The cost function to be minimized, (5a), contains the fuel cost in each time period given by $\alpha_t P_t + \beta_t z_t$ and a penalty on the deviation of the terminal battery charge from its maximum given by $\eta(E^{\text{max}} - E_T)$. The initial battery state is given by (5b). The bounds on the battery state are stated in (5c). The battery charge balance is given by (5d), where τ denotes the length of each time interval. We assume that the engine can operate at different levels, modeled using the integer variable z_t . The different levels represent different fractions of the maximum engine power available for use in a given time period. As per constraints (5e), when $z_t = 0$, no power can be derived from the engine, and when $z_t = S$, the maximum amount of power can be drawn. Finally, the combined power output from the battery and the engine must at least match the demand D_t as stated in (5f).

4.1.1 Data generation and surrogate design

To generate different problem instances, we choose $\eta \sim \mathcal{N}(2.5, 5.5)$, $\alpha_t \sim \mathcal{N}(6, 16)$, $\beta_t \sim \mathcal{N}(0.5, 2)$, and $E_{\text{init}} \sim \mathcal{N}(90, 97)$, and set $\tau = 5$, $P^{\text{max}} = 1$, and $E^{\text{max}} = 100$. For each instance, the training dataset is generated by varying the power demand profile D , which is the model

input, and solving the original MILP for that demand profile to obtain the corresponding optimal solution $(E^*, P^{\text{eng}*}, z^*)$. Repeating this process provides a set of data points, each consisting of an input-solution pair.

The additional linear inequalities in the postulated surrogate LP take the form of $\hat{A}(D, \theta)[E \ P^{\text{eng}} \ z]^\top \leq \hat{b}(D, \theta)$, where the number of constraints $|\mathcal{V}|$ is a hyperparameter that can be adjusted. Each element of \hat{A} and \hat{b} is a cubic polynomial in D with θ being the coefficients. In this case, the time required to train the surrogate model for 100 training data points is around 10,000 seconds.

We also compare the performance of the DFSM approach with that of more commonly used NN-based optimization proxies, which are similarly trained in a decision-focused manner using the same datasets. Details on the architecture of these NNs and how they were trained are provided in Appendix A.3.

4.1.2 Surrogate model performance

All reported values are averaged over 10 different randomly generated instances. For both the DFSOM and the NN-based optimization proxy, if a predicted solution is not directly integer-feasible, an inexpensive projection-based feasibility restoration problem is solved to recover a feasible solution. More details on the feasibility restoration step can be found in Appendix A.4.

The decision prediction errors and optimality gaps for each instance are determined using 100 unseen test data points, each given by a different power demand profile. The relative prediction error is defined as the ℓ_1 -norm of the difference between the predicted solution (after feasibility restoration) and true optimal solution divided by the ℓ_1 -norm of the true optimal solution. Similarly, the optimality gap is the difference between the costs of the predicted and true optimal solutions. The size of the problem increases with T . In the following, we present results for the case with $T = 30$, which has 61 continuous variables, 30 integer variables, and 122 constraints in the resulting MILP; additional results for $T = 10$ and $T = 20$ are shown in Appendix A.5.

Figure 2 compares the performance of the DFSOM and the NN-based optimization proxy. For both methods, it shows how the prediction errors and optimality gaps change with the number of training data points. Note that while the maximum number of training data points we use to construct each DFSOM is 100, we use up to 500 data points to train the NNs. Also, to aid the interpretation of the results, we show the prediction errors with respect to the discrete (Figure 2(a)) and continuous (Figure 2(b)) decisions separately. We observe that the DFSOM significantly outperforms the NN in terms of prediction accuracy as the prediction errors plateau at much lower values as the size of the training dataset increases. DFSM also proves to be very data-efficient as it achieves a high prediction accuracy with only 50 data points while the NNs seem to require much more data.




Figure 2: DFSOM performance compared to NN-based optimization proxy in the hybrid vehicle control problem.

Notice that the relative prediction errors that the DFSOM achieves are about 20% and 8% in terms of the discrete and continuous decisions, respectively, which seem relatively high. The corresponding optimality gaps, however, are close to zero, as shown in Figure 2(c). While surprising at first, upon closer investigation, we can attribute this behavior to the specific nature of the hybrid vehicle control problem. Given a fixed solution in terms of the discrete variables z for problem (5), due to the flexibility that the battery provides, there are many solutions in terms of the continuous variables that are optimal or close to optimal. Moreover, as the cost parameter α_t has a much larger value than β_t , the contribution of the continuous variables to the total cost outweighs that of the discrete

variables. As a result, from a cost standpoint, it is more important to predict the continuous variables accurately, hence the difference in the relative prediction errors. However, it is also important to predict feasible discrete solutions, which is where DFSM has an advantage as it keeps all linear inequalities from the original MILP in the DFSOM. The NN tends to predict solutions that are far from being integer-feasible such that the obtained solutions after feasibility restoration are highly suboptimal, as indicated in Figure 2(c).

We further investigate the impact of the number of added constraints, $|\mathcal{V}|$, on the performance of the resulting DFSOM. Figure 3 shows the decision prediction errors and optimality gaps for different $|\mathcal{V}|$. Here, we can see that when $T/3$ linear inequalities are added, the DFSOM cannot reduce the prediction error to a reasonable level even with a large number of training data points. As we increase $|\mathcal{V}|$ to T and then to $2T$, the prediction accuracy increases significantly. However, there is only a marginal improvement from $|\mathcal{V}| = 2T$ to $|\mathcal{V}| = 3T$, which indicates that $|\mathcal{V}| = 2T$ is likely a good choice that provides a good balance between prediction accuracy and computational complexity.




Figure 3: DFSOM data points performance for varying number of constraints learned ($|\mathcal{V}|$) in the hybrid vehicle control problem.

Finally, we consider 1,000 randomly generated problem instances to compare the computation times of solving the original MILPs, the corresponding DFSOMs, and the original MILPs but to the same optimality gaps as achieved by the DFSOMs. The third method serves as a benchmark heuristic solution method that allows a fair comparison with the DFSOM. Figure 6(a) shows the number of instances solved by each of the three methods as the solution time increases. One can see that the surrogate LP clearly outperforms the MILP, even when the MILP is only solved to achieve a solution of the same quality as the DFSOM.

4.2 Production scheduling

In the second case study, we consider a single-stage production scheduling problem with parallel units, which can be formulated as the following MILP (24):

$$\underset{S, T, X}{\text{minimize}} \quad \sum_{i \in \mathcal{I}} \sum_{j \in \mathcal{J}} \sum_{t \in \mathcal{T}} \gamma_{ij} X_{ijt} \quad (6a)$$

$$\text{subject to} \quad T_{jt} \geq T_{j,t-1} \quad \forall j \in \mathcal{J}, t \in \mathcal{T} \quad (6b)$$

$$\sum_{j \in \mathcal{J}} \sum_{t \in \mathcal{T}} X_{ijt} = 1 \quad \forall i \in \mathcal{I} \quad (6c)$$

$$\sum_{i \in \mathcal{I}} X_{ijt} \leq 1 \quad \forall j \in \mathcal{J}, t \in \mathcal{T} \quad (6d)$$

$$S_{ij} \leq M \sum_{t \in \mathcal{T}} X_{ijt} \quad \forall i \in \mathcal{I}, j \in \mathcal{J} \quad (6e)$$

$$S_{ij} \geq T_{j,t-1} - \eta(1 - X_{ijt}) \quad \forall i \in \mathcal{I}, j \in \mathcal{J}, t \in \mathcal{T} \quad (6f)$$

$$S_{ij} + \tau_{ij} \leq T_{jt} + \eta(1 - X_{ijt}) \quad \forall i \in \mathcal{I}, j \in \mathcal{J}, t \in \mathcal{T} \quad (6g)$$

$$\sum_j S_{ij} \geq \rho_i \quad \forall i \in \mathcal{I} \quad (6h)$$

$$\sum_j S_{ij} + \sum_{j \in \mathcal{J}} \sum_{t \in \mathcal{T}} \tau_{ij} X_{ijt} \leq \epsilon_i, \quad \forall i \in \mathcal{I} \quad (6i)$$

$$S_{ij} \geq 0, T_{jt} \geq 0, X_{ijt} \in \{0, 1\} \quad \forall i \in \mathcal{I}, j \in \mathcal{J}, t \in \mathcal{T}, \quad (6j)$$

where \mathcal{J} denotes the set of units, \mathcal{I} is the set of batches to be processed, \mathcal{T} is the set of time slots, and η is the horizon length. For each batch i , we are given a release time ρ_i , a due time ϵ_i , and processing time τ_{ij} if it is processed on unit j . The binary variable X_{ijt} equals 1 if batch i is processed on unit j in time slot t , which is associated with a cost denoted by γ_{ij} ; S_{ij} denotes the start time of batch i on unit j , and T_{jt} is the end time of time slot t for unit j . The objective is to minimize the total production cost given in (6a). Constraints (6b) ensure the non-negative length of each time slot, equations (6c) ensure that every batch is processed, (6d) allow at most one batch to be processed on a given unit at a given time, (6e) set the start time of a batch on a unit to 0 if the batch is not being processed at any time on that unit and otherwise provide a bound on the start time, (6f) and (6g) combined determine the end time of a time slot on each unit, (6h) only allow a batch to start processing after its release, and (6i) ensure that the processing of each batch is completed before its due time.

4.2.1 Data generation and surrogate design

In all problem instances, we use a horizon length of $\eta = 40$. We choose $\tau_{ij} \sim \mathcal{N}(1, 7)$, $\rho_i \sim \mathcal{N}(1, 9)$, $\epsilon_i \sim \mathcal{N}(10, 39)$, $\gamma_{ij} \sim \mathcal{N}(30, 100)$, and we set $M = \max_{i \in \mathcal{I}}(\epsilon_i)$. Here, the model input parameters are ρ , ϵ , and τ , which we vary to generate the training datasets. We also set $\mathcal{T} = \{1, \dots, 8\}$, which is the smallest set that is still sufficiently large for all considered instances. With $|\mathcal{I}| = 13$, $|\mathcal{J}| = 4$, and $|\mathcal{T}| = 8$, the MILP has 84 continuous variables, 416 binary variables, and 987 constraints.

In the hybrid vehicle control case study, we learned additional linear inequalities that involve all decision variables. If we were to take the same approach here, each new constraint would involve $|\mathcal{I}||\mathcal{J}||\mathcal{T}| + |\mathcal{I}||\mathcal{J}| + |\mathcal{J}||\mathcal{T}|$ decision variables; this would lead to a very large number of parameters to be learned, which would significantly increase the computational complexity of the DFSM problem. Hence, instead, we try to exploit the structure of the scheduling problem in designing the additional constraints. Specifically, we notice that most of the constraints in (5) are written for all $i \in \mathcal{I}$, and it also makes intuitive sense that the relationships are strongest among the variables associated with the same batch. Using this rationale, we propose to add for each batch i linear inequalities that only involve variables associated with that batch. The constraint coefficients and right-hand-sides are given as quadratic functions of the input parameters. In this case, the time taken to train the surrogate model for 100 training data points is around 3,000 seconds.

4.2.2 Surrogate model performance

Like in the first case study, we assess the performance of the DFSOM as well as that of an NN-based optimization proxy. Note that the MILP solutions that serve as the basis for comparison are obtained at 1% optimality gap since many problem instances cannot be solved to full optimality within several hours. The results in Figure 4 show that the DFSOM clearly outperforms the NN. The DFSM approach is again very data-efficient, achieving a decision prediction error with respect to the binary variables of less than 10% with only 50 training data points (Figure 4(a)). In this case, the prediction error with respect to the continuous variables is much higher and does not improve with increasing number of training data points (Figure 4(b)), yet the DFSOM still achieves very small optimality gaps (Figure 4(c)). The reason is that the objective function in problem (6) only involves the binary variables, which is why the optimality gap will be small as long as the solution in terms of the binary variables is predicted accurately. In addition, for a fixed assignment of batches to units and time slots (discrete decisions), there are many start times (continuous variables) that are feasible and hence optimal since they do not affect the cost. Due to this multiplicity of optimal solutions, it is not surprising that the surrogate LP does not achieve the same solutions in terms of the continuous variables. But as long as the predicted solutions in terms of the binary variables are close to the true ones, the DFSOM will perform well.

Figure 5 shows the impact of the number of added constraints on the DFSOM's performance. Here, $|\mathcal{V}|$ denotes the number of constraints added per batch. Interestingly, we observe that it is sufficient to add just one constraint for each batch. In fact, the DFSOMs for $|\mathcal{V}| = 5$ and $|\mathcal{V}| = 10$ have much larger prediction errors with respect to the binary variables and optimality gaps for smaller training datasets, which indicates overfitting.

We again solve 1,000 problem instances to compare the computation times of solving the original MILPs, the corresponding DFSOMs, and the original MILPs but to the same optimality gaps as achieved by the DFSOMs. In this case, the original MILPs were solved to 1% optimality gap as




Figure 4: DFSOM performance compared to NN-based optimization proxy in the production scheduling problem.




Figure 5: DFSOM performance for varying number of constraints learned ($|\mathcal{V}|$) in the production scheduling problem.

it would have taken excessively long to solve them to full optimality. Even with 1% optimality, as shown in Figure 6(b), some instances of the MILP take multiple hours to solve while the DFSOM solves within a few seconds in all instances.




Figure 6: Computational performance of DFSOMs evaluated across 1,000 random instances in each case compared to directly solving the original MILPs and to solving the MILPs to the same optimality gaps achieved by the corresponding DFSOMs.

5 Conclusions

Motivated by the need to solve difficult MILPs in real-time settings, we developed a data-driven approach for constructing efficient surrogate LPs that can replace the MILPs. When generating these surrogate LPs, we explicitly try to minimize the decision prediction error defined as the difference between the optimal solutions of the surrogate and the original optimization problems. The resulting decision-focused surrogate modeling problem is a large-scale bilevel program that we solve using a penalty-based block coordinate descent algorithm. In our computational case studies, we demonstrated the efficacy of the proposed approach both in terms of prediction accuracy and data efficiency. It also allows the use of problem-specific knowledge to design surrogate model structures that enhance the training and/or the performance of the surrogate optimization models.

References

- [1] Brandon Amos and J. Zico Kolter. Optnet: Differentiable optimization as a layer in neural networks. 3 2017.
- [2] Yoshua Bengio, Emma Frejinger, Andrea Lodi, Rahul Patel, and Sriram Sankaranarayanan. A learning-based algorithm to quickly compute good primal solutions for stochastic integer programs. In *Integration of Constraint Programming, Artificial Intelligence, and Operations Research: 17th International Conference, CPAIOR 2020, Vienna, Austria, September 21–24, 2020, Proceedings 17*, pages 99–111. Springer, 2020.
- [3] Yoshua Bengio, Andrea Lodi, and Antoine Prouvost. Machine learning for combinatorial optimization: a methodological tour d’horizon. *European Journal of Operational Research*, 290(2):405–421, 2021.
- [4] Dimitris Bertsimas and Bartolomeo Stellato. Online mixed-integer optimization in milliseconds. *INFORMS Journal on Computing*, 34(4):2229–2248, 2022.
- [5] Atharv Bhosekar and Marianthi Ierapetritou. Advances in surrogate based modeling, feasibility analysis, and optimization: A review. *Computers and Chemical Engineering*, 108:250–267, 2018.
- [6] Steven Chen, Kelsey Saulnier, Nikolay Atanasov, Daniel D. Lee, Vijay Kumar, George J. Pappas, and Manfred Morari. Approximating Explicit Model Predictive Control Using Constrained Neural Networks. In *Proceedings of the American Control Conference*, pages 1520–1527. AACC, 2018.
- [7] Arnaud Deza and Elias B Khalil. Machine learning for cutting planes in integer programming: A survey. *arXiv preprint arXiv:2302.09166*, 2023.
- [8] Priya L Donti, Brandon Amos, and J Zico Kolter. Task-based End-to-End Model Learning in Stochastic Optimization. In *Advances in Neural Information Processing Systems 30*, 2017.
- [9] Iain Dunning, Joey Huchette, and Miles Lubin. Jump: A modeling language for mathematical optimization. *SIAM Review*, 59(2):295–320, 2017.
- [10] Adam N. Elmachtoub and Paul Grigas. Smart "Predict, then Optimize". *Management Science*, 68(1):9–26, 2022.
- [11] Aaron Ferber, Bryan Wilder, Bistra Dilkina, and Milind Tambe. MIPaaL: Mixed integer program as a layer. In *AAAI 2020 - 34th AAAI Conference on Artificial Intelligence*, pages 1504–1511, 2020.
- [12] Aaron M Ferber, Taoan Huang, Daochen Zha, Martin Schubert, Benoit Steiner, Bistra Dilkina, and Yuandong Tian. Surco: Learning linear surrogates for combinatorial nonlinear optimization problems. In *International Conference on Machine Learning*, pages 10034–10052. PMLR, 2023.
- [13] Ferdinando Fioretto, Terrence W. K. Mak, and Pascal van Hentenryck. Predicting AC optimal power flows: Combining deep learning and Lagrangian dual methods. In *Proceedings of the AAAI Conference on Artificial Intelligence*, pages 630–637, 2020.
- [14] Rishabh Gupta and Qi Zhang. Efficient learning of decision-making models: A penalty block coordinate descent algorithm for data-driven inverse optimization. *Computers & Chemical Engineering*, page 108123, 2022.
- [15] Rishabh Gupta and Qi Zhang. Data-driven decision-focused surrogate modeling. *AIChE Journal*, page e18338, 2024.
- [16] Zeren Huang, Kerong Wang, Furui Liu, Hui-Ling Zhen, Weinan Zhang, Mingxuan Yuan, Jianye Hao, Yong Yu, and Jun Wang. Learning to select cuts for efficient mixed-integer programming. *Pattern Recognition*, 123:108353, 2022.

- [17] Asunción Jiménez-Cordero, Juan Miguel Morales, and Salvador Pineda. Warm-starting constraint generation for mixed-integer optimization: A machine learning approach. *Knowledge-Based Systems*, 253:109570, 2022.
- [18] Benjamin Karg and Sergio Lucia. Efficient Representation and Approximation of Model Predictive Control Laws via Deep Learning. *IEEE Transactions on Cybernetics*, 50(9):3866–3878, 2020.
- [19] Elias Khalil, Pierre Le Bodic, Le Song, George Nemhauser, and Bistra Dilkina. Learning to branch in mixed integer programming. In *Proceedings of the AAAI Conference on Artificial Intelligence*, volume 30, 2016.
- [20] James Kotary, Ferdinando Fioretto, and Pascal Van Hentenryck. Fast Approximations for Job Shop Scheduling: A Lagrangian Dual Deep Learning Method. In *Proceedings of the AAAI Conference on Artificial Intelligence*, 2022.
- [21] Pratyush Kumar, James B. Rawlings, and Stephen J. Wright. Industrial, large-scale model predictive control with structured neural networks. *Computers and Chemical Engineering*, 150: 107291, 2021.
- [22] Andrea Lodi and Giulia Zarpellon. On learning and branching: a survey. *Top*, 25(2):207–236, 2017.
- [23] Jayanta Mandi, Emir Demirović, Peter J. Stuckey, and Tias Guns. Smart predict-and-optimize for hard combinatorial optimization problems. In *AAAI 2020 - 34th AAAI Conference on Artificial Intelligence*, pages 1603–1610, 2020.
- [24] Christos T Maravelias. *Chemical Production Scheduling: Mixed-Integer Programming Models and Methods*. Cambridge University Press, 2021.
- [25] Hugues Marchand, Alexander Martin, Robert Weismantel, and Laurence Wolsey. Cutting planes in integer and mixed integer programming. *Discrete Applied Mathematics*, 123(1-3):397–446, 2002.
- [26] Xiang Pan, Tianyu Zhao, and Minghua Chen. DeepOPF: Deep neural network for DC optimal power flow. In *Proceedings of the 2019 IEEE International Conference on Communications, Control, and Computing Technologies for Smart Grids (SmartGridComm)*. IEEE, 2019.
- [27] Joel A. Paulson and Ali Mesbah. Approximate Closed-Loop Robust Model Predictive Control with Guaranteed Stability and Constraint Satisfaction. *IEEE Control Systems Letters*, 4(3): 719–724, 2020.
- [28] Alexander Schrijver. *Theory of linear and integer programming*. John Wiley & Sons, 1998.
- [29] Yunzhuang Shen, Yuan Sun, Andrew Eberhard, and Xiaodong Li. Learning primal heuristics for mixed integer programs. In *2021 international joint conference on neural networks (ijcnn)*, pages 1–8. IEEE, 2021.
- [30] Haoran Sun, Xiangyi Chen, Qingjiang Shi, Mingyi Hong, Xiao Fu, and Nicholas D. Sidiropoulos. Learning to Optimize: Training Deep Neural Networks for Interference Management. *IEEE Transactions on Signal Processing*, 66(20):5438–5453, 2018.
- [31] Reza Takapoui, Nicholas Moehle, Stephen Boyd, and Alberto Bemporad. A simple effective heuristic for embedded mixed-integer quadratic programming. 9 2015.
- [32] Yunhao Tang, Shipra Agrawal, and Yuri Faenza. Reinforcement learning for integer programming: Learning to cut. In *International conference on machine learning*, pages 9367–9376. PMLR, 2020.
- [33] Alexandre Velloso and Pascal Van Hentenryck. Combining Deep Learning and Optimization for Preventive Security-Constrained DC Optimal Power Flow. *IEEE Transactions on Power Systems*, 36(4):3618–3628, 2021.

- [34] Bryan Wilder, Bistra Dilkina, and Milind Tambe. Melding the data-decisions pipeline: Decision-focused learning for combinatorial optimization. In *33rd AAAI Conference on Artificial Intelligence, AAAI 2019, 31st Innovative Applications of Artificial Intelligence Conference, IAAI 2019 and the 9th AAAI Symposium on Educational Advances in Artificial Intelligence, EAAI 2019*, pages 1658–1666, 2019.
- [35] Ahmed S. Zamzam and Kyri Baker. Learning optimal solutions for extremely fast ac optimal power flow. *Proceedings of the 2020 IEEE International Conference on Communications, Control, and Computing Technologies for Smart Grids (SmartGridComm)*, 2020.

A Appendix

A.1 Illustrative example

To illustrate the working of the surrogate LP model, we present a 2-dimensional multi-constraint knapsack problem with one of its constraints changing as a function of the input parameter u :

$$\begin{aligned}
 & \underset{x_1 \in \mathbb{Z}, x_2 \in \mathbb{Z}}{\text{maximize}} && 4.8x_1 + 6x_2 \\
 & \text{subject to} && 4x_1 + 3x_2 \leq 70 \\
 & && 100ux_1 + 85x_2 \leq 800u + 680 \\
 & && x_1 \leq 17, x_2 \leq 17.
 \end{aligned} \tag{7}$$

We obtain an surrogate LP for problem (7) by adding linear inequalities to the original problem whose parameters are trained by solving the DFSM problem (3). The resulting DFSOM is the following LP:

$$\begin{aligned}
 & \underset{x_1 \in \mathbb{R}, x_2 \in \mathbb{R}}{\text{maximize}} && 4.8x_1 + 6x_2 \\
 & \text{subject to} && 4x_1 + 3x_2 \leq 70 \\
 & && 100ux_1 + 85x_2 \leq 800u + 680 \\
 & && (17.9 - 56.9u + 45.1u^2)x_1 + (-4.5 + 25.3u - 14.3u^2)x_2 \leq 100 \\
 & && (7.4 + 6.4u - 7.9u^2)x_1 \leq 100 \\
 & && (-0.2 + 14.5u - 9.4u^2)x_1 + (12 - 9.7u + 3.7u^2)x_2 \leq 100 \\
 & && x_1 \leq 17, x_2 \leq 17.
 \end{aligned} \tag{8}$$

In Figure 7, we show for different values of u the feasible regions of the LP relaxation of problem (7), which we denote as $\tilde{\mathcal{S}}$, in blue. The feasible region of problem (8), denoted by \mathcal{S}' , is shown in green. The integer-feasible points for problem (7) constitute the set \mathcal{S} . From the figure, one can see that the solutions obtained by solving the surrogate LP (8) for different values of u are the same as those obtained by solving the original MILP (7).




Figure 7: Comparison of feasible regions and optimal solutions of (7) and (8). For the three instances of $u = \{1.45; 0.2; 0.61\}$, the corresponding optimal solutions are $x^* = \{(2, 17); (12, 7); (12, 5)\}$.

Note that the added inequalities $\hat{A}(u)x \leq \hat{b}(u)$ may not be valid for all integer-feasible points of the original problem as DFSM only aims to minimize the prediction error with respect to the optimal solutions. Indeed, for the three cases of u -values shown in Figure 7, $\text{conv}(\mathcal{S}) \not\subseteq \mathcal{S}'$ in the first two instances as shown in Figures 7(a) and 7(b).

A.2 The BCD algorithm

To describe the BCD approach, we first re-write the formulation (4) in the following form:

$$\begin{aligned}
& \underset{\theta \in \Theta, \hat{x}, \lambda, \mu}{\text{minimize}} && \sum_{i \in \mathcal{I}} \|x_i^* - \hat{x}_i\|_1 \\
& \text{subject to} && c + A_i'^T d_i' = 0 \quad \forall i \in \mathcal{I} \\
& && A_i' \hat{x}_i - b_i' \leq 0 \quad \forall i \in \mathcal{I} \\
& && D(d_i')(A_i' \hat{x}_i - b_i') = 0 \quad \forall i \in \mathcal{I} \\
& && d_i' \geq 0, \hat{x}_i \in \mathbb{R}^n \quad \forall i \in \mathcal{I} \\
& && A_i' = \begin{bmatrix} A(\bar{u}_i) \\ \hat{A}(\bar{u}_i, \theta) \end{bmatrix}, b_i' = \begin{bmatrix} b(\bar{u}_i) \\ \hat{b}(\bar{u}_i, \theta) \end{bmatrix}, d_i' = \begin{bmatrix} \lambda_i \\ \mu_i \end{bmatrix} \quad \forall i \in \mathcal{I}.
\end{aligned} \tag{9}$$

Problem (9) is a nonconvex NLP which becomes intractable for large instances. Furthermore, some constraints, such as the complementarity constraints, in the problem cause it to violate constraint qualification conditions leading to convergence difficulties for standard NLP solvers.

We address the lack of regularity in (9) by considering its penalty reformulation in (10), which is a standard strategy employed in the NLP literature for degenerate NLPs such as (9):

$$\begin{aligned}
& \underset{\theta \in \Theta, \hat{x}, d'}{\text{minimize}} && \sum_{i \in \mathcal{I}} \|x_i^* - \hat{x}_i\|_1 + q^T \begin{bmatrix} \sum_{i \in \mathcal{I}} \|c + A_i'^T d_i'\|_1 \\ \sum_{i \in \mathcal{I}} \max\{0, A_i' \hat{x}_i - b_i'\} \\ \sum_{i \in \mathcal{I}} \|d_i'^T (A_i' \hat{x}_i - b_i')\|_1 \end{bmatrix} \\
& \text{subject to} && d_i' \geq 0, \hat{x}_i \in \mathbb{R}^n \quad \forall i \in \mathcal{I},
\end{aligned} \tag{10}$$

where we penalize the violation of the constraints using a nonsmooth ℓ_1 -norm-based penalty function. This particular penalty function is known to be exact in the sense that, for values of the penalty parameters q larger than a certain threshold, every optimal solution of (9) also minimizes (10). Therefore, instead of (9), one can solve (10) which is amenable to solution via standard NLP solvers if the description of the set Θ satisfies necessary constraint qualification conditions.

However, the threshold value for q above which the exactness of the penalty reformulation holds is generally hard to determine a priori. Therefore, we employ an iterative approach where we start with small values for q and successively increase them by a factor ρ in every iteration until we arrive at a solution that is feasible for (9) (Algorithm 1).

The reformulated problem (10) is still a nonconvex NLP that is difficult to solve when the number of data points ($|\mathcal{I}|$) is large. We alleviate this issue by observing that (10) is a multiconvex optimization problem if the set Θ is convex. This feature of (10) allows us to solve it via an efficient block-coordinate-descent (BCD) approach. While implementing BCD, we tackle the nonsmoothness of the objective functions of BCD subproblems by augmenting them with the proximal operator.

Algorithm 1 The penalty-based BCD algorithm.

```

initialize  $(\hat{x}, \theta, d')$  with a feasible solution from IPOPT
initialize  $q \leftarrow q^0$ , fix  $\rho \leftarrow \bar{\rho}$ 
while convergence criteria for blocks are not satisfied do
    solve (10) with BCD or IPOPT,
     $q = q + \bar{\rho} \begin{bmatrix} \sum_{i \in \mathcal{I}} \|c + A_i'^T d_i'\|_1 \\ \sum_{i \in \mathcal{I}} \max\{0, A_i' \hat{x}_i - b_i'\} \\ \sum_{i \in \mathcal{I}} \|d_i'^T (A_i' \hat{x}_i - b_i')\|_1 \end{bmatrix}$ 
end while

```

A.3 Design of NN-based optimization proxies

We contrast the performance of the proposed DFSOM approach with NN-based optimization proxies as surrogates for MILPs. To train the NN models, we split the data containing input parameters and optimal solutions into training and test datasets. We use the mean squared error between the true and predicted values as the loss function and apply the ADAM optimizer to estimate the NN parameters. Similar to DFSOM, for a given input, the NN model is also trained to predict an optimal solution for the original problem.

For the NN model, the numbers of hidden layers and neurons in each layer are determined through a trial-and-error approach aiming to minimize the training loss over a fixed number of epochs. The number of hidden layers is based on the empirical observation that increasing the number of hidden layers resulted in little improvements in the model’s accuracy. The design of the specific NN model used in the hybrid vehicle control case study is as follows: the input layer contains T nodes, the same as the dimension of the input vector u . The two hidden layers have $3T$ and $6T$ nodes, and finally, the output layer consists of $3T + 1$ nodes aligning with the dimensionality of the decision space. We also account for the effect of different learning rates (namely 0.1, 0.01, and 0.001) on the training loss. Based on our analysis, we determine 0.01 to be the most suitable learning rate for our purpose.

Given that there are no hard constraints embedded in the NN model, the feasibility of the predicted optimal solutions with respect to the constraints of the original model is not guaranteed. Therefore, we use the same feasibility restoration strategy that is applied to the outputs of DFSOM; a discussion of this strategy is provided in the next section.

A.4 Feasibility restoration

The predicted decisions from the DFSOM may not always satisfy the integrality constraints. For such instances, we employ an inexpensive feasibility restoration strategy to obtain an integer-feasible solution from the predicted solution. Let \hat{x}_i be the optimal solution of the DFSOM for \bar{u}_i . Suppose the discrete decisions associated with \hat{x}_i , denoted by \hat{x}_i^z , are not integer. To restore integer feasibility, we solve the following problem:

$$\begin{aligned} & \underset{x \in \mathbb{R}^m \times \mathbb{Z}^{n-m}}{\text{minimize}} && \|x^z - \hat{x}_i^z\|_1 \\ & \text{subject to} && A(\bar{u}_i)x \leq b(\bar{u}_i). \end{aligned} \quad (11)$$

We then solve the original MILP with the discrete decision variables fixed to the values of the optimal solution to problem (11) to obtain the corresponding optimal values for the continuous variables. Figure 8(a) provides an illustration of an infeasible prediction from the DFSOM. By using the feasibility restoration strategy described above, we obtain the closest integer-feasible point as shown in Figure 8(b).




Figure 8: The predicted decision variables that are not integer-feasible are used in a projection problem to return discrete decision values.

A.5 Additional results

For the hybrid vehicle control problem, Figures 9 and 10 compare the performance of the DFSOM and the NN-based optimization proxy for $T = 10$ and $T = 20$, respectively. The DFSOMs were trained with $|\mathcal{V}| = 2T$. The results indicate DFSOM's superior performance even for these smaller problems, emphasizing the benefit of incorporating original constraints in DFSM. Notably, with only 50 training data points, DFSOM reliably yields solutions with an optimality gap close to zero in both cases.




Figure 9: DFSOM performance compared to NN-based optimization proxy for $T = 10$.




Figure 10: DFSOM performance compared to NN-based optimization proxy for $T = 20$.