

OpenECAD: An Efficient Visual Language Model for Computer-Aided Design

Zhe Yuan^{a,*}, Jianqi Shi^{a,b}, Yanhong Huang^{a,b}

^aSoftware Engineering Institute, East China Normal University, Shanghai, China

^bNational Trusted Embedded Software Engineering Technology Research Center, Shanghai, China

Abstract

Computer-aided design (CAD) tools are utilized in the manufacturing industry for modeling everything from cups to spacecraft. These programs are complex to use and typically require years of training and experience to master. Structured and well-constrained 2D sketches and 3D constructions are crucial components of CAD modeling. A well-executed CAD model can be seamlessly integrated into the manufacturing process, thereby enhancing production efficiency. Deep generative models of 3D shapes and 3D object reconstruction models have garnered significant research interest. However, most of these models are represented in discrete forms. Moreover, the few models based on CAD operations often have substantial input restrictions. In this work, we fine-tuned pre-trained models to create OpenECAD (0.55B, 0.89B, 2.4B, 3.2B and 4.2B), leveraging the visual, logical, coding, and general capabilities of visual language models. OpenECAD can process images of 3D designs as input and generate highly structured 2D sketches and 3D construction commands. These outputs can be directly used with existing CAD tools' APIs to generate project files. To train our network, we created a new CAD dataset. This dataset is based on existing public CAD datasets, with adjustments and augmentations to meet the requirements of VLM training.

Keywords: small language model, visual language model, computer aided design, automated CAD design, 2D-3D shape modeling, geometric deep learning, machine learning

1. Introduction

Using 3D shape representation aligns with human intuition. In today's digital era, computer-aided design (CAD) tools are employed in various industrial fields for 3D shape design, including automotive, aerospace, manufacturing, and architectural design. However, due to drafting conventions and the requirements for shape constraints and edit-ability, 3D shapes are still based on 2D sketches. This approach allows for the meticulous development, relation, and annotation of all design details, mirroring the precision of traditional draftsmen.

A typical 3D part drawing process involves multiple "Sketch-Extrusion" steps. The relationship between sketch and extrusion is not strictly one-to-one; a single sketch can correspond to multiple extrusions, and one extrusion can be composed of multiple sketches. A sketch consists of multiple closed loops formed by several lines and includes constraints within or between them to ensure the sketch is fully defined. The extrusion operation generates a 3D feature based on the 2D sketch(es). Generally, there is a sequential relationship between "Sketch-Extrusion" steps, as a sketch's reference plane may rely on an existing face in the model, and constraints within the Sketch may depend on points or lines already present in the model. As shown in Figure 1, this is a simple process for drawing 3D parts.

There has been extensive research on 3D model generation. However, most of this research focuses on creating

computer-discretized forms of 3D shapes, such as 3D point clouds[1, 2, 3, 4, 5], voxelized shapes[6, 7, 8, 9], polygon meshes[10, 11, 12], and levelset fields[13, 14, 15, 16, 17]. This approach neglects the essence of 3D shape design—the drawing process. In practical applications, the generated models often do not fully meet the requirements, and other steps in the production process may necessitate design modifications. Consequently, modifications to the generated models are frequently needed. However, due to the absence of the drawing process, modifying these models can be less efficient than manually modeling from scratch, making these methods challenging to apply in real-world scenarios.

To address this issue, some studies have emerged with the development of neural networks. Since 3D shapes are still based on 2D sketches, these studies can be divided into 2D sketch generation and 3D CAD model generation. SketchGraphs[18] provides a dataset of constrained 2D sketches, CurveGen and TurtleGen[19] generate closed curve sketches, and CADL[20] uses language models to generate sketches. For 3D model generation, SolidGen[21] and ComplexGen[22] generate B-rep models, while Point2Cyl[23], DeepCAD[24], and Free2CAD[25] generate CAD command sequences. It is worth noting that these models often have significant input limitations. For example, they may require existing 3D point clouds, may not accept inputs to limit how to generate, or require isometric hand-drawn sketches. These constraints significantly differ from existing manual modeling workflows, making it challenging to apply them in production processes.

*Corresponding author.

Email address: yuanzhe1999@outlook.com (Zhe Yuan)




Figure 1: A schematic diagram of the process for drawing 3D parts using CAD tools.

Now, with the development of language models and multimodal language models, these limitations are expected to be overcome. Multimodal language models can flexibly accept various forms of input and understand their meaning, thereby constraining the output. Currently, multimodal language models already have the capability to accept model images and program code and describe their meaning in simple language. For example, GPT-4o can possess simple 3D shape’s generation and has understanding capabilities, and many language models can interpret program code. Therefore, in this work, we leverage the visual, logical, coding, and general capabilities of visual language models to make the following contributions:

1. We established OpenECAD dataset. Based on existing public CAD datasets, such as SketchGraphs[18], Fusion 360 Gallery[26], and DeepCAD[24], we convert these datasets into “image-CAD operation code” pairs, including 2D sketch generation and 3D shape generation. Using currently available multimodal large language models, such as GPT-4o, we generate high-quality annotated datasets. Additionally, we utilize rendering tools to generate various forms of images to enhance the versatility of model inputs.
2. We trained OpenECAD model. Based on existing public small language models and multimodal small language models, such as TinyLLaMA[27], OpenELM[28], Gemma[29], Phi-2, Phi-3-mini[30], and TinyLLaVA[31], we train them using the aforementioned training sets and test their performance in CAD design.
3. We integrated the code generated by OpenECAD into CAD tools. We design a program that can interface with the APIs of various CAD tools, enabling the generated model code to be directly used in CAD applications.

2. Related Work

2.1. Small Language and Visual Language Models

Small language models have recently become very popular due to the growing demand for privacy and local execution. Small language models are those that are smaller in size and require fewer computational resources, allowing them to run on local devices and ensure data privacy and security. Despite their smaller size, these models can still deliver efficient performance on specific tasks, making them suitable for resource-constrained environments. Currently available small language models include Microsoft’s Phi series[30], Apple’s OpenELM[28], Google’s Gemma[29] and TinyLLaMA[27], based on Meta’s LLaMA[32].

Multimodal small language models further expand the applications of small language models. These models can process not only text data but also understand and generate data in various modalities, such as images and audio. By integrating information from multiple modalities, these models excel in a wider range of tasks. For example, they can convert image descriptions into text or transform hand-drawn sketches into structured textual information. Currently available multimodal small language models include the TinyLLaVA series[31], based on small language models above, and Microsoft’s Phi3 Vision[30].

2.2. Generative models of 3D shapes’ CAD commands

Currently, there are several models designed for generating CAD commands for 2D Sketches or 3D shapes. SketchGraphs[18] provides a dataset of constrained 2D sketches and proposes corresponding generative models. CurveGen and TurtleGen[19] aim to generate usable sketches by producing closed curves, ignoring non-essential constraint solving. CADL[20] focuses on defining sketch operations as structures similar to programming languages, leveraging language models for sketch generation.

For 3D model generation, approaches can be divided into models generating B-rep and those generating CAD commands, depending on the final output. The Boundary representation (B-rep) format is the de-facto shape representation in CAD for modeling solid and sheet objects. B-rep has poorer editability compared to other formats but can accommodate simple model modifications. SolidGen[21] and ComplexGen[22] can both generate B-rep models. Models generating CAD commands can directly output CAD command sequences. Point2Cyl[23] can convert cylindrical 3D point clouds into CAD command sequences. DeepCAD[24] provides a dataset of CAD command sequences and proposes a model capable of generating sequences randomly. Free2CAD[25] can convert hand-drawn isometric sketches into CAD command sequences.

As these are traditional small models, they have significant input and output limitations, making integration with existing manual modeling workflows challenging. However, they offer high-quality and structurally complete datasets, which provide a foundation for generating training data for multimodal small language models. To our knowledge, there are currently no multimodal small language models specifically trained for generating CAD commands for 3D shapes.




Figure 2: Overview of the OpenECAD Dataset and Model.

3. Method overview

We now present our OpenECAD dataset and model, which includes a new CAD command sequence format designed for language models (see Figure 2). The dataset has been improved based on existing CAD datasets and utilizes large language models to generate high-quality natural language descriptions of CAD models. We fine-tune pre-trained vision-language models based on small language models, resulting in the OpenECAD models that are compact in size and capable of running locally, specifically designed for CAD applications.

4. Generation of Datasets

In this chapter, we encompass several key components essential for OpenECAD datasets. We cover the design and generation of datasets (Section 4.1), the definition of the code format for CAD operation sequences (Section 4.2), and the translation of these sequences (Section 4.3). Additionally, we address the generation of natural language descriptions for CAD models (Section 4.4), the production of CAD model view images (Section 4.5), and the overall creation of the CAD dataset (Section 4.6).

4.1. Design and Generation of Datasets

CAD models can be represented in various ways. At the user interaction level with CAD software, 3D shapes are described by a series of CAD operations to create solid forms. For instance, to model a simple table, a user begins by sketching on a 2D plane, drawing a rectangle (a closed curve) and constraining its dimensions. After completing the sketch, the user extrudes it to form the tabletop and constrains its thickness. Next, the user sketches on the existing model, drawing four squares (four

closed curves) and constraining their dimensions. After completing this sketch, the user extrudes these shapes to form the table legs, merging them with the previous model and constraining their height. This completes the modeling of a simple table (see Figure 3). This process constitutes a CAD operation sequence, consisting of two Sketch-Extrusion pairs. Clearly, this CAD operation sequence can be described in natural language, as demonstrated above. Additionally, the 2D view of a CAD model is the most intuitive way to express it to humans, akin to the flowchart mentioned above.

In this work, we aim to generate CAD operation sequences using visual language models. CAD operation sequences not only interact with CAD software but also have meanings understandable by humans, allowing modifications and applications in other design processes. To constrain the generation of CAD operation sequences, we use human-understandable inputs such as model images or textual descriptions. Therefore, our dataset includes pairs of target model images as input with CAD operation codes and descriptions as output, pairs of target models as input with CAD operation codes as output, and pairs of target model images and descriptions as input with CAD operation codes as output. These datasets encompass both 3D CAD models and pure 2D sketches to enhance the model’s ability to generate and constrain 2D sketches.

4.2. Definition of the Code Format for CAD Operation Sequences

Mature CAD tools support a rich set of commands, most of which are simplified calls to collections of basic commands—for example, a rectangle is a collection of four line segments and some constraints. However, in practice, only a small subset of these commands is widely used. Therefore, we currently consider only the most basic and commonly used




Figure 3: A CAD Command Sequence Diagram for Drawing a Table.

Command Name	Parameters
Curves Series	
<code>add_line</code>	<code>start_point, end_point</code>
<code>add_arc</code>	<code>start_point, end_point, mid_point</code>
<code>add_circle</code>	<code>center_point, radius</code>
Sketch and its helper	
<code>add_sketchplane</code>	<code>origin_point, x_axis, y_axis</code>
<code>add_profile</code>	<code>loops_list</code>
<code>add_sketch</code>	<code>sketchplane, profile</code>
Extrusion	
<code>add_extrude</code>	<code>sketch, operation, type, extent_size</code>

Table 1: CAD commands and their parameters.

commands in our dataset (see Table 1). Due to the versatility of language models, extending the dataset later is relatively easy.

Sketch. Sketch is the core of CAD operations. Extrusion is built upon Sketch. Curves and constraints form closed loops within a Sketch. Multiple closed loops make up the profile of a closed region. In our representation, the definition of Sketch begins with defining the sketch reference plane, similar to most CAD tools. We then maintain a list of loops and start drawing curves and adding constraints. Once a loop is completed, it is stored in the list. After all loops are completed, the corresponding profile is generated, and finally, the sketch is created based on the reference plane and the profile. The sketch reference plane is defined by the three-dimensional coordinates of the origin and the direction of the sketch's XY axes.

Curves. In practice, we consider three types of widely used curve commands: drawing a line, drawing an arc, and drawing a circle. The line is defined by its starting and ending points, the arc is determined by its starting point, ending point, and midpoint, and the circle is specified by its center and radius.

Extrusion. The extrusion command extrudes a sketch from a 2D plane into a 3D body. The extrusion type can be one-sided, symmetric, or two-sided with respect to the sketch plane. The

Algorithm 1 Pseudo Code Example

```

SketchPlane = add_sketchplane(origin, normal, x_axis, y_axis)
Loops and Curves are lists.
Line1 = add_line(start, end)
Line1 is appended to Curves.
...
Loop = add_loop(Curves)
Loop is appended to Loops.
Profile = add_profile(Loops)
Sketch = add_sketch(SketchPlane, profile, position, size)
Extrude = add_extrude(Sketch, operation, type, extent)

```

command also specifies how to merge the newly extruded 3D body with the previously created shape using one of the operations: creating a new body, or joining, cutting, or intersecting with the existing body.

All operation names are chosen to be as meaningful as possible to aid the language model in understanding and using them. With these operation commands, we describe a CAD model as a sequence of executable commands in code. The pseudo code corresponding to a pair of Sketch-Extrusion operations is shown in the Algorithm 1.

4.3. Translation of CAD Operation Sequences

According to the definitions provided in the previous section, we can convert any CAD model covered by the described operations (in Table 1) into a CAD operation sequence as defined by us. However, in practice, different CAD tools or datasets may have slight variations in their definitions of CAD operations (see Figure 4). Therefore, we determine and transform each curve-drawing operation according to its degrees of freedom to match the syntax of the OpenECAD dataset. We have developed scripts to convert other CAD models or datasets into CAD operation sequence codes for training our VLM.




Figure 4: Comparison Diagram of Two Definitions for Line, Arc, and Circle.

4.4. Generation of Natural Language Descriptions for CAD Models

Describing CAD models in natural language is crucial for understanding 3D shapes. Adding these descriptions as annotations to the CAD operation sequence code can help people quickly grasp the meaning of each code segment and swiftly locate and modify the necessary parts. To construct natural language descriptions corresponding to CAD operation sequence codes, we employed existing large language models such as GPT-4o. By using prompts and examples, we added natural language annotations to the existing CAD operation sequence codes. The prompt used was:

“Please add comments to the drawing code below to indicate what shape is drawn by each section of the code. Don’t add comment for every line or arc.”

To prevent the language model from adding annotations to every CAD operation (like drawing lines or arcs), we constrained the model to add annotations by operation units, such as drawing a rectangle, etc.

4.5. Generation of CAD Model View Images

We have introduced how to define and generate CAD model codes and textual descriptions, providing text materials for VLM training. In this section, we will briefly explain how to generate image materials for VLM training, specifically by creating 2D views of CAD models. We first use the PythonOCC[33] tool to write scripts that generate step files (B-Rep format) based on the CAD operation sequence codes. Then, we render the step files using PythonOCC. Finally, we select a direction that forms a random angle with the isometric view direction vector to generate 2D views as image materials.

4.6. Creation of CAD Dataset

Based on the above method, we generated a 3D CAD dataset derived from DeepCAD dataset[24] and Fusion 360 Gallery Reconstruction Dataset[26]. We excluded designs that were generated incorrectly or had overly long CAD command sequences due to the number of tokens that small language models can




Figure 5: The statistical distribution of the number of “Sketch-Extrusion” steps in OpenECAD 3D dataset.

accept is limited, resulting in a total of 130,239 3D designs. The statistical distribution of the number of “Sketch-Extrusion” steps in the 3D dataset is shown in the Figure 5.

5. Training and Fine-tuning Vision Language Models

In this chapter, we introduce the process of obtaining OpenECAD models. We discuss the choice of language models and multimodal approach (Section 5.1), as well as the fine-tuning of a pre-trained visual language model (Section 5.2).

5.1. The choice of language models and multimodal approach

Due to the high confidentiality requirements of manufacturing enterprises and the substantial CPU and GPU resources typically occupied by CAD design tools, we chose OpenELM[28] (450M), Gemma[29] (2B), Phi-2 (2.7B) and Phi-3 mini[30] (3.8B) with relatively small parameter sizes as the foundation for our language model. OpenELM is an efficient language model family developed by Apple. It employs a layer-wise scaling strategy to allocate parameters efficiently within each layer of the transformer model. This approach enhances accuracy while maintaining computational efficiency. Gemma is a family of lightweight, text-to-text, decoder-only large language models developed by Google. Phi, developed by Microsoft Research, is another series of advanced small language models (SLMs). This series includes Phi-2 (2.7B), Phi-3-mini (3.8B), Phi-3-small (7B), and Phi-3-medium (14B), each with different parameter sizes. Despite their compact parameter scales, Phi-3 models achieve language understanding and reasoning capabilities comparable to larger models. These models are trained on high-quality data and optimized algorithms. It is worth noting that the context acceptance length for OpenELM (450M) is 2048 tokens. In contrast, Gemma and Phi has a minimum context acceptance length of 3072 tokens, with an option to use a version supporting up to 128k tokens at the cost of some content accuracy.

To endow the language model foundation with multimodal capabilities, we selected OpenAI’s CLIP[34] and Google’s SigLIP [35] as visual encoders for OpenELM (450M), Gemma

OpenECAD 0.55B & 0.89B	
CPU	Intel Core i9-7960X
GPU	Nvidia GeForce GTX 1080 Ti
RAM	DDR4-2666 32 GB
OS	Ubuntu Server 22.04 LTS
OpenECAD 2.4B & 3.1B	
CPU	AMD EPYC 9754 Processor (18 vCPU)
GPU	2 x Nvidia GeForce RTX 4090D
RAM	60 GB
OS	Ubuntu Server 22.04 LTS
OpenECAD 4.2B	
CPU	AMD EPYC 9754 Processor (18 vCPU)
GPU	Nvidia GeForce RTX 4090D
RAM	60 GB
OS	Ubuntu Server 22.04 LTS

Table 2: Development and running environment.

(2B) and Phi-2 (2.7B). These models are trained on large datasets consisting of images paired with corresponding text descriptions, combining visual and textual information to make predictions.

To train the entire model with multimodal conversational abilities, we employed the LLaVA[36] method and its dataset. LLaVA combines a visual encoder and a large language model in an innovative multimodal approach, enabling comprehensive visual and language understanding. LLaVA uses GPT-4 to generate multimodal language-image instruction data. For training the model, we utilized the training framework provided by TinyLLaVA[31].

For Phi-3 mini, since Microsoft has already released its multimodal version, Phi-3 Vision (4.2B), which was trained using methods similar to LLaVA, we will directly use the pre-trained model provided by Microsoft.

5.2. Fine-tuning on a pre-trained visual language model

To enable the general visual-language model to generate CAD code, we fine-tuned it using the LoRA[37] method on the pre-trained OpenELM-CLIP, OpenELM-SigLIP, Gemma-SigLIP and Phi-2-SigLIP models. LoRA stands for Low-Rank Adaptation of Large Language Models. In the field of natural language processing (NLP), there is a common paradigm that involves large-scale pre-training on general domain data followed by adaptation to specific tasks or domains. However, as we pre-train larger models, fully fine-tuning all model parameters becomes less feasible due to computational costs. LoRA proposes a novel approach. Instead of full fine-tuning, LoRA freezes the pre-trained model weights and injects trainable rank decomposition matrices into each layer of the Transformer architecture. This significantly reduces the number of trainable parameters for downstream tasks.

We performed LoRA fine-tuning on the pre-trained OpenELM-CLIP (0.55B) and OpenELM-SigLIP (0.89B) models using an Nvidia GeForce GTX 1080 Ti (11 GB VRAM). The Rank and Alpha for LoRA were set to 128 and 256, respectively. The learning rate is 10^{-4} . Training for one epoch with




Figure 6: The loss curves for the OpenECAD 0.55B, 0.89B, 2.4B, 3.2B and 4.2B models during training.

our 3D dataset took approximately 60 hours. Through fine-tuning, we obtained the OpenECAD 0.55B and 0.89B models.

Similarly, we used 2 Nvidia GeForce RTX 4090 D (24 GB VRAM) to perform LoRA fine-tuning on the Gemma-SigLIP (2.4B) and Phi-2-SigLIP (3.1B) model. The Rank and Alpha for LoRA were set to 128 and 256, respectively. The learning rate is 10^{-4} . Training for one epoch with our 3D dataset took approximately 14 hours. Through fine-tuning, we obtained the OpenECAD 2.4B and 3.1B models.

We used an Nvidia GeForce RTX 4090 D (24 GB VRAM) to perform LoRA fine-tuning on the Phi-3 Vision (4.2B) model. The LoRA rank and alpha were set to 256 and 512, respectively. The learning rate is 10^{-4} . Training with our dataset for one epoch took approximately 20 hours. Through fine-tuning, we obtained OpenECAD 4.2B model.

The specific development, training, and runtime environments are shown in the Table 2. The loss curves for the OpenECAD 0.55B, 0.89B, 2.4B, 3.2B and 4.2B models during training are illustrated in the Figure 6. Due to the different batch sizes used during training, the loss curves are proportionally scaled. As shown, the models converge after a single round of fine-tuning.

6. Experiments

In this chapter, we evaluate the ability of OpenECAD models to generate CAD designs based on input images and analyze the results. As there are no existing CAD models that use images for CAD generation, we first define evaluation metrics (Section 6.1) and create CAD designs for testing (Section 6.2). Following this, we test the models, obtain the results (Section 6.3), and analyze them (Section 6.4).

6.1. Evaluation Metrics

For a given 3D shape, there are often multiple methods to create it using CAD tools. Moreover, the input views of the model generally lack dimensional information, meaning the generated model only adheres to the proportional relationships visible in the image. Therefore, directly comparing the generated CAD




Figure 7: Example illustrations of CAD designs for evaluating.

Scoring Item	Score (out of 100)
Is the code executable?	10
Accuracy of 3D shape construction	90
For each Loop-Extrusion pair (out of 100)	
- 2D sketch positioning	20
- Accuracy of 2D Loop	60
- 3D operation	20

Table 3: Scoring Table.

operation sequence codes is not reasonable. To address this, we designed a scoring algorithm and created several test CAD designs (see Figure 7). We used specific views of these designs as input images for evaluation, serving as a metric for assessing the model’s generation capability.

6.1.1. Scoring Algorithm for Evaluating Outputs

To assess the generative capability of our model, we designed a scoring algorithm. First, the algorithm verifies if the generated code can be executed directly by the API operator to create a model. If it cannot run, it scores 0 points. If it can run, we then use a visual language model (such as GPT-4o) to compare the generated model’s view with the target input, evaluating each basic feature. Each basic feature corresponds to a 2D loop. We separately evaluate the loops in the 2D sketches during the modeling process to ensure precise assessment, as these loops may or may not be considered a single sketch during modeling.

We score the results based on executability and the correctness of the 3D shapes (see Table 3). Each Loop-Extrusion pair is considered a basic 3D shape. If the number of generated Loop-Extrusion pairs is insufficient, points will be deducted proportionally. For each Loop-Extrusion pair, we score based on the reference plane position of the 2D sketch, the extrusion operation, and the drawing of the 2D loop. The specific calculation method is shown in the following formula.

$$score = 10R + \frac{90}{N_s} \sum_{i=1}^{N_s} (20P_i + 20O_i + 60L_j) \quad (1)$$

where R denotes executability, N_s represents the number of Loop-Extrusion pairs, P_i and O_i indicate the correctness of the 2D sketch position and 3D extrusion operation for the i -th Sketch-Extrusion pair, and L_j denotes the accuracy of the curves within the loop. $R, P_i, O_i, L_j \in [0, 1]$.

6.2. CAD Designs for Test

To test the model, we require high-quality CAD designs. We extracted approximately 100 3D designs from the training set, maintaining a ratio of 10:5:3:2 for designs containing 1, 2, 3, and 4 or more Sketch-Extrusion pairs, respectively. After filtering and removing duplicates, we obtained 57 unique 3D designs. These designs were redrawn using CAD tools such as AutoDesk Fusion, and appropriate views were selected to generate the input images. Some examples are shown in the Figure 7. The resolution of the images is 640x400.

6.3. Evaluation Results

6.3.1. The Inference Speed of the Models

The input was standardized to a 640x400 image of a 3D shape, with the prompt:

“This image is a view of a 3D model from a certain angle. Please try to use Python-style APIs to render this model.”

For OpenECAD 0.55B and 0.89B, we used an Nvidia GeForce GTX 1080 Ti (11 GB VRAM) for inference, with a peak memory usage of less than 5GB. Getting a 3D shape’s code took approximately 20 seconds. For OpenECAD 2.4B, we used an Nvidia GeForce RTX 4090 D (24 GB VRAM) for inference, with a peak memory usage of less than 9GB. For OpenECAD 3.2B and 4.2B, we used an Nvidia GeForce RTX 4090 D (24 GB VRAM) for inference, with a peak memory usage of less than 18GB. Getting a 3D shape’s code took approximately 45 seconds.

6.3.2. Generating Code and Rendering

We tested OpenECAD versions 0.55B, 0.89B, 2.4B, 3.2B and 4.2B, and also tested GPT-4o. Some successfully rendered test results are illustrated in Figure 8. Since GPT-4o was not trained specifically for the use case described in this paper, we used the following prompt for testing:

“I am going to provide you with a 3D shape’s corresponding Python code for its modeling process. After that, I will input images of other 3D shapes, and please provide the corresponding Python code for them. <OpenECAD style Code Example> This image is a view of a 3D model from a certain angle. Please write the codes of it in the format above.”

During the testing of OpenECAD, the maximum number of new tokens that 0.55B, 0.89B, 3.2B and 4.2B models can generate is 1536, 1024, 2048, 3072 and 3072, respectively. Due to these context limitations, there are instances where the generated code is incomplete. GPT-4o, due to its support for a longer context, did not encounter issues with incomplete code generation.




Figure 8: Comparison of some successful rendered test results illustrations.

Model	Overall Score	Executable	Unfinished	Run with Errors	Completely Correct
0.55B	46.52	36	21	0	15
0.89B	37.19	22	35	0	19
2.4B	59.86	50	7	0	20
3.1B	55.39	53	0	4	16
4.2B	51.91	51	4	2	14
GPT-4o	15.44	52	0	5	4

Table 4: Evaluation Results Table.

Similar to generating datasets, we use the PythonOCC tool to write a library that attempts to directly run the generated code to create CAD projects and output them as STEP files (B-Rep format). Then, we use PythonOCC to render the STEP files to obtain views. Since the generated programs from the model cannot ensure complete accuracy, errors may occur that the API operator cannot handle, leading to model rendering failures.

Based on the scoring method mentioned above, we obtained the scores, the number of executable results, the number of incomplete results, the number of runtime errors, and the number of completely correct results for each model, as shown in the Table 4.

As shown in Table 4, OpenECAD 2.4B achieved the highest overall score and the most fully correct outputs. Both 0.55B and 0.89B models produced a significant amount of incomplete code. The 0.89B model’s higher token consumption for image inputs reduced the number of new tokens it could generate, leading to more incomplete outputs compared to the 0.55B model, and thus a lower overall score. The 3.1B and 4.2B models achieved relatively high scores, but the number of fully correct generations was lower than that of the 0.55B and 0.89B

models. All OpenECAD models demonstrated significant advantages over the unrefined GPT-4o, whose sole advantage was its ability to handle the entire code due to its extended context length.

6.4. Analysis of OpenECAD’s outputs

6.4.1. Code Generation Analysis

For the generated code, the language model effectively adheres to the OpenECAD dataset’s syntax, even without being explicitly instructed on the specific details of the syntax. Regarding the curves in the sketch, the language model successfully ensures that consecutive curves are connected end-to-end, with the first and last curves also joined, thus maintaining closure. Additionally, the language model adeptly manages the positions of points to ensure the profile’s validity. For the fully generated code, the vast majority can be executed and rendered directly. For generated code with runtime errors, this includes both execution crashes and issues where the B-Rep file fails to render correctly.




Figure 9: Typical errors in generated results.

6.4.2. Generation Error Analysis

In the generated results, several typical errors were observed (see Figure 9), including:

- **Case 1 and Case 2:** For complex and irregular shapes, the corresponding sketches often fail to generate correctly, or the profiles of the 2D sketches are inaccurately created. Possible reasons include the vision tower's low resolution, which hinders accurate recognition of complex shapes, and the language model's inability to comprehend complex shapes from the CAD operation code. These issues ultimately result in incorrect loops or intersecting loops, leading to erroneous sketch profiles and broken extrusions.
- **Case 3 and Case 7:** The model lacks spatial reasoning capabilities, resulting in incorrect handling of the size proportions between sketches and extrusions. This leads to extrusions that are either too long or too small, causing discrepancies in size relative to other parts.
- **Case 4:** When multiple "Sketch-Extrusion" steps are involved, the positions of the sketches in subsequent steps are often incorrect, leading to errors in the final overall model.
- **Case 5:** Due to the minimal color difference between the outer surface of a solid cylinder and the inner wall of a

hollow cylinder, the primary distinguishing feature is the inner wall circle at the top. This makes it difficult for the model to differentiate between solid and hollow cylinders, leading to confusion. This issue also extends to other similar shapes with holes.

- **Case 6:** The difficulty in distinguishing concave and convex shapes results in erroneous models. This issue may arise because the vision tower can detect these shapes but cannot differentiate between them, or because the language model fails to generate the correct code, leading to sketch errors.
- **Case 8:** Missing part(s). For some relatively subtle features, the model struggles to accurately identify them, resulting in missing features.

Based on the above results and typical errors, we can infer the current shortcomings of the OpenECAD model:

- The model has weak handling capabilities for complex sketches. This includes issues such as the vision tower's low resolution, which leads to an inability to recognize shapes, and the language model's failure to correctly process complex shapes, resulting in erroneous sketch generation.

- The generated models have poor size accuracy, particularly in handling the proportions between sketch dimensions and extrusion sizes. This results in mismatched parts, as the model fails to ensure consistent sizes between the sketches and extrusions of different components.
- For complex shapes involving multiple "Sketch-Extrusion" steps, the model struggles to generate accurate results. It has difficulty remembering the previously drawn parts through the context, leading to errors.
- Due to the current work focusing only on basic instructions without a combined instruction set like drawing rectangles in one command, the CAD operation codes for 3D shapes tend to be lengthy. Moreover, due to contextual limitations of the model, especially with OpenECAD 0.55B and 0.89B using OpenELM which supports only 2048 tokens, and considering that image inputs also consume tokens, there are situations where the code cannot be completed.

6.5. Future Work

6.5.1. Refinement

Based on the above analysis, our future work will focus on the following areas:

- **Enhancing the dataset** involves several key strategies: expanding support for additional CAD instructions, annotating critical shape dimensions in input images to aid accurate size-based shape drawing by the model, selecting optimal angles for input images to showcase all features comprehensively, and employing diverse rendering tools to enhance the model's ability to recognize shapes under varied lighting conditions and artistic styles.
- **Improving the visual model** is crucial as the current resolution limits its ability to distinguish between certain shapes. Therefore, training a visual model capable of handling higher resolutions is necessary. Additionally, integrating an image segmentation module like FastSAM[38] before the visual model can aid in identifying which parts compose the 3D shapes.
- **Improving the language model's** capabilities is essential, as the current model supports a limited context length and has weak code generation abilities, resulting in incomplete or erroneous code. We can address this by using larger language models that support longer contexts, such as Phi-3-medium or LLaMA-3. Additionally, implementing Retrieval-Augmented Generation (RAG) [39] and prompting techniques can further enhance the model's contextual understanding and code generation capabilities.
- **Enhancing feedback integration with CAD tools.** By adopting a conversational approach, partly generated CAD instructions can be promptly sent to the CAD tool for rendering. The rendering results can then be immediately returned to the model, helping it understand the current drawing status, identify potential errors, correct them, and

Command Name	Parameters
Constraints Series	
make_horizontal(vertical)	line0
fix_size	curve0, size
make_coincident	point0, point1
make_parallel	line0, line1
make_perpendicular	line0, line1
make_tangent	curve0, curve1
make_mirror	curve0, curve1 (same type)
make_angle	line0, line1, clockwise

Table 5: CAD commands and their parameters.




Figure 10: The statistical distribution of the number of curves and constraints operations in OpenECAD 2D dataset.

continue generating code based on the target shape and the already rendered results.

At the same time, we have added a Constraints section to the dataset. We consider nine types of widely used constraint commands (see Table 5): making a line horizontal or vertical, fixing the size of a curve, making two points of curves coincident, making two lines parallel, perpendicular, or at a fixed angle, and making two curves tangent or mirrored. These constraints reduce the degrees of freedom in the sketch. A sketch with exactly zero degrees of freedom is fully defined, while one with fewer than zero degrees of freedom is over-constrained. We generated a 2D CAD dataset derived from the SketchGraphs dataset[18], resulting in a total of 628,499 2D sketches. The statistical distribution of the number of curves and constraints operations in the 2D dataset is shown in the Figure 10.

6.5.2. Applications

Currently, OpenECAD primarily serves as a simple CAD operation generation model, focusing on generating models from images. However, by improving the dataset, we can train models using similar methods and apply them to downstream applications (like Figure 11). These applications include, but are not limited to:

- Assisting users in operating CAD design tools by guiding them on how to proceed with CAD operations to build or




Figure 11: An example of a real-world application of the model.

modify models based on their requirements and existing CAD actions.

- Enhancing the ability to handle user CAD needs, such as design reusability and designing connectors for existing parts.
- Introducing CAE-related knowledge to the model to address some CAE issues, such as structural reinforcement, material reduction, and kinematic simulation, during the CAD phase.

7. Discussion and Conclusion

For CAD model generation, our approach has some limitations. Currently, we only consider three of the most widely used curve command types (lines, arcs, and circles), but other curve commands can be easily added. We also only consider using a single image as a reference, with the model attempting to generate the complete output result rather than step-by-step outputs. Not every CAD command sequence code currently generates a topologically valid shape. Our network cannot guarantee the correctness of its output. In practice, when the context length is sufficient, the number of execution failures in the generated CAD command sequence code is relatively low. However, when the context length is insufficient, it becomes challenging to generate the code completely.

To address these limitations, more work needs to be done. Enhancements to the dataset should include support for multi-view perspectives, complex curves, and textual requirements. The code generation process should be improved to better integrate with CAD tools, allowing the model to generate code incrementally, similar to how humans draw while referencing the design, rather than outputting the entire CAD code at once.

In summary, we have introduced OpenECAD, a visual language model and its accompanying dataset designed for generating CAD operation sequence codes. OpenECAD aims to address the challenge of CAD model generation using visual language models and has successfully generated some relatively simple 3D shapes. We offer 5 sizes of OpenECAD models, ranging from 0.55B to 4.2B parameters.

CRedit authorship contribution statement

Zhe Yuan: Software, Writing – original draft, Writing – review & editing, Project administration. **Jianqi Shi:** Writing – review & editing, Supervision. **Yanhong Huang:** Supervision.

Declaration of competing interest

The authors declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Data availability

Data will be made available on request.

Declaration of generative AI and AI-assisted technologies in the writing process

During the preparation of this work the author(s) used ChatGPT in order to correct the possible wrong expression in English. After using this tool/service, the author(s) reviewed and edited the content as needed and take(s) full responsibility for the content of the published article.

Acknowledgment

This research did not receive any specific grant from funding agencies in the public, commercial, or not-for-profit sectors.

References

- [1] P. Achlioptas, O. Diamanti, I. Mitliagkas, L. Guibas, Learning representations and generative models for 3d point clouds, in: International conference on machine learning, PMLR, 2018, pp. 40–49.
- [2] Y. Yang, C. Feng, Y. Shen, D. Tian, Foldingnet: Point cloud auto-encoder via deep grid deformation, in: Proceedings of the IEEE conference on computer vision and pattern recognition, 2018, pp. 206–215.
- [3] K. Mo, P. Guerrero, L. Yi, H. Su, P. Wonka, N. Mitra, L. J. Guibas, StructureNet: Hierarchical graph networks for 3d shape generation, arXiv preprint arXiv:1908.00575 (2019).
- [4] G. Yang, X. Huang, Z. Hao, M.-Y. Liu, S. Belongie, B. Hariharan, Pointflow: 3d point cloud generation with continuous normalizing flows, in: Proceedings of the IEEE/CVF international conference on computer vision, 2019, pp. 4541–4550.
- [5] R. Cai, G. Yang, H. Averbuch-Elor, Z. Hao, S. Belongie, N. Snavely, B. Hariharan, Learning gradient fields for shape generation, in: Computer Vision–ECCV 2020: 16th European Conference, Glasgow, UK, August 23–28, 2020, Proceedings, Part III 16, Springer, 2020, pp. 364–381.
- [6] R. Girdhar, D. F. Fouhey, M. Rodriguez, A. Gupta, Learning a predictable and generative vector representation for objects, in: Computer Vision–ECCV 2016: 14th European Conference, Amsterdam, The Netherlands, October 11–14, 2016, Proceedings, Part VI 14, Springer, 2016, pp. 484–499.
- [7] J. Wu, C. Zhang, T. Xue, B. Freeman, J. Tenenbaum, Learning a probabilistic latent space of object shapes via 3d generative-adversarial modeling, *Advances in neural information processing systems* 29 (2016).
- [8] J. Li, K. Xu, S. Chaudhuri, E. Yumer, H. Zhang, L. Guibas, Grass: Generative recursive autoencoders for shape structures, *ACM Transactions on Graphics (TOG)* 36 (4) (2017) 1–14.
- [9] Y. Liao, S. Donne, A. Geiger, Deep marching cubes: Learning explicit surface representations, in: Proceedings of the IEEE Conference on Computer Vision and Pattern Recognition, 2018, pp. 2916–2925.
- [10] T. Groueix, M. Fisher, V. G. Kim, B. C. Russell, M. Aubry, A papier-mâché approach to learning 3d surface generation, in: Proceedings of the IEEE conference on computer vision and pattern recognition, 2018, pp. 216–224.
- [11] N. Wang, Y. Zhang, Z. Li, Y. Fu, W. Liu, Y.-G. Jiang, Pixel2mesh: Generating 3d mesh models from single rgb images, in: Proceedings of the European conference on computer vision (ECCV), 2018, pp. 52–67.

- [12] C. Nash, Y. Ganin, S. A. Eslami, P. Battaglia, Polygen: An autoregressive generative model of 3d meshes, in: International conference on machine learning, PMLR, 2020, pp. 7220–7229.
- [13] Z. Chen, H. Zhang, Learning implicit fields for generative shape modeling, in: Proceedings of the IEEE/CVF conference on computer vision and pattern recognition, 2019, pp. 5939–5948.
- [14] L. Mescheder, M. Oechsle, M. Niemeyer, S. Nowozin, A. Geiger, Occupancy networks: Learning 3d reconstruction in function space, in: Proceedings of the IEEE/CVF conference on computer vision and pattern recognition, 2019, pp. 4460–4470.
- [15] J. J. Park, P. Florence, J. Straub, R. Newcombe, S. Lovegrove, DeepSDF: Learning continuous signed distance functions for shape representation, in: Proceedings of the IEEE/CVF conference on computer vision and pattern recognition, 2019, pp. 165–174.
- [16] Z. Chen, A. Tagliasacchi, H. Zhang, Bsp-net: Generating compact meshes via binary space partitioning, in: Proceedings of the IEEE/CVF conference on computer vision and pattern recognition, 2020, pp. 45–54.
- [17] R. Wu, Y. Zhuang, K. Xu, H. Zhang, B. Chen, Pq-net: A generative part seq2seq network for 3d shapes, in: Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition, 2020, pp. 829–838.
- [18] A. Seff, Y. Ovadia, W. Zhou, R. P. Adams, Sketchgraphs: A large-scale dataset for modeling relational geometry in computer-aided design, arXiv preprint arXiv:2007.08506 (2020).
- [19] K. D. Willis, P. K. Jayaraman, J. G. Lambourne, H. Chu, Y. Pu, Engineering sketch generation for computer-aided design, in: Proceedings of the IEEE/CVF conference on computer vision and pattern recognition, 2021, pp. 2105–2114.
- [20] Y. Ganin, S. Bartunov, Y. Li, E. Keller, S. Saliceti, Computer-aided design as language, Advances in Neural Information Processing Systems 34 (2021) 5885–5897.
- [21] P. K. Jayaraman, J. G. Lambourne, N. Desai, K. D. Willis, A. Sanghi, N. J. Morris, Solidgen: An autoregressive model for direct b-rep synthesis, arXiv preprint arXiv:2203.13944 (2022).
- [22] H. Guo, S. Liu, H. Pan, Y. Liu, X. Tong, B. Guo, Complexgen: Cad reconstruction by b-rep chain complex generation, ACM Transactions on Graphics (TOG) 41 (4) (2022) 1–18.
- [23] M. A. Uy, Y.-Y. Chang, M. Sung, P. Goel, J. G. Lambourne, T. Birdal, L. J. Guibas, Point2cyl: Reverse engineering 3d objects from point clouds to extrusion cylinders, in: Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition, 2022, pp. 11850–11860.
- [24] R. Wu, C. Xiao, C. Zheng, Deepcad: A deep generative network for computer-aided design models, in: Proceedings of the IEEE/CVF International Conference on Computer Vision, 2021, pp. 6772–6782.
- [25] C. Li, H. Pan, A. Bousseau, N. J. Mitra, Free2cad: Parsing freehand drawings into cad commands, ACM Transactions on Graphics (TOG) 41 (4) (2022) 1–16.
- [26] K. D. D. Willis, Y. Pu, J. Luo, H. Chu, T. Du, J. G. Lambourne, A. Solar-Lezama, W. Matusik, Fusion 360 gallery: A dataset and environment for programmatic cad construction from human design sequences, ACM Transactions on Graphics (TOG) 40 (4) (2021).
- [27] P. Zhang, G. Zeng, T. Wang, W. Lu, Tinyllama: An open-source small language model (2024). arXiv:2401.02385.
- [28] S. Mehta, M. H. Sekhvat, Q. Cao, M. Horton, Y. Jin, C. Sun, I. Mirzadeh, M. Najibi, D. Belenko, P. Zatloukal, M. Rastegari, OpenELM: An Efficient Language Model Family with Open Training and Inference Framework, arXiv.org (Apr. 2024). URL <https://arxiv.org/abs/2404.14619v1>
- [29] G. Team, T. Mesnard, C. Hardin, R. Dadashi, S. Bhupatiraju, S. Pathak, L. Sifre, M. Rivière, M. S. Kale, J. Love, et al., Gemma: Open models based on gemini research and technology, arXiv preprint arXiv:2403.08295 (2024).
- [30] M. Abdin, S. A. Jacobs, A. A. Awan, J. Aneja, A. Awadallah, H. Awadalla, N. Bach, A. Bahree, A. Bakhtiari, H. Behl, et al., Phi-3 technical report: A highly capable language model locally on your phone, arXiv preprint arXiv:2404.14219 (2024).
- [31] B. Zhou, Y. Hu, X. Weng, J. Jia, J. Luo, X. Liu, J. Wu, L. Huang, Tinyllava: A framework of small-scale large multimodal models (2024). arXiv:2402.14289.
- [32] H. Touvron, T. Lavril, G. Izacard, X. Martinet, M.-A. Lachaux, T. Lacroix, B. Rozière, N. Goyal, E. Hambro, F. Azhar, A. Rodriguez, A. Joulin, E. Grave, G. Lample, Llama: Open and efficient foundation language models (2023). arXiv:2302.13971.
- [33] T. Pavot, pythonocc (Dec. 2022). doi:10.5281/zenodo.7471333. URL <https://doi.org/10.5281/zenodo.7471333>
- [34] A. Radford, J. W. Kim, C. Hallacy, A. Ramesh, G. Goh, S. Agarwal, G. Sastry, A. Askell, P. Mishkin, J. Clark, et al., Learning transferable visual models from natural language supervision, in: International conference on machine learning, PMLR, 2021, pp. 8748–8763.
- [35] X. Zhai, B. Mustafa, A. Kolesnikov, L. Beyer, Sigmoid loss for language image pre-training, in: Proceedings of the IEEE/CVF International Conference on Computer Vision, 2023, pp. 11975–11986.
- [36] H. Liu, C. Li, Q. Wu, Y. J. Lee, Visual instruction tuning, Advances in neural information processing systems 36 (2024).
- [37] E. J. Hu, Y. Shen, P. Wallis, Z. Allen-Zhu, Y. Li, S. Wang, L. Wang, W. Chen, Lora: Low-rank adaptation of large language models, arXiv preprint arXiv:2106.09685 (2021).
- [38] X. Zhao, W. Ding, Y. An, Y. Du, T. Yu, M. Li, M. Tang, J. Wang, Fast segment anything, arXiv preprint arXiv:2306.12156 (2023).
- [39] Y. Gao, Y. Xiong, X. Gao, K. Jia, J. Pan, Y. Bi, Y. Dai, J. Sun, H. Wang, Retrieval-augmented generation for large language models: A survey, arXiv preprint arXiv:2312.10997 (2023).