

---

# Not All Prompts Are Made Equal: Prompt-based Pruning of Text-to-Image Diffusion Models

---

**Alireza Ganjdanesh** \*  
University of Maryland

**Reza Shirkavand** \*  
University of Maryland

**Shangqian Gao**  
Florida State University

**Heng Huang**  
University of Maryland

## Abstract

Text-to-image (T2I) diffusion models have demonstrated impressive image generation capabilities. Still, their computational intensity prohibits resource-constrained organizations from deploying T2I models after fine-tuning them on their internal *target* data. While pruning techniques offer a potential solution to reduce the computational burden of T2I models, static pruning methods use the same pruned model for all input prompts, overlooking the varying capacity requirements of different prompts. Dynamic pruning addresses this issue by utilizing a separate sub-network for each prompt, but it prevents batch parallelism on GPUs. To overcome these limitations, we introduce Adaptive Prompt-Tailored Pruning (APTP), a novel prompt-based pruning method designed for T2I diffusion models. Central to our approach is a *prompt router* model, which learns to determine the required capacity for an input text prompt and routes it to an architecture code, given a total desired compute budget for prompts. Each architecture code represents a specialized model tailored to the prompts assigned to it, and the number of codes is a hyperparameter. We train the prompt router and architecture codes using contrastive learning, ensuring that similar prompts are mapped to nearby codes. Further, we employ optimal transport to prevent the codes from collapsing into a single one. We demonstrate APTP’s effectiveness by pruning Stable Diffusion (SD) V2.1 using CC3M and COCO as *target* datasets. APTP outperforms the single-model pruning baselines in terms of FID, CLIP, and CMMD scores. Our analysis of the clusters learned by APTP reveals they are semantically meaningful. We also show that APTP can automatically discover previously empirically found challenging prompts for SD, *e.g.*, prompts for generating text images, assigning them to higher capacity codes. Code is available here.

## 1 Introduction

In recent years, diffusion models [25, 62, 64, 65] have revolutionized generative modeling. For instance, modern Text-to-Image (T2I) diffusion models [1, 3, 48] like Stable Diffusion [53, 56] have achieved remarkable success in generating realistic images [49, 54, 58] and editing them [20, 30, 81]. Consequently, their integration into various applications is of great interest. However, the sampling process of T2I diffusion models is slow and computationally intensive, making them expensive to deploy on GPU clouds for a large number of users and preventing their utilization on edge devices. Thus, reducing the computational cost of T2I models is essential prior to serving them.

---

\* Authors Contributed Equally. Correspondence to [aliganj](mailto:aliganj@umd.edu), [rezashkv@cs.umd.edu](mailto:rezashkv@cs.umd.edu)




Figure 1: **Overview:** We prune a text-to-image diffusion model like Stable Diffusion (left) into a mixture of efficient experts (right) in a prompt-based manner. Our prompt router *routes* distinct types of prompts to different experts, allowing experts’ architectures to be separately specialized by removing layers or channels.

Two orthogonal factors underlie the sampling cost of T2I diffusion models: their large number of denoising steps and their parameter-heavy backbone architectures. Most acceleration methods for T2I models reduce the computation per sampling step or skip steps using techniques like distillation [14, 47, 59] and improved noise schedules [50, 63]. Other ideas address the second factor and propose efficient architectures for T2I models. Architecture modification methods [29, 83] modify the U-Net [57] of Stable Diffusion (SD) [56] to reduce its parameters and FLOPs while preserving performance. Still, they only provide a few architectural configurations, and generalizing their design choices to new compute budgets or datasets is highly non-trivial. Search-based methods [35, 38] search for an efficient architecture [35] or an efficient mixture [38] of pretrained T2I models in a model zoo. Yet, evaluating each action in the search process and gathering a model zoo of T2I models are both extremely costly, making search methods impractical in resource-constrained scenarios.

The efficient architecture design methods [29, 35, 83] have shown promise, but they aim to develop ‘one-size-fits-all’ architectures for *all* applications. We argue that this approach is misaligned with the common practice for two reasons: 1) Organizations typically fine-tune pretrained T2I models (*e.g.*, SD) on their proprietary *target* data and deploy the resulting model for their specific application. They prioritize performance on their *target* data distribution while meeting their computation budget, and the trade-off between efficiency and performance can vary depending on the complexity of the *target* dataset between organizations. 2) Verifying the validity of each design choice on large-scale datasets used in one-size-fits-all methods is costly and slow to iterate, making them impractical.

Model pruning [7] can reduce a model’s computational burden to any desired budget with significantly less effort than designing [29, 83] or searching [35] for efficient architectures. Still, T2I models have unique characteristics making existing pruning techniques unsuitable for them. Static pruning methods are input-agnostic and use the same pruned model for all inputs, but distinct prompts of T2I models may require different model capacities. Dynamic pruning employs a separate model for each input sample, but it cannot benefit from batch-parallelism in modern hardware like GPUs and TPUs.

In this paper, we introduce Adaptive Prompt-Tailored Pruning (AFTP), a novel prompt-based pruning method for T2I diffusion models. AFTP prunes a T2I model pretrained on a large-scale dataset (*e.g.*, SD) using a smaller *target* dataset given a desired compute budget. It tackles the challenges of static and dynamic pruning methods for T2I models by training a *prompt router* module along with a set of *architecture codes*. The prompt router learns to route an input prompt to an architecture code, determining the sub-architecture, called *expert*, of the T2I model to use. Each expert specializes in generating images for the prompts assigned to it by the prompt router (Fig. 1), and the number of experts is a hyperparameter. We train the prompt router and architecture codes using a contrastive learning objective that regularizes the prompt router to select similar architecture codes for similar prompts. In addition, we employ optimal transport to diversify the architecture codes and the resulting experts’ budgets, allowing deploying them on hardware with varying capabilities. We take CC3M [60] and MS-COCO [37] as the *target* datasets and prune Stable Diffusion V2.1 [56] using AFTP in our experiments. AFTP outperforms the single-model pruning baseline, and we show that our prompt router learns to group the input prompts into semantic clusters. Further, our analysis demonstrates that AFTP can automatically discover challenging prompts for SD, such as prompts for generating text images, found empirically by prior work [6, 77]. We summarize our contributions as follows:

- We introduce AFTP, a novel prompt-based pruning method for T2I diffusion models. It is more suitable than static pruning for T2I models as it is not input-agnostic. In addition, AFTP enables batch parallelism on GPUs, which is not possible with dynamic pruning.

- APTP trains a prompt router and a set of architecture codes. The prompt router maps an input prompt to an architecture code. Each architecture code resembles a pruned sub-architecture expert of the T2I model, specialized in handling certain types of prompts assigned to it.
- We develop a framework to train the prompt router and architecture codes using contrastive learning and employ optimal transport to diversify the architecture codes and their corresponding sub-architectures’ computational requirements, given a desired compute budget.

## 2 Related Work

Several works have addressed improving the architectural efficiency of diffusion models, which is our paper’s primary focus. **Multi-expert** [32, 38, 51, 80] methods employ several models each responsible for an interval of diffusion model’s denoising process. These methods design expert model architectures [32, 80], train several models with varying capacities from scratch [38], or utilize existing pretrained models [38, 51]. However, pretrained experts may not be available, and training several models from scratch, as done by multi-expert methods, is prohibitively expensive. **Architecture Design** [29, 75, 83] approaches redesign the U-Net architecture [57] of diffusion models to enhance its efficiency. MobileDiffusion [83] does so using empirical heuristics derived from performance metrics on MS-COCO [37]. BK-SDM [29] removes some blocks from the SD’s U-Net and applies distillation [23] to train the pruned model. Spectral Diffusion [75] introduces a wavelet gating operation and performs frequency domain distillation. Yet, generalizing heuristics and design choices of the architecture design methods to other tasks and compute budgets is non-trivial. Alternatively, SnapFusion [35] searches for an efficient architecture for T2I models. Yet, evaluating each action in the search process requires 2.5 A100 GPU hours, making it costly in practice. Finally, SPDM [11] estimates the importance of different weights using Taylor expansion and removes the low-scored ones. Despite their promising results, all these methods are ‘static’ in that they obtain an efficient model and utilize it for *all* inputs. This is sub-optimal for T2I models as input prompts may vary in complexity, demanding different model capacity levels. Our method differs from existing approaches by introducing a prompt-based pruning technique for T2I models. It is the first method that allocates computational resources to prompts based on their individual complexities while ensuring optimal utilization and batch-parallelizability. We refer to Appendix A for a detailed review of related work.

## 3 Method

We introduce a framework for prompt-based pruning of T2I diffusion models termed Adaptive Prompt-Tailored Pruning (ATPT). ATPT prunes a T2I model pretrained on large-scale datasets (*e.g.*, Stable Diffusion [56]) using a smaller *target* dataset. This approach mirrors the common practice where organizations fine-tune pretrained T2I models on their internal proprietary data and deploy the resulting model for their customers. The core component of ATPT is a *prompt router* that learns to map an input prompt to an *architecture code* during the pruning process. Each architecture code corresponds to a specialized *expert* model, which is a sub-network of the T2I model. We train the prompt router and architecture codes in an end-to-end manner. After the pruning phase, ATPT fine-tunes each specialized model using samples from the target dataset assigned to it by the prompt router. We elaborate on the components of ATPT in the following subsections.

### 3.1 Background

Given an input text prompt, text-to-image (T2I) diffusion models generate a corresponding image by iteratively denoising a Gaussian noise [25, 62, 64]. They achieve this by training a denoising model,  $\epsilon(\cdot; \theta)$ , parameterized by  $\theta$ . For a given training image-text pair  $(x_0, p) \sim \mathcal{P}$ , T2I models define a forward diffusion process, progressively adding Gaussian noise to the initial image  $x_0$  over  $T$  steps. This process is defined as  $q(x_t|x_0) = \mathcal{N}(x_t; \sqrt{\bar{\alpha}_t}x_0, (1 - \bar{\alpha}_t)I)$ , where  $\bar{\alpha}_t$  is the forward noise schedule parameter, typically chosen such that  $q(x_t|x_0) \rightarrow \mathcal{N}(0, I)$  as  $t \rightarrow T$ . T2I models are trained using the variational evidence lower bound (ELBO) objective [25].




Figure 2: **Our pruning scheme.** We train our prompt router and the set of architecture codes to prune a text-to-image diffusion model into a mixture of experts. The prompt router consists of three modules. We use a Sentence Transformer [55] as our prompt encoder to encode the input prompt into a representation  $z$ . Then, the architecture predictor transforms  $z$  into the architecture embedding  $e$  that has the same dimensionality as architecture codes. Finally, the router routes the embedding  $e$  into an architecture code  $a^{(i)}$ . We use optimal transport to evenly assign the prompts in a training batch to the architecture codes. The architecture code  $a^{(i)} = (u^{(i)}, v^{(i)})$  determines pruning the model’s width and depth. We train the prompt router’s parameters and architecture codes in an end-to-end manner using the denoising objective of the pruned model  $\mathcal{L}_{\text{DDPM}}$ , distillation loss between the pruned and original models  $\mathcal{L}_{\text{distill}}$ , average resource usage for the samples in the batch  $\mathcal{R}$ , and contrastive objective  $\mathcal{L}_{\text{cont}}$ , encouraging embeddings  $e$  preserving semantic similarity of the representations  $z$ .

$$\mathcal{L}_{\text{DDPM}}(\theta) = \mathbb{E}_{\substack{(x_0, p) \sim \mathcal{P} \\ t \sim [1, T] \\ \epsilon \sim \mathcal{N}(0, I) \\ x_t \sim q(x_t | x_0)}} \|\epsilon(x_t, p, t; \theta) - \epsilon\|^2 \quad (1)$$

T2I models sample an image starting from a Gaussian noise  $x_T \sim \mathcal{N}(0, I)$  and denoising it using the trained denoising model. We refer to appendix C for a thorough review of diffusion models.

### 3.2 Prompt Router and Architecture Codes

We employ our prompt router to determine the specialized sub-network of the T2I model to be used for a given input prompt. Specifically, we denote our prompt router with the function  $f_{\text{PR}}(\cdot; \eta, \mathcal{A})$ , parameterized by  $\eta$ , which maps an input prompt  $p$  to an architecture code  $a$ :

$$a = f_{\text{PR}}(p; \eta, \mathcal{A}) \quad (2)$$

We define the set of learnable architecture codes as  $\mathcal{A} = \{a^{(i)}\}_{i=1}^N$ , where  $N$  is a hyperparameter. Also,  $a^{(i)} \in \mathbb{R}^D$ , with  $D$  being the number of prunable width and depth units in the T2I model. Given a desired constraint  $T_d$  on the total compute budget (latency, MACs, etc.) for the prompts in the target dataset, we train the prompt router’s parameters  $\eta$  and architecture codes in  $\mathcal{A}$  to obtain a set of expert models. These experts are specialized, efficient, and performant sub-networks of the T2I model, as determined by the architecture codes. As illustrated in Fig. 2, the prompt router consists of a prompt encoder, an architecture predictor, and a router module. We provide details of these components in the following subsections and present our pruning objective in Eq. 15.

#### 3.2.1 Prompt Encoder and Architecture Predictor

Our primary intuition in designing the prompt router is that it should route semantically similar prompts to similar sub-networks of a T2I model. Accordingly, we use a pretrained frozen Sentence Transformer model [55] as our prompt encoder module. It can effectively encode input prompts  $p$  into semantically meaningful embeddings  $z$ :

$$z = f_{\text{PE}}(p) \quad (3)$$

$f_{\text{PE}}(\cdot)$  is the prompt encoder. We do not explicitly show the prompt encoder’s parameters as we do not train them in our pruning method. The Sentence Transformer can encode semantically similar prompts to nearby embeddings and distant from dissimilar ones. We leverage this property in our framework (Eq. 13) to ensure the prompt router maps similar prompts to similar architecture codes.

The architecture predictor module transforms prompt embeddings  $z$  into architecture embeddings  $e$ :

$$e = f_{\text{AP}}(z; \eta) \quad (4)$$

$\eta$  denotes the parameters of the architecture predictor  $f_{\text{AP}}(\cdot)$ , implemented with a single feed-forward layer (Appendix D.1). The embeddings  $e$  have the same dimensionality as the architecture codes  $a$ .

### 3.2.2 Router

The router module takes an architecture embedding  $e$  and routes it to an architecture code  $a \in \mathcal{A}$ . A straightforward way to implement the router is to map an input embedding  $e$  to its nearest architecture code in  $\mathcal{A}$ . However, we found that this approach may lead to the collapse of architecture codes, as they could converge to a single code that meets the desired compute budget  $T_d$  with a relatively decent performance, causing the prompt router to route all input prompts to it.

To tackle this challenge, we employ optimal transport in our router module during the pruning phase. Formally, let  $E = [e_1, \dots, e_B]$  represent  $B$  architecture embeddings in a training batch, and  $A = [a^{(1)}, \dots, a^{(N)}]$  represent the  $N$  codes. The goal is to find an assignment matrix  $Q = [q_1, \dots, q_B]$  that maximizes the similarity between architecture embeddings and their assigned architecture codes:

$$\max_{Q \in \mathcal{Q}} \text{Tr}(Q^T A^T E) + \epsilon \text{H}(Q) \quad (5)$$

$\text{H}$  is an entropy term  $\text{H}(Q) = -\sum_{i,j} q_{ij} \log(q_{ij})$  and  $\epsilon$  is the regularization strength. It has been shown [5, 79] that high values of  $\epsilon$  lead to a uniform assignment matrix  $Q$ , causing all codes in  $A$  to collapse to a single code. Thus, we set  $\epsilon$  to a small value. Further, we impose an equipartition [79] constraint on  $Q$  so that architecture embeddings in a batch are assigned equally to architecture codes:

$$\mathcal{Q} = \{Q \in \mathbb{R}_+^{N \times B} \mid Q \mathbf{1}_B = \frac{1}{N} \mathbf{1}_N, Q^T \mathbf{1}_N = \frac{1}{B} \mathbf{1}_B\} \quad (6)$$

Here,  $\mathbf{1}_{\{B,N\}}$  are vectors of ones with length  $B$  and  $N$ , respectively. These constraints enforce that, on average,  $\frac{B}{N}$  embeddings are assigned to an architecture code per training batch, thereby ensuring that each architecture code gets enough samples for training. The optimal transport problem in Eq. 5 with the constraints in Eq. 6 can be solved using the fast version [9] of the Sinkhorn-Knopp algorithm and the solution has the normalized exponential matrix form [9]:

$$Q^* = \text{diag}(m) \exp\left(\frac{A^T E}{\epsilon}\right) \text{diag}(n) \quad (7)$$

Here,  $m$  and  $n$  are renormalization vectors that can be calculated using a few iterations of the Sinkhorn-Knopp algorithm. With  $\epsilon$  set to a small value, the matrix  $BQ^*$  will have columns that are close to one-hot vectors, which we use to assign the architecture embeddings to the architecture codes. In summary, the router module’s function during the pruning process is:

$$a = f_{\text{R}}(e, \mathcal{A}; Q^*) \quad (8)$$

After the pruning stage, the trained router simply routes an input architecture embedding to an architecture code with the highest cosine similarity. We provide the definition of  $f_{\text{R}}$  in Appendix D.2.

### 3.3 Pruning

We divide each architecture code  $a^{(i)} \in \mathcal{A}$  into two sub-vectors  $a^{(i)} = (u^{(i)}, v^{(i)})$ . We utilize the vectors  $u^{(i)}$  and  $v^{(i)}$  to prune the depth layers and determine widths of the layers, respectively.

A simple approach to prune the width of a layer (a depth layer) is to use binary vectors  $v^{(i)}$  ( $u^{(i)}$ ), indicating whether the channels (layers) should be pruned. Yet, doing so is not differentiable, and one needs to solve a discrete optimization problem to find the optimal binary vectors. Instead, we employ soft vectors  $\mathbf{v}^{(i)}$  ( $\mathbf{u}^{(i)}$ ) that are continuous and differentiable for pruning. We calculate them as:

$$\mathbf{v}^{(i)} = \text{sigmoid}\left(\frac{v^{(i)} + g_v}{\gamma}\right), \quad \mathbf{u}^{(i)} = \text{sigmoid}\left(\frac{u^{(i)} + g_u}{\gamma}\right) \quad (9)$$

$g_{\{u,v\}} \sim \text{Gumbel}(0, 1)$  represents a noise vector sampled from the Gumbel distribution [13], and  $\gamma$  is the temperature. This formulation, known as the Gumbel-sigmoid reparameterization [27, 46], is a differentiable approximation of sampling from Bernoulli distributions with parameters  $\text{sigmoid}(v^{(i)})$  and  $\text{sigmoid}(u^{(i)})$ . When the temperature  $\gamma$  is set appropriately, the vectors  $\mathbf{v}^{(i)}$  and  $\mathbf{u}^{(i)}$  will be close to binary vectors, and we use them for pruning the layers' width and depth layers. Assuming  $\mathbf{v}^{(i)} = [\mathbf{v}_l^{(i)}]_{l=1}^L$  where  $L$  is the number of the model's layers, we prune the width of the  $l$ -th layer as:

$$\widehat{\mathcal{F}}_l = \mathcal{F}_l \odot \mathbf{v}_l^{(i)} \quad (10)$$

In this equation,  $\mathcal{F}_l$  represents feature maps of the  $l$ -th layer, and  $\odot$  is the element-wise multiplication. We prune the channels of the convolution layers in the ResBlocks [16], attention heads in the Transformer layers [69], and the channels of the feed-forward layers in the Transformer layers.

In a similar manner, we apply the vectors  $\mathbf{u}^{(i)} = [\mathbf{u}_j^{(i)}]_{j=1}^M$  (where  $M$  is the number of depth layers that we prune) for pruning the model's depth. Specifically, we prune the  $j$ -th depth layer  $f_j$  as:

$$\widehat{\mathcal{F}}_j = \mathbf{u}_j^{(i)} f_j(\mathcal{F}_{j-1}) + (1 - \mathbf{u}_j^{(i)}) \mathcal{F}_{j-1} \quad (11)$$

$\mathcal{F}_{j-1}$  denotes the previous layer's feature maps. The granularity of our depth pruning is a ResBlock or a Transformer layer in the U-Net of the T2I model. We provide more details in Appendix D.3. In summary, we employ the architecture vectors  $\mathbf{a}^{(i)} = (\mathbf{v}^{(i)}, \mathbf{u}^{(i)})$  to prune the T2I model.

#### 3.3.1 Training the Prompt Router and Architecture Codes

We jointly train the prompt router and architecture codes in an end-to-end manner, guiding the prompt router to map similar prompts to similar architecture codes. In addition, we regularize the architecture codes to correspond to performant sub-networks of the T2I model, be diverse, and adhere to the desired compute budget  $T_d$  on aggregate.

**Contrastive Training** Given a training batch with  $B$  prompts, we compute their prompt embeddings  $z$  (Eq. 3) and architecture embeddings  $e$  (Eq. 4). Then, we calculate architecture vectors  $\mathbf{e}'$ :

$$\mathbf{e}' = \text{sigmoid}\left(\frac{e + g}{\gamma}\right) \quad (12)$$

where  $\gamma$  and  $g$  have the same definitions as Eq. 9. We define the cosine similarity of two vectors as  $\text{sim}(\mathbf{m}, \mathbf{n}) = \mathbf{m}^T \mathbf{n} / (\|\mathbf{m}\| \cdot \|\mathbf{n}\|)$ , and we use the following objective to train the architecture predictor:

$$\mathcal{L}_{\text{cont}}(\eta) = \frac{1}{B^2} \sum_{i=1}^B \sum_{j=1}^B r_{i,j} \log(s_{i,j}) + (1 - r_{i,j}) \log(1 - s_{i,j}) \quad (13)$$

$$r_{i,j} = \frac{\exp(\text{sim}(z_i, z_j)/\tau)}{\sum_{k=1}^B \exp(\text{sim}(z_i, z_k)/\tau)}, \quad s_{i,j} = \frac{\exp(\text{sim}(\mathbf{e}'_i, \mathbf{e}'_j)/\tau)}{\sum_{k=1}^B \exp(\text{sim}(\mathbf{e}'_i, \mathbf{e}'_k)/\tau)} \quad (14)$$

$\tau$  is a temperature parameter. Eq. 13 regularizes the architecture predictor to map representations  $z$  to the regions of the space of the architecture embeddings  $e$  such that their corresponding architecture vectors  $\mathbf{e}'$  maintain the similarity between the prompts. Note that we do not actually use the architecture vectors  $\mathbf{e}'$  to prune the model (Sec. 3.2.2, 3.3). Yet, we apply our contrastive regularization to the vectors  $\mathbf{e}'$  instead of embeddings  $e$ . This design choice is a result of our observation that applying  $\mathcal{L}_{\text{cont}}$  to embeddings  $e$  may not lead to diverse architecture vectors  $\mathbf{a}^{(i)} = (\mathbf{v}^{(i)}, \mathbf{u}^{(i)})$  that we use for pruning (Sec. 3.3). For instance, embeddings  $e$  (and their nearby architecture codes  $a$ ) can be distributed in the embedding space (before Gumbel-Sigmoid estimation), but all be in saturation regions of the sigmoid function (Eqs. 9, 12), resulting in similar architecture vectors  $\mathbf{e}'$  and  $\mathbf{a}^{(i)}$ .

In contrast, Eq. 13 implicitly diversifies the architecture vectors  $\mathbf{a}^{(i)}$ . The reason is that the router routes embeddings  $e$  to codes  $a$  (Eq. 8) that have high similarity with each other (Eq. 7). Also, Eq. 13 distributes embeddings  $e$  in the space of the architecture embeddings such that the architecture vectors  $\mathbf{e}'$  become similar (different) for similar (dissimilar) prompts. As the vectors  $\mathbf{e}'$  and  $\mathbf{a}^{(i)}$  are calculated in a similar manner (Eqs. 9, 12), the diversity of vectors  $\mathbf{e}'$  implies the same for vectors  $\mathbf{a}^{(i)}$ .

Assuming  $B^{(i)}$  samples get routed to the architecture code  $a^{(i)}$  in a training batch ( $\sum_i B^{(i)} = B$ ), we train the prompt router and the architecture codes using the following objective:

$$\begin{aligned} \min_{\eta, \mathcal{A}} \mathcal{L} = & \left[ \frac{1}{N} \sum_{i=1}^N \left[ \frac{1}{B^{(i)}} \sum_{j=1}^{B^{(i)}} [\mathcal{L}_{\text{DDPM}}(x_j^{(i)}, p_j^{(i)}; a^{(i)}) + \lambda_{\text{distill}} \mathcal{L}_{\text{distill}}(x_j^{(i)}, p_j^{(i)}; a^{(i)})] \right] \right] \\ & + \lambda_{\text{res}} \mathcal{R}(\widehat{T}(\mathcal{A}), T_d) + \lambda_{\text{cont}} \mathcal{L}_{\text{cont}}(\eta) \end{aligned} \quad (15)$$

$\mathcal{L}_{\text{DDPM}}((x_j^{(i)}, p_j^{(i)}); a^{(i)})$  denotes the denoising objective for the sample  $(x_j^{(i)}, p_j^{(i)})$  routed to sub-network chosen by the architecture code  $a^{(i)}$ .  $\mathcal{R}(\widehat{T}(\mathcal{A}), T_d)$  regularizes the weighted average of the MACs used by architecture codes ( $\widehat{T}(\mathcal{A}) = \sum_i \frac{B^{(i)}}{B} [\widehat{T}(a^{(i)})]$ ) to be close to  $T_d$ . We define  $\mathcal{R}(x, y) = \log(\max(x, y)/\min(x, y))$ , and  $\{\lambda_{\text{distill}}, \lambda_{\text{res}}, \lambda_{\text{cont}}\}$  are hyperparameters. Finally,  $\mathcal{L}_{\text{distill}}$  is the distillation objective [29] regularizing the pruned model having similar outputs to the original one. We refer to Appendix D.4 for more details about our distillation objective.

### 3.4 Fine-tuning the Pruned Expert Models

After the pruning stage, we use the learned architecture codes to prune the T2I model into our experts. Then, we fine-tune experts using samples routed to them. We use the same training objective as the pretraining stage while adding distillation to fine-tune experts and refer to Appendix D.5 for more details. At test time, our trained prompt router routes an input prompt to one of the experts, and we use the expert to generate an image for it.

## 4 Experiments

We use Conceptual Captions 3M (CC3M) [60] and MS-COCO [37] as our *target* datasets to prune the Stable Diffusion (SD) V2.1 model to demonstrate APTP’s effectiveness. On CC3M, we prune the model with Base: (0.85 MACs, 16 experts) and Small: (0.66 MACs, 8 experts) configurations. On MS-COCO, we perform Base: (0.78 MACs, 8 experts) and Small: (0.64 MACs, 8 experts) pruning settings. We set  $(\lambda_{\text{distill}}, \lambda_{\text{res}}, \lambda_{\text{cont}}) = (0.2, 2.0, 100)$  (Eq. 15) and the temperature  $\tau$  (Eq. 14) to 0.03. We evaluate all models with FID [22], CLIP [21], and CMMD [28] scores using 14k samples in the validation set of CC3M and 30k samples from the MS-COCO’s validation split. For all models, we sample the images at the resolution of 768 and resize them to 256 for calculating the metrics, using the 25-steps PNDM [41] sampler following BK-SDM [29]. We refer to appendix E for more details.

### 4.1 Comparison Results

As APTP is the first pruning method to prune a pretrained T2I model on a *target* dataset, we compare its performance with SD V2.1 and the weight norm pruning [33] in this section, and Table 1 shows the results. We found that the APTP and Norm pruning baseline reach their final performance after about 30k and 50k iterations fine-tuning after pruning.




Figure 3: Samples of the APTP-Base experts after pruning the Stable Diffusion V2.1 using CC3M [60] and COCO [37] as the *target* datasets. Expert IDs are shown on the top right of images. (See Table 6 for prompts)

Table 1: Results on CC3M and MS-COCO. We report performance metrics using samples generated at the resolution of 768 then downsampled to 256 [29]. We measure models’ MACs/Latency with the input resolution of 768 on an A100 GPU. @30/50k shows fine-tuning iterations after pruning.

Method	CC3M					Method	MS-COCO				
	Complexity		Performance				Complexity		Performance		
	MACs (@768)	Latency (↓) (Sec/Sample) (@768)	FID (↓)	CLIP (↑)	CMMD (↓)		MACs (@768)	Latency (↓) (Sec/Sample) (@768)	FID (↓)	CLIP (↑)	CMMD (↓)
Norm [33] @50k	1185.3G	3.4	141.04	26.51	1.646	Norm [33] @50k	1077.4G	3.1	47.35	28.51	1.136
APTP(0.66) @30k	916.3G	2.6	60.04	28.64	1.094	APTP(0.64) @30k	890.0G	2.5	39.12	29.98	0.867
APTP(0.85) @30k	1182.8G	3.4	36.77	30.84	0.675	APTP(0.78) @30k	1076.6G	3.1	22.60	31.32	0.569
SD 2.1	1384.2G	4.0	32.08	31.12	0.567	SD 2.1	1384.2G	4.0	15.47	31.33	0.500

(a)

(b)

**CC3M:** Table 1a summarizes the results on CC3M. With a similar MACs budget, APTP (0.85) significantly outperforms the Norm pruning [33] baseline in terms of FID, CLIP, and CMMD scores. It also achieves 15% less latency while showing close performance scores to SD V2.1. Notably, APTP (0.66) has 23% less latency and 21% lower MACs budget than Norm [33], and at the same time, shows a large gap with the Norm pruning.

**MS-COCO:** We present the results for MS-COCO in Table 1b. APTP (0.78) reduces the latency of SD by 22.5% while preserving its CLIP score and achieving a close CMMD score. Further, APTP (0.78) significantly outperforms the model pruned by Norm [33] with a similar latency. Similar to the results on CC3M, APTP (0.64) achieves 19.3% less latency than the Norm pruning while outperforming it on FID, CLIP, and CMMD scores. In summary, our quantitative evaluations show the clear advantage of prompt-based compared to static pruning for T2I models. We provide samples of APTP on the validation sets of CC3M and MS-COCO in Fig. 3 (See Appendix. E.4.6 for more samples).

## 4.2 Analysis of the Prompt Router

We analyze our prompt router’s behavior by examining the prompts it assigns to experts in the APTP-Base (0.85) model for the CC3M experiment. Table 2 displays the most frequent words in the



Table 2: The most frequent words in prompts assigned to each expert of APTP-Base pruned on CC3M. The resource utilization of each expert is indicated in parentheses.

Expert 1 (0.72)	Expert 2 (0.73)	Expert 3 (0.75)	Expert 4 (0.76)
View - Sunset - City - Building - Sky	View - Boat - Sea	Artist - Actor	Actor - Dress - Portrait
Expert 5 (0.77)	Expert 6 (0.78)	Expert 7 (0.79)	Expert 8 (0.79)
Illustration - Portrait - Photo	Player - Ball - Game - Team	Background - Water - River - Tree	Biological Species - Dog - Cat
Expert 9 (0.79)	Expert 10 (0.80)	Expert 11 (0.81)	Expert 12 (0.81)
Illustration - Vector	People	Car - City - Road	Person - Player - Team - Couple
Expert 13 (0.86)	Expert 14 (0.90)	Expert 15 (0.95)	Expert 16 (0.98)
Room - House	Art - Artist - Digital	Food - Water	Person - Man - Woman - Text




Figure 4: Comparison of samples generated by low and high budget experts of APTP-Base vs. SD V2.1 on CC3M and MS-COCO validation sets.

prompts routed to each expert, along with the experts’ MACs budgets. Our prompt router effectively "specializes" experts by assigning distinct topics to experts with varying budgets. For instance, Expert 1 focuses on cityscapes, Expert 8 on animals, and Expert 13 on house interiors and exteriors. Notably, the prompt router assigns images of textual content and human beings to Expert 16, which has the highest budget. These categories have been empirically found to be challenging for SD 2.1 [6, 77], and our prompt router can automatically discover and route them to higher-capacity experts. In contrast, paintings and illustrations are assigned to lower-budget experts, as they seem to be easier for the model to generate. We provide examples of high and low resource prompts for APTP-Base on both CC3M and COCO in Fig. 4.

### 4.3 Ablation Study

We conduct two ablation experiments to study the impact of APTP’s components on its performance. First, we implement a naive baseline that uses parameterizations  $\mathbf{v} = \text{sigmoid}((\eta_v + g_v)/\tau)$  and  $\mathbf{u} = \text{sigmoid}((\eta_u + g_u)/\tau)$  (Eq. 9) to prune a single model. It directly trains two vectors  $(\eta_v, \eta_u)$  to do so (Uni-Arch Baseline’ in Table 3). Then, we start with a router trained only using the contrastive objective (Eq. 13) and add optimal transport and distillation incrementally to prune SD V2.1 into 8 experts with 80% MACs budget on MS-COCO [37]. We fine-tune all pruned models with 10k iterations, and Table 3 presents the results. We observe that the contrastive training (Eq. 13) alone fails to improve results from pruning a single model to a mixture of experts. This is because although the contrastive objective makes the architecture codes diverse, it does not enforce the prompt router to distribute the prompts between architecture codes. Thus, it routes most of the input prompts to a single expert. As a result, all experts except one receive insufficient training samples and generate low-quality samples after fine-tuning, leading to the mixture showing worse metrics than the baseline. Employing optimal transport (Eq. 5) in the prompt router significantly improves FID (10.22), CLIP (1.17), and CMMD (0.18) scores of the mixture. In addition, distillation can further improve the architecture search process of the experts, resulting in a more performant mixture. In summary, these results validate the effectiveness of our design choices for APTP.

Table 3: Ablation results of APTP’s components on 30k samples from MS-COCO [37] validation set. We fine-tune all models for 10k iterations after pruning.

Method	MACs(@768)	Latency(@768)	FID (↓)	Clip Score (↑)	CMMD (↓)
Uni-Arch Baseline	1088.8G	3.1	46.56	29.11	0.91
Contrastive Router	1079.5G	3.1	48.78	28.90	0.92
+ Optimal Transport	1076.6G	3.1	38.56	30.07	0.74
+ Distillation ( <b>APT</b> )	1076.6G	3.1	25.57	31.13	0.58

In our second ablation experiment, we explore the impact of the number of experts on APTP. We prune SD V2.1 to 80% MACs budget using APTP with 4, 8, and 12 experts on MS-COCO. Fig. 5 shows the results. Interestingly, the results demonstrate that the relationship between FID and CLIP scores with the number of experts is nonlinear, and the optimal number of experts is dataset-dependent. This observation illustrates that prompt-based pruning is more suitable than static pruning for T2I models.

## 5 Conclusion

In this paper, we develop Adaptive Prompt-Tailored Pruning (APT), the first prompt-based pruning method for text-to-image (T2I) diffusion models. APT takes a T2I model, pretrained on large-scale data, and prunes it using a *target* dataset, resembling the common practice that organizations fine-tune T2I models on their internal data before deployment. The core element of APT is a prompt router module that learns to decide the model capacity required to generate a sample for an input prompt, routing it to an architecture code given a desired compute budget. Each architecture code corresponds to a sub-network of the T2I model, specializing in generating images for the prompts that prompt router routes to it. APT trains the prompt router and architecture codes in an end-to-end manner, encouraging the prompt router to route similar prompts to similar architecture codes. Further, we utilize optimal transport in the prompt router of APT during pruning to diversify the architecture codes. Our experiments in which we prune Stable Diffusion (SD) V2.1 using CC3M and MS-COCO as *target* datasets demonstrate the benefit of prompt-based pruning compared to conventional static pruning methods for T2I models. Further, our analysis on APT’s prompt router reveals that it can automatically discover challenging prompt types for SD, like generating text, humans, and fingers, routing them to experts with high compute budgets.




Figure 5: Ablation Results for the number of experts of APTP on MS-COCO.

## References

- [1] Adobe. Firefly, 2023. URL <https://www.adobe.com/sensei/generative-ai/firefly.html>.
- [2] Shubham Agarwal, Subrata Mitra, Sarthak Chakraborty, Srikrishna Karanam, Koyel Mukherjee, and Shiv Saini. Approximate caching for efficiently serving diffusion models. *arXiv preprint arXiv:2312.04429*, 2023.
- [3] James Betker, Gabriel Goh, Li Jing, Tim Brooks, Jianfeng Wang, Linjie Li, Long Ouyang, Juntang Zhuang, Joyce Lee, Yufei Guo, et al. Improving image generation with better captions. *Computer Science. https://cdn.openai.com/papers/dall-e-3.pdf*, 2(3):8, 2023.
- [4] Han Cai, Chuang Gan, Tianzhe Wang, Zhekai Zhang, and Song Han. Once-for-all: Train one network and specialize it for efficient deployment. In *International Conference on Learning Representations*, 2020. URL <https://openreview.net/forum?id=Hy1xE1HKwS>.
- [5] Mathilde Caron, Ishan Misra, Julien Mairal, Priya Goyal, Piotr Bojanowski, and Armand Joulin. Unsupervised learning of visual features by contrasting cluster assignments. *Advances in neural information processing systems*, 33:9912–9924, 2020.
- [6] Haoxing Chen, Zhuoer Xu, Zhangxuan Gu, Yaohui Li, Changhua Meng, Huijia Zhu, Weiqiang Wang, et al. Diffute: Universal text editing diffusion model. *Advances in Neural Information Processing Systems*, 36, 2024.
- [7] Hongrong Cheng, Miao Zhang, and Javen Qinfeng Shi. A survey on deep neural network pruning-taxonomy, comparison, analysis, and recommendations. *arXiv preprint arXiv:2308.06767*, 2023.
- [8] Huanpeng Chu, Wei Wu, Chengjie Zang, and Kun Yuan. Qncd: Quantization noise correction for diffusion models. *arXiv preprint arXiv:2403.19140*, 2024.
- [9] Marco Cuturi. Sinkhorn distances: Lightspeed computation of optimal transport. *Advances in neural information processing systems*, 26, 2013.
- [10] Sara Elkerdawy, Mostafa Elhoushi, Hong Zhang, and Nilanjan Ray. Fire together wire together: A dynamic pruning approach with self-supervised mask prediction. In *Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition*, pages 12454–12463, 2022.
- [11] Gongfan Fang, Xinyin Ma, and Xinchao Wang. Structural pruning for diffusion models. In *Advances in Neural Information Processing Systems*, 2023.
- [12] Rohit Gandikota, Joanna Materzynska, Tingrui Zhou, Antonio Torralba, and David Bau. Concept sliders: Lora adaptors for precise control in diffusion models. *arXiv preprint arXiv:2311.12092*, 2023.
- [13] Emil Julius Gumbel. *Statistical theory of extreme values and some practical applications: a series of lectures*, volume 33. US Government Printing Office, 1954.
- [14] Amirhossein Habibian, Amir Ghodrati, Noor Fathima, Guillaume Sautiere, Risheek Garrepalli, Fatih Porikli, and Jens Petersen. Clockwork diffusion: Efficient generation with model-step distillation. *arXiv preprint arXiv:2312.08128*, 2023.
- [15] Song Han, Jeff Pool, John Tran, and William Dally. Learning both weights and connections for efficient neural network. *Advances in neural information processing systems*, 28, 2015.
- [16] Kaiming He, Xiangyu Zhang, Shaoqing Ren, and Jian Sun. Deep residual learning for image recognition. In *Proceedings of the IEEE conference on computer vision and pattern recognition*, pages 770–778, 2016.
- [17] Yang He and Lingao Xiao. Structured pruning for deep convolutional neural networks: A survey. *IEEE Transactions on Pattern Analysis and Machine Intelligence*, pages 1–20, 2023. doi: 10.1109/TPAMI.2023.3334614.
- [18] Yefei He, Luping Liu, Jing Liu, Weijia Wu, Hong Zhou, and Bohan Zhuang. Ptqd: Accurate post-training quantization for diffusion models. *Advances in Neural Information Processing Systems*, 36, 2024.
- [19] Yihui He, Ji Lin, Zhijian Liu, Hanrui Wang, Li-Jia Li, and Song Han. Amc: Automl for model compression and acceleration on mobile devices. In *Proceedings of the European conference on computer vision (ECCV)*, pages 784–800, 2018.
- [20] Amir Hertz, Ron Mokady, Jay Tenenbaum, Kfir Aberman, Yael Pritch, and Daniel Cohen-Or. Prompt-to-prompt image editing with cross attention control. *arXiv preprint arXiv:2208.01626*, 2022.

- [21] Jack Hessel, Ari Holtzman, Maxwell Forbes, Ronan Le Bras, and Yejin Choi. Clipscore: A reference-free evaluation metric for image captioning. *arXiv preprint arXiv:2104.08718*, 2021.
- [22] Martin Heusel, Hubert Ramsauer, Thomas Unterthiner, Bernhard Nessler, and Sepp Hochreiter. Gans trained by a two time-scale update rule converge to a local nash equilibrium. *Advances in neural information processing systems*, 30, 2017.
- [23] Geoffrey Hinton, Oriol Vinyals, and Jeff Dean. Distilling the knowledge in a neural network. *arXiv preprint arXiv:1503.02531*, 2015.
- [24] Jonathan Ho and Tim Salimans. Classifier-free diffusion guidance. *CoRR*, abs/2207.12598, 2022. doi: 10.48550/ARXIV.2207.12598. URL <https://doi.org/10.48550/arXiv.2207.12598>.
- [25] Jonathan Ho, Ajay Jain, and Pieter Abbeel. Denoising diffusion probabilistic models. *Advances in neural information processing systems*, 33:6840–6851, 2020.
- [26] Lu Hou, Zhiqi Huang, Lifeng Shang, Xin Jiang, Xiao Chen, and Qun Liu. Dynabert: Dynamic bert with adaptive width and depth. *Advances in Neural Information Processing Systems*, 33:9782–9793, 2020.
- [27] Eric Jang, Shixiang Gu, and Ben Poole. Categorical reparameterization with gumbel-softmax. In *International Conference on Learning Representations*, 2017. URL <https://openreview.net/forum?id=rkE3y85ee>.
- [28] Sadeep Jayasumana, Srikumar Ramalingam, Andreas Veit, Daniel Glasner, Ayan Chakrabarti, and Sanjiv Kumar. Rethinking fid: Towards a better evaluation metric for image generation. *arXiv preprint arXiv:2401.09603*, 2023.
- [29] Bo-Kyeong Kim, Hyoung-Kyu Song, Thibault Castells, and Shinkook Choi. On architectural compression of text-to-image diffusion models. *arXiv preprint arXiv:2305.15798*, 2023.
- [30] Gwanghyun Kim, Taesung Kwon, and Jong Chul Ye. Diffusionclip: Text-guided diffusion models for robust image manipulation. In *Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition*, pages 2426–2435, 2022.
- [31] Ashish Kumar, Daneul Kim, Jaesik Park, and Laxmidhar Behera. Pick-or-mix: Dynamic channel sampling for convnets, 2024. URL <https://openreview.net/forum?id=Howb7fXB4V>.
- [32] Yunsung Lee, JinYoung Kim, Hyojun Go, Myeongho Jeong, Shinhyeok Oh, and Seungtaek Choi. Multi-architecture multi-expert diffusion models. In *Proceedings of the AAAI Conference on Artificial Intelligence*, volume 38, pages 13427–13436, 2024.
- [33] Hao Li, Asim Kadav, Igor Durdanovic, Hanan Samet, and Hans Peter Graf. Pruning filters for efficient convnets. In *International Conference on Learning Representations*, 2017. URL <https://openreview.net/forum?id=rJqFGTslg>.
- [34] Xiuyu Li, Yijiang Liu, Long Lian, Huanrui Yang, Zhen Dong, Daniel Kang, Shanghang Zhang, and Kurt Keutzer. Q-diffusion: Quantizing diffusion models. In *Proceedings of the IEEE/CVF International Conference on Computer Vision*, pages 17535–17545, 2023.
- [35] Yanyu Li, Huan Wang, Qing Jin, Ju Hu, Pavlo Chemerys, Yun Fu, Yanzhi Wang, Sergey Tulyakov, and Jian Ren. Snapfusion: Text-to-image diffusion model on mobile devices within two seconds. *Advances in Neural Information Processing Systems*, 36, 2024.
- [36] Tao Lin, Sebastian U. Stich, Luis Barba, Daniil Dmitriev, and Martin Jaggi. Dynamic model pruning with feedback. In *International Conference on Learning Representations*, 2020. URL <https://openreview.net/forum?id=SJem81SFwB>.
- [37] Tsung-Yi Lin, Michael Maire, Serge Belongie, James Hays, Pietro Perona, Deva Ramanan, Piotr Dollár, and C Lawrence Zitnick. Microsoft coco: Common objects in context. In *Computer Vision—ECCV 2014: 13th European Conference, Zurich, Switzerland, September 6–12, 2014, Proceedings, Part V 13*, pages 740–755. Springer, 2014.
- [38] Enshu Liu, Xuefei Ning, Zinan Lin, Huazhong Yang, and Yu Wang. Oms-dpm: Optimizing the model schedule for diffusion probabilistic models. *arXiv preprint arXiv:2306.08860*, 2023.
- [39] Enshu Liu, Xuefei Ning, Huazhong Yang, and Yu Wang. A unified sampling framework for solver searching of diffusion probabilistic models. *arXiv preprint arXiv:2312.07243*, 2023.

- [40] Hanxiao Liu, Karen Simonyan, and Yiming Yang. DARTS: Differentiable architecture search. In *International Conference on Learning Representations*, 2019. URL <https://openreview.net/forum?id=S1eYHoC5FX>.
- [41] Luping Liu, Yi Ren, Zhijie Lin, and Zhou Zhao. Pseudo numerical methods for diffusion models on manifolds. In *The Tenth International Conference on Learning Representations, ICLR 2022, Virtual Event, April 25-29, 2022*. OpenReview.net, 2022. URL <https://openreview.net/forum?id=PlKWVd2yBkY>.
- [42] Xuewen Liu, Zhikai Li, Junrui Xiao, and Qingyi Gu. Enhanced distribution alignment for post-training quantization of diffusion models. *arXiv preprint arXiv:2401.04585*, 2024.
- [43] Ilya Loshchilov and Frank Hutter. Decoupled weight decay regularization. In *7th International Conference on Learning Representations, ICLR 2019, New Orleans, LA, USA, May 6-9, 2019*. OpenReview.net, 2019. URL <https://openreview.net/forum?id=Bkg6RiCqY7>.
- [44] Cheng Lu, Yuhao Zhou, Fan Bao, Jianfei Chen, Chongxuan Li, and Jun Zhu. DPM-solver++: Fast solver for guided sampling of diffusion probabilistic models, 2023. URL <https://openreview.net/forum?id=4vGwQqviud5>.
- [45] Xinyin Ma, Gongfan Fang, and Xinchao Wang. Deepcache: Accelerating diffusion models for free. *arXiv preprint arXiv:2312.00858*, 2023.
- [46] Chris J. Maddison, Andriy Mnih, and Yee Whye Teh. The concrete distribution: A continuous relaxation of discrete random variables. In *International Conference on Learning Representations*, 2017. URL <https://openreview.net/forum?id=S1jE5L5gl>.
- [47] Chenlin Meng, Robin Rombach, Ruiqi Gao, Diederik Kingma, Stefano Ermon, Jonathan Ho, and Tim Salimans. On distillation of guided diffusion models. In *Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition*, pages 14297–14306, 2023.
- [48] Midjourney. Midjourney, n.d. URL <https://www.midjourney.com/home>.
- [49] Alex Nichol, Prafulla Dhariwal, Aditya Ramesh, Pranav Shyam, Pamela Mishkin, Bob McGrew, Ilya Sutskever, and Mark Chen. Glide: Towards photorealistic image generation and editing with text-guided diffusion models. *arXiv preprint arXiv:2112.10741*, 2021.
- [50] Alexander Quinn Nichol and Prafulla Dhariwal. Improved denoising diffusion probabilistic models. In *International Conference on Machine Learning*, pages 8162–8171. PMLR, 2021.
- [51] Zizheng Pan, Bohan Zhuang, De-An Huang, Weili Nie, Zhiding Yu, Chaowei Xiao, Jianfei Cai, and Anima Anandkumar. T-stitch: Accelerating sampling in pre-trained diffusion models with trajectory stitching. *arXiv preprint arXiv:2402.14167*, 2024.
- [52] Nilesh Prasad Pandey, Marios Fournarakis, Chirag Patel, and Markus Nagel. Softmax bias correction for quantized generative models. In *Proceedings of the IEEE/CVF International Conference on Computer Vision*, pages 1453–1458, 2023.
- [53] Dustin Podell, Zion English, Kyle Lacey, Andreas Blattmann, Tim Dockhorn, Jonas Müller, Joe Penna, and Robin Rombach. SDXL: Improving latent diffusion models for high-resolution image synthesis. In *The Twelfth International Conference on Learning Representations*, 2024. URL <https://openreview.net/forum?id=di52zR8xgf>.
- [54] Aditya Ramesh, Prafulla Dhariwal, Alex Nichol, Casey Chu, and Mark Chen. Hierarchical text-conditional image generation with clip latents. *arXiv preprint arXiv:2204.06125*, 1(2):3, 2022.
- [55] Nils Reimers and Iryna Gurevych. Sentence-BERT: Sentence embeddings using Siamese BERT-networks. In Kentaro Inui, Jing Jiang, Vincent Ng, and Xiaojun Wan, editors, *Proceedings of the 2019 Conference on Empirical Methods in Natural Language Processing and the 9th International Joint Conference on Natural Language Processing (EMNLP-IJCNLP)*, pages 3982–3992, Hong Kong, China, November 2019. Association for Computational Linguistics. doi: 10.18653/v1/D19-1410. URL <https://aclanthology.org/D19-1410>.
- [56] Robin Rombach, Andreas Blattmann, Dominik Lorenz, Patrick Esser, and Björn Ommer. High-resolution image synthesis with latent diffusion models. In *Proceedings of the IEEE/CVF conference on computer vision and pattern recognition*, pages 10684–10695, 2022.
- [57] Olaf Ronneberger, Philipp Fischer, and Thomas Brox. U-net: Convolutional networks for biomedical image segmentation. In *Medical Image Computing and Computer-Assisted Intervention—MICCAI 2015: 18th International Conference, Munich, Germany, October 5-9, 2015, Proceedings, Part III 18*, pages 234–241. Springer, 2015.

- [58] Chitwan Saharia, William Chan, Saurabh Saxena, Lala Li, Jay Whang, Emily L Denton, Kamyar Ghasemipour, Raphael Gontijo Lopes, Burcu Karagol Ayan, Tim Salimans, et al. Photorealistic text-to-image diffusion models with deep language understanding. *Advances in neural information processing systems*, 35:36479–36494, 2022.
- [59] Tim Salimans and Jonathan Ho. Progressive distillation for fast sampling of diffusion models. In *International Conference on Learning Representations*, 2022. URL <https://openreview.net/forum?id=TiIXIpzhoI>.
- [60] Piyush Sharma, Nan Ding, Sebastian Goodman, and Radu Soricut. Conceptual captions: A cleaned, hypernymed, image alt-text dataset for automatic image captioning. In *Proceedings of ACL*, 2018.
- [61] Junhyuk So, Jungwon Lee, Daehyun Ahn, Hyungjun Kim, and Eunhyeok Park. Temporal dynamic quantization for diffusion models. *Advances in Neural Information Processing Systems*, 36, 2024.
- [62] Jascha Sohl-Dickstein, Eric Weiss, Niru Maheswaranathan, and Surya Ganguli. Deep unsupervised learning using nonequilibrium thermodynamics. In *International conference on machine learning*, pages 2256–2265. PMLR, 2015.
- [63] Jiaming Song, Chenlin Meng, and Stefano Ermon. Denoising diffusion implicit models. In *International Conference on Learning Representations*, 2021. URL <https://openreview.net/forum?id=St1giarCHLP>.
- [64] Yang Song and Stefano Ermon. Generative modeling by estimating gradients of the data distribution. *Advances in neural information processing systems*, 32, 2019.
- [65] Yang Song, Jascha Sohl-Dickstein, Diederik P Kingma, Abhishek Kumar, Stefano Ermon, and Ben Poole. Score-based generative modeling through stochastic differential equations. In *International Conference on Learning Representations*, 2021. URL <https://openreview.net/forum?id=PxtTIG12RRHS>.
- [66] Yuda Song, Zehao Sun, and Xuanwu Yin. Sdxs: Real-time one-step latent diffusion models with image conditions. *arXiv preprint arXiv:2403.16627*, 2024.
- [67] Siao Tang, Xin Wang, Hong Chen, Chaoyu Guan, Zewen Wu, Yansong Tang, and Wenwu Zhu. Post-training quantization with progressive calibration and activation relaxing for text-to-image diffusion models. *arXiv preprint arXiv:2311.06322*, 2023.
- [68] Yehui Tang, Yunhe Wang, Yixing Xu, Yiping Deng, Chao Xu, Dacheng Tao, and Chang Xu. Manifold regularized dynamic network pruning. In *Proceedings of the IEEE/CVF conference on computer vision and pattern recognition*, pages 5018–5028, 2021.
- [69] Ashish Vaswani, Noam Shazeer, Niki Parmar, Jakob Uszkoreit, Llion Jones, Aidan N Gomez, Łukasz Kaiser, and Illia Polosukhin. Attention is all you need. *Advances in neural information processing systems*, 30, 2017.
- [70] Daniel Watson, William Chan, Jonathan Ho, and Mohammad Norouzi. Learning fast samplers for diffusion models by differentiating through sample quality. In *International Conference on Learning Representations*, 2022. URL <https://openreview.net/forum?id=VFBjuF8HEp>.
- [71] Daniel Watson, Jonathan Ho, Mohammad Norouzi, and William Chan. Learning to efficiently sample from diffusion probabilistic models, 2022. URL <https://openreview.net/forum?id=L0zOxDpw4Y>.
- [72] Colin White, Mahmoud Safari, Rhea Sukthanker, Binxin Ru, Thomas Elsken, Arber Zela, Debadeepta Dey, and Frank Hutter. Neural architecture search: Insights from 1000 papers. *arXiv preprint arXiv:2301.08727*, 2023.
- [73] Felix Wimbauer, Bichen Wu, Edgar Schoenfeld, Xiaoliang Dai, Ji Hou, Zijian He, Artsiom Sanakoyeu, Peizhao Zhang, Sam Tsai, Jonas Kohler, et al. Cache me if you can: Accelerating diffusion models through block caching. *arXiv preprint arXiv:2312.03209*, 2023.
- [74] Yilun Xu, Mingyang Deng, Xiang Cheng, Yonglong Tian, Ziming Liu, and Tommi Jaakkola. Restart sampling for improving generative processes. *arXiv preprint arXiv:2306.14878*, 2023.
- [75] Xingyi Yang, Daquan Zhou, Jiashi Feng, and Xinchao Wang. Diffusion probabilistic model made slim. In *Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition*, pages 22552–22562, 2023.
- [76] Yuewei Yang, Xiaoliang Dai, Jialiang Wang, Peizhao Zhang, and Hongbo Zhang. Efficient quantization strategies for latent diffusion models. *arXiv preprint arXiv:2312.05431*, 2023.

- [77] Yukang Yang, Dongnan Gui, Yuhui Yuan, Weicong Liang, Haisong Ding, Han Hu, and Kai Chen. Glyph-control: Glyph conditional control for visual text generation. *Advances in Neural Information Processing Systems*, 36, 2024.
- [78] Lewei Yao, Renjie Pi, Hang Xu, Wei Zhang, Zhenguo Li, and Tong Zhang. Joint-detnas: Upgrade your detector with nas, pruning and dynamic distillation. In *Proceedings of the IEEE/CVF conference on computer vision and pattern recognition*, pages 10175–10184, 2021.
- [79] Asano YM., Rupprecht C., and Vedaldi A. Self-labelling via simultaneous clustering and representation learning. In *International Conference on Learning Representations*, 2020. URL <https://openreview.net/forum?id=Hyx-jyBFPr>.
- [80] Huijie Zhang, Yifu Lu, Ismail Alkhouri, Saiprasad Ravishankar, Dogyoon Song, and Qing Qu. Improving efficiency of diffusion models via multi-stage framework and tailored multi-decoder architectures. *arXiv preprint arXiv:2312.09181*, 2023.
- [81] Lvmin Zhang, Anyi Rao, and Maneesh Agrawala. Adding conditional control to text-to-image diffusion models. In *Proceedings of the IEEE/CVF International Conference on Computer Vision*, pages 3836–3847, 2023.
- [82] Qinsheng Zhang, Molei Tao, and Yongxin Chen. gDDIM: Generalized denoising diffusion implicit models. In *The Eleventh International Conference on Learning Representations*, 2023. URL <https://openreview.net/forum?id=1hKE9qjvz->.
- [83] Yang Zhao, Yanwu Xu, Zhisheng Xiao, and Tingbo Hou. Mobicdiffusion: Subsecond text-to-image generation on mobile devices. *arXiv preprint arXiv:2311.16567*, 2023.
- [84] Barret Zoph and Quoc Le. Neural architecture search with reinforcement learning. In *International Conference on Learning Representations*, 2017. URL <https://openreview.net/forum?id=r1Ue8Hcxg>.

## A Related Work

**Efficient Diffusion Models:** Methods for accelerating and improving the efficiency of diffusion models fall into two categories. The first group focuses on reducing the complexity or the number of sampling steps of diffusion models. They use techniques like distillation [14, 47, 59, 66], learning optimal denoising time-steps [70, 71], designing improved noise schedules [50, 63, 82], caching intermediate computations [2, 45, 73], and proposing faster solvers [39, 44, 74]. The second group is aimed at improving the architectural efficiency of diffusion models, which is the main focus of our paper. **Multi-expert** [32, 38, 51, 80] methods employ multiple expert models each responsible for a separate part of the denoising process of diffusion models. These methods either design expert model architectures [32, 80], train several models with varying capacities from scratch [38], or utilize existing pretrained experts [38, 51] with different capacities. However, pretrained experts are not necessarily available, and training several models from scratch, as required by multi-expert methods, is prohibitively expensive in practice. **Architecture Design** approaches [29, 75, 83] redesign the architecture of diffusion models to enhance efficiency. MobileDiffusion [83] modifies the U-Net [57] architecture of Stable Diffusion (SD) based on empirical heuristics derived from the model’s performance on the MS-COCO [37] dataset. BK-SDM [29] removes some blocks from the U-Net model of SD and applies knowledge distillation from the original SD model to the pruned model. Spectral Diffusion [75] introduces a wavelet gating operation and performs frequency domain distillation from a pretrained teacher model into a small student model. Yet, generalization of the heuristics and design choices in the architecture design methods to other tasks and compute budgets is non-trivial. **Quantization** methods [8, 18, 34, 42, 52, 61, 67, 76] reduce the precision of model weights and activations during the forward pass to accelerate the sampling process. Different from these methods, SnapFusion [35] searches for an efficient architecture for T2I models. However, evaluating each action in the search process consumes about 2.5 A100 GPU hours, rendering it impractical for resource-constrained scenarios. Finally, SPDM [11] estimates the importance of different weights in the model using Taylor expansion and removes the low-scored architectures. Despite their promising results, all these methods are ‘static’ in that they obtain an efficient model and utilize it for all inputs. This is suboptimal for T2I models as input prompts may vary in complexity, demanding different model capacity levels.

**Pruning and Neural Architecture Search (NAS):** Our paper also intersects with model pruning [7] and NAS [4, 26, 40, 72, 78, 84] methods. These methods prune pretrained models and search for suitable architectures given a specific task and computational budget. Existing pruning techniques can be categorized into Static and Dynamic methods. Static pruning approaches [15, 19, 33] prune a pretrained model and use the pruned model for all inputs. Conversely, dynamic pruning methods [10, 31, 36, 68] employ a separate sub-network of the model for each input. Although static and dynamic pruning methods have been successful for image classification, they are not suitable to be directly applied to T2I models. Static pruning methods neglect prompt complexity and employ the same model for all prompts while dynamic pruning ideas cannot utilize batch-parallelism in GPUs. We refer to recent surveys [7, 17, 72] for a comprehensive review of pruning and NAS methods.

Our method distinguishes itself from existing approaches by introducing a prompt-based pruning technique for T2I models. This work marks the first instance where computational resources are allocated to prompts based on their individual complexities while ensuring optimal utilization and batch-parallelizability.

## B Limitations and Broader Impacts

We believe a limitation of our work may be that our experimental scope is relatively limited. We chose CC3M [60] and MS-COCO [37] as they contain at least 100k image-text pairs and are diverse to enable us to simulate the real-world case of fine-tuning a pretrained T2I model like SD v2.1 on a *target* dataset before deploying it. Yet, exploring APTP’s performance on other tasks is an interesting future work. In addition, APTP, like Stable Diffusion, has challenges generating images of text, humans, and fingers (Sec. 4.2, Fig. 4), and one can employ techniques in recent works [6, 12, 77] to alleviate these issues. Finally, we note that our method can enable organizations to serve their models with a lower cost for GenAI applications, but it may also facilitate harmful content generation, necessitating responsible usage of generative models.



## C Overview of Diffusion Models

Given a random variable  $\mathbf{x}_0 \sim \mathcal{P}$ , the goal of diffusion models [25, 62] is to model the underlying distribution  $\mathcal{P}$  using a training set  $\mathcal{D} = \{x_0\}$  of samples. To do so, first, diffusion models define a forward process parameterized by  $t$  in which they gradually perturb each sample  $x_0$  with Gaussian noise with the variance schedule of  $\beta_t$ :

$$q(x_t|x_{t-1}) = \mathcal{N}(x_t; \sqrt{1 - \beta_t}x_{t-1}, \beta_t I) \quad (16)$$

where  $t \in [1, T]$ . Thus,  $q(x_t|x_0)$  has a Gaussian form:

$$q(x_t|x_0) = \mathcal{N}(x_t; \sqrt{\bar{\alpha}_t}x_0, (1 - \bar{\alpha}_t)I) \quad (17)$$

where  $\alpha_t = 1 - \beta_t$  and  $\bar{\alpha}_t = \prod_{i=1}^t \alpha_i$ . The noise schedule  $\beta_t$  is usually selected [25] such that  $q(x_T) \rightarrow \mathcal{N}(0, I)$ . Assuming  $\beta_t$  is small, diffusion models approximate the denoising distribution  $q(x_{t-1}|x_t)$  by a parameterized Gaussian distribution  $p_\theta(x_{t-1}|x_t) = \mathcal{N}(x_{t-1}; \frac{1}{\sqrt{\alpha_t}}(x_t - \frac{\beta_t}{\sqrt{1-\alpha_t}}\epsilon_\theta(x_t, t)), \sigma_t^2 I)$ , and  $\sigma_t^2$  is often set to  $\beta_t$ . Diffusion models implement  $\epsilon_\theta(\cdot)$  with a neural network called the denoising model and train it with the variational evidence lower bound (ELBO) objective [25]:

$$\mathcal{L}_{\text{DDPM}}(\theta) = \mathbb{E}_{\substack{t \sim [1, T] \\ \epsilon \sim \mathcal{N}(0, I) \\ x_t \sim q(x_t|x_0)}} \|\epsilon(x_t, t; \theta) - \epsilon\|^2 \quad (18)$$

Similarly, T2I diffusion models train a denoising model using pairs of image and text prompts  $(x_0, p) \sim \mathcal{P}$  to model the distribution  $\mathcal{P}(\mathbf{x}_0|\mathbf{p})$  of images given an input text prompt:

$$\mathcal{L}_{\text{DDPM}}(\theta) = \mathbb{E}_{\substack{(x_0, p) \sim \mathcal{P} \\ t \sim [1, T] \\ \epsilon \sim \mathcal{N}(0, I) \\ x_t \sim q(x_t|x_0)}} \|\epsilon(x_t, p, t; \theta) - \epsilon\|^2 \quad (19)$$

T2I Diffusion models generate a new sample by sampling an initial noise from  $x_T \sim p(x_T) = \mathcal{N}(0, I)$  and iteratively denoising it using the denoising model by sampling from  $p_\theta(x_{t-1}|x_t, p)$ . Thus, the sampling process requires  $T$  sequential forward calculation of the denoising model, making it a slow and costly process.

## D More Details of APTP

In this section we provide more details of the architecture predictor, the prompt router module, and our pruning method.

### D.1 Architecture Predictor

$f_{\text{AP}}(\cdot)$  in Eq. 4 is the architecture predictor. The architecture predictor changes the dimensionality of  $z$  to the dimensionality of  $e$  and codes  $a$ , which is the number of prunable width and depth units in the T2I model. We implement the  $f_{\text{AP}}$  function with a single feed-forward layer. Our prompt encoder, Sentence Transformer [55], has an output dimension of **768**. The total number of prunable units in SD 2.1 is **1620**, so the architecture predictor has an input dimension of **768** and an output dimension of **1620** in all of our experiments.

### D.2 Router Module Definition

During the pruning process, we use the assignment matrix  $Q^*$  calculated by optimal transport (Eq. 7) to route the architecture embeddings  $e$  to the architecture codes  $a$ . Thus, during the pruning process, the definition of function  $f_{\text{R}}$  is as follows:

$$I = \operatorname{argmax}(BQ^*, \dim = 0) \quad (20)$$

$$f_R(e, \mathcal{A}, Q^*) = A[:, I] \quad (21)$$

where  $e$  represents the architecture embeddings in a pruning batch,  $\mathcal{A}$  is the set of architecture codes,  $Q^*$  is the calculated optimal assignment matrix, and  $A$  is the matrix of architecture codes.

At test time, the router function routes an input architecture embedding  $e$  to the most similar trained architecture code:

$$f_R(e, \mathcal{A}) = \operatorname{argmax}_{a \in \mathcal{A}} \frac{e^T a}{\|e\| \|a\|} \quad (22)$$

### D.3 Pruning Depth

We apply the vectors  $\mathbf{u}^{(i)} = [\mathbf{u}_j^{(i)}]_{j=1}^M$  (Eq. 9) to prune the model’s depth with  $M$  being the total number of layers we prune. As the U-Net [57] architecture of T2I models has skip connections, we prune the depth layers in the encoder and decoder sides separately.

**Pruning Depth in Encoder.** We prune the  $j$ -th depth layer  $f_j$  in the encoder by applying the vector  $\mathbf{u}_j^{(i)}$  with the following formulation:

$$\widehat{\mathcal{F}}_j = \mathbf{u}_j^{(i)} f_j(\mathcal{F}_{j-1}) + (1 - \mathbf{u}_j^{(i)}) \mathcal{F}_{j-1} \quad (23)$$

where  $\mathcal{F}_{j-1}$  is the feature maps of the previous layer. When  $\mathbf{u}_j^{(i)}$  is close to one/zero, the  $j$ -th layer will be kept/pruned.

**Pruning Depth in Decoder.** In the decoder, the input of each layer is a concatenation of feature maps of the previous layer and feature maps of its corresponding encoder layer from the skip connection  $\mathcal{F}_{j,skip}$ . Thus, we prune the  $j$ -th depth layer  $f_j$  in the decoder as:

$$\widehat{\mathcal{F}}_j = \mathbf{u}_j^{(i)} f_j(\mathcal{F}_{j-1} || \mathcal{F}_{j,skip}) + (1 - \mathbf{u}_j^{(i)}) \mathcal{F}_{j-1} \quad (24)$$

### D.4 Distillation Objective

Assuming  $B^{(i)}$  samples get routed to the architecture code  $a^{(i)}$  in a training batch ( $\sum_i B^{(i)} = B$ ), we train the prompt router and the architecture codes using the following objective:

$$\begin{aligned} \min_{\eta, \mathcal{A}} \mathcal{L} = & \frac{1}{N} \sum_{i=1}^N \left[ \frac{1}{B^{(i)}} \sum_{j=1}^{B^{(i)}} [\mathcal{L}_{\text{DDPM}}(x_j^{(i)}, p_j^{(i)}; a^{(i)}) + \lambda_{\text{distill}} \mathcal{L}_{\text{distill}}(x_j^{(i)}, p_j^{(i)}; a^{(i)})] \right] \\ & + \lambda_{\text{res}} \mathcal{R}(\widehat{T}(\mathcal{A}), T_d) + \lambda_{\text{cont}} \mathcal{L}_{\text{cont}}(\eta) \end{aligned} \quad (25)$$

$\mathcal{L}_{\text{DDPM}}(x_j^{(i)}, p_j^{(i)}; a^{(i)})$  denotes the denoising objective for the sample  $(x_j^{(i)}, p_j^{(i)})$  routed to the sub-network chosen by the architecture code  $a^{(i)}$  (Eq. 19).  $\mathcal{R}(\widehat{T}(\mathcal{A}), T_d)$  regularizes the weighted average of the MACs used by architecture codes ( $\widehat{T}(\mathcal{A}) = \sum_i \frac{B^{(i)}}{B} \widehat{T}(a^{(i)})$ ) to be close to  $T_d$ . We define

$$\mathcal{R}(x, y) = \log(\max(x, y) / \min(x, y)) \quad (26)$$

as it can keep the resource usage close to the target value.  $\mathcal{L}_{\text{cont}}$ , given by Eq. 13, is the contrastive loss that guides the architecture predictor to map prompt representations to the regions of the space of the architecture embeddings such that their corresponding architecture vectors maintain the similarity between the prompts. Finally,  $\mathcal{L}_{\text{distill}}$  is the distillation objective [23], regularizing the pruned model to have similar outputs to the original one. We do distillation at two levels, output level and block level. The output level distillation objective is:

$$\mathcal{L}_{\text{output-distill}}(x_j^{(i)}, p_j^{(i)}; a^{(i)}) = \mathbb{E}_{\substack{t \sim [1, T] \\ \epsilon \sim \mathcal{N}(0, I) \\ x_{j,t}^{(i)} \sim q(x_t | x_j^{(i)})}} [|\epsilon_{\text{Teacher}}(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta) - \epsilon_{\text{Sub-Net}}(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta, a^{(i)})|^2] \quad (27)$$

Here,  $\epsilon_{\text{Teacher}}(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta)$  denotes the original model’s output and  $\epsilon_{\text{Sub-Net}}(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta, a^{(i)})$  denotes the output of the sub-network chosen by the architecture code  $a^{(i)}$ . The way we prune the U-Net preserves the output shape of each block. Doing so enables us to do distillation at block level as well and regularize the sub-network to match the output of the original model at each block. The block-level distillation objective is:

$$\mathcal{L}_{\text{block-distill}}(x_j^{(i)}, p_j^{(i)}; a^{(i)}) = \mathbb{E}_{\substack{t \sim [1, T] \\ \epsilon \sim \mathcal{N}(0, I) \\ x_{j,t}^{(i)} \sim q(x_t | x_j^{(i)})}} \left[ \sum_b \|\epsilon_{\text{Teacher}}^b(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta) - \epsilon_{\text{Sub-Net}}^b(x_{j,t}^{(i)}, p_j^{(i)}; t; \theta, a^{(i)})\|^2 \right] \quad (28)$$

Here,  $\epsilon_{\text{Teacher}}^b$  and  $\epsilon_{\text{Sub-Net}}^b$  denote the outputs of block  $b$  of the original model and the chosen sub-network of it, respectively. The total distillation loss  $\mathcal{L}_{\text{distill}}$  is simply the sum of the output-level loss and the block-level distillation loss:

$$\mathcal{L}_{\text{distill}} = \mathcal{L}_{\text{output-distill}} + \mathcal{L}_{\text{block-distill}} \quad (29)$$

## D.5 Fine-tuning

The finetuning loss is a weighted average of the original DDPM objective (Eq. 19) and the distillation loss term (Eq. 29):

$$\mathcal{L}_{\text{finetuning}} = \alpha_{\text{DDPM}} \mathcal{L}_{\text{DDPM}} + \alpha_{\text{distill}} \mathcal{L}_{\text{distill}} \quad (30)$$

# E Experiments

## E.1 Models and Datasets

We use two datasets as our *target* datasets: Conceptual Captions 3M (CC3M) [60] and MS-COCO Captions 2014 [37] with approximately 2.5M and 400K image-caption pairs, respectively. We apply APTP to the Stable Diffusion 2.1 (SD 2.1) [56] model. On CC3M, we prune SD2.1 with two settings: Base (0.85 budget, 16 experts) and Small (0.66 budget, 8 experts). Similarly, for COCO, we have two settings: Base (0.78 budget, 8 experts) and Small (0.64 budget, 8 experts). We use a pruned SD 2.1 using weight norm pruning [33] as a baseline for our main experiments.

## E.2 Experimental Settings

We train at a fixed resolution of  $256 \times 256$  across all settings. During pruning, we first train the architecture predictor for 500 iterations as a warm-up phase. During this warm-up phase, we directly use its predicted architectures for pruning. Then, we start architecture codes and train the architecture predictor jointly with the codes for an additional 2500 iterations. We use the AdamW [43] optimizer and a constant learning rate of 0.0002 for both modules, with a 100-iteration linear warm-up. The effective pruning batch size is 1024, achieved by training on 16 NVIDIA A100 GPUs with a local batch size of 64. The temperature of the Gumbel-Sigmoid reparametrization (Eq. 9) is set to  $\gamma = 0.4$ . We set the regularization strength of the optimal transport objective (Eq. 5) to  $\epsilon = 0.05$ . We use 3 iterations of the Sinkhorn-Knopp algorithm [9] to solve the optimal transport problem [5]. We set the contrastive loss temperature  $\tau$  to 0.03. The total pruning loss is the weighted average of DDPM loss, distillation loss, resource loss, and contrastive loss (see Eq. 15) with weights  $\lambda_{\text{distill}} = 0.2$ ,  $\lambda_{\text{res}} = 2.0$ , and  $\lambda_{\text{cont}} = 100.0$ . After the pruning phase, we fine-tune the experts with the prompts assigned to them for 30,000 iterations using the AdamW optimizer, a fixed learning rate of 0.00001, and a batch size of 128. Upon experiments, we observed that higher weights of the DDPM loss result in unstable




Figure 6: Resource and Contrastive loss observed when applying APTP-Base with a MAC budget of 0.77 to prune Stable Diffusion 2.1 using the COCO dataset. The comparison is made between two settings: with and without optimal transport. APTP both adheres to the target MAC budget and finds architecture vectors that maintain the similarity between the prompts.

fine-tuning and slow convergence. As a result, we set the DDPM loss weight in the fine-tuning loss (Eq. 30)  $\alpha_{\text{DDPM}}$  to 0.0001. We set  $\alpha_{\text{distill}} = 1.0$ . For sample generation, we use the classifier-free guidance [24] technique with the scale of 7.5 and 25 steps of the PNDM sampler [41].

### E.3 Evaluation

For quantitative evaluation of models pruned on CC3M, we use its validation dataset of approximately 14k samples. For COCO, we sample 30k captions of unique images from its 2014 validation dataset. We report Fréchet inception distance (FID) [22], CLIP score [21], and Maximum Mean Discrepancy with CLIP Embeddings (CMMD) [28] for APTP, the baselines, and SD 2.1 itself.

### E.4 Results

#### E.4.1 Training Loss

Introduced in section 3.3.1, the resource loss regularizes the weighted average of the MACs used by architecture codes ( $\widehat{T}(\mathcal{A}) = \sum_i \frac{B^{(i)}}{B} [\widehat{T}(a^{(i)})]$ ) to be close to  $T_d$ . We define resource loss as:

$$\mathcal{R}(x, y) = \log(\max(x, y) / \min(x, y)) \quad (31)$$


Fig. 6a illustrates the resource loss when applying APTP-Base to prune Stable Diffusion 2.1 using the COCO dataset as the target. This is shown under two conditions: with and without optimal transport following the initial warm-up phase (refer to E for details). APTP effectively regularizes the model so average MACs of the architecture codes is very close to the target budget. Fig. 6b presents the contrastive loss (Eq. 13) under the same conditions. APTP maps the prompt embeddings to regions of architecture embeddings such that their corresponding architectures maintain the similarity between prompts.

#### E.4.2 Visualization of the Impact of Optimal Transport

Fig. 7 displays the assignment of prompts to experts with and without optimal transport. By adding optimal transport, the assignment becomes more diverse, ensuring all experts get enough samples. This results in a significant improvement of performance metrics (See Table 3). Fig. 8 shows the distribution of the number of training CC3M samples mapped to each expert of APTP-Base.

#### E.4.3 Analysis of Prompt Router on COCO

Table 4 demonstrates the most frequent words in the prompts assigned to each expert of APTP-Base pruned on COCO, revealing distinct topics and effective specialization. For example, Expert 1 specializes in indoor scenes, Expert 5 in wildlife, and Expert 6 in urban scenes. Expert 8 which has the highest resource utilization, focuses on images of human beings and hands, an observation consistent with our prompt analysis on CC3M (Table 2). Hands are another category that have been found to be challenging for SD 2.1 [12].



(a) Without Optimal Transport

(b) With Optimal Transport

Figure 7: Comparison of sample assignments in a batch to experts with and without optimal transport. The incorporation of optimal transport results in a more diverse assignment pattern. In the figure, each square represents a prompt within the batch, and the color signifies the budget level of the expert assigned to the prompt. Higher-resource experts are indicated by darker blue.




Figure 8: Distribution of CC3M Samples Mapped to Each Expert of APTP-Base, Including Resource Utilization Ratios

Table 4: The most frequent words in prompts assigned to each expert of APTP-Base pruned on COCO. The resource utilization of each expert is indicated in parentheses.

<b>Expert 1 (0.65, Indoor Scenes and Dining)</b>	<b>Expert 2 (0.77, Food and Small Groups)</b>
table - plate - kitchen - sitting	food - pizza - sandwich
<b>Expert 3 (0.78, People and Objects)</b>	<b>Expert 4 (0.79, Sports and Activities)</b>
skateboard - surfboard - laptop - tie - phone	tennis - baseball - racquet - skateboard - skis
<b>Expert 5 (0.79, Wildlife and Nature)</b>	<b>Expert 6 (0.80, Urban Scenes and Transportation)</b>
giraffe - herd - sheep - zebra - elephants	street - train - bus - park - building
<b>Expert 7 (0.81, Outdoor Activities and Nature)</b>	<b>Expert 8 (0.83, Domestic Life and Pets)</b>
beach - ocean - surfboard - kite - wave	man - woman - girl - hand - bed - cat

Table 5: Quantitative results on CC3M and MS-COCO. We report the performance metrics using samples generated at the resolution of 768 and downsampled to 256 [29]. We measure models’ MACs and Latency with the input resolution of 768 on an A100 GPU. @30/50k shows the model’s fine-tuning iterations after pruning.

CC3M						MS-COCO					
Method	Complexity		Performance			Method	Complexity		Performance		
	MACs (@768)	Latency (↓) (Sec/Sample) (@768)	FID (↓)	CLIP (↑)	CMMD (↓)		MACs (@768)	Latency (↓) (Sec/Sample) (@768)	FID (↓)	CLIP (↑)	CMMD (↓)
Norm [33] @30k	1185.3G	3.4	157.51	26.23	1.778	Norm [33] @30k	1077.4G	3.1	60.42	27.06	1.524
Norm [33] @50k	1185.3G	3.4	141.04	26.51	1.646	Norm [33] @50k	1077.4G	3.1	47.35	28.51	1.136
APTP(0.66) @30k	916.3G	2.6	60.04	28.64	1.094	APTP(0.64) @30k	890.0G	2.5	39.12	29.98	0.867
APTP(0.66) @50k	916.3G	2.6	54.95	29.08	1.017	APTP(0.64) @50k	890.0G	2.5	36.17	30.21	0.739
APTP(0.85) @30k	1182.8G	3.4	36.77	30.84	0.675	APTP(0.78) @30k	1076.6G	3.1	22.60	31.32	0.569
APTP(0.85) @50k	1182.8G	3.4	36.09	30.90	0.669	APTP(0.78) @50k	1076.6G	3.1	22.26	31.38	0.561
SD 2.1	1384.2G	4.0	32.08	31.12	0.567	SD 2.1	1384.2G	4.0	15.47	31.33	0.500

(a)

(b)

#### E.4.4 Quantitative Results

The quantitative results on the CC3M and MS-COCO datasets (Table 5) indicate that APTP significantly outperforms the baseline Norm method in terms of FID and CLIP scores while also reducing complexity. For both datasets, APTP at 30k and 50k fine-tuning iterations shows lower FID and CMMD values and higher CLIP scores compared to the baseline, demonstrating the advantage of prompt based pruning compared to static pruning ideas for T2I models.

#### E.4.5 Expert Architectures

Figures 9 and 10 display the block-level U-Net architecture of all experts of APTP-Base, with CC3M and COCO as the target datasets, respectively. The retained MAC patterns are markedly different, further corroborating that different datasets require distinct architectures and that a ‘one-size-fits-all’ approach is not well-suited for T2I models. For CC3M, down-sampling blocks generally are retained with higher ratios. Overall, APTP tends to prune Resnet Blocks more frequently and aggressively compared to Attention Blocks.

#### E.4.6 Samples of APTP

Table 6 displays the prompts for the images in Fig. 3 from CC3M and COCO validation sets.




Figure 9: The block-level retained MAC ratio of the UNet architecture of all experts of APTP-Base applied to Stable Diffusion 2.1 with CC3M as the target dataset. The groups of ResBlocks and the heads of Attention Blocks are pruned based on the outputs of the architecture predictor. The intensity of the color of each block represents the resource utilization of it. The number in each block indicates the precise ratio of retained MACs of the block. Conv\_in, Conv\_out, and skip connections between corresponding down and up blocks are omitted for brevity.



Figure 10: The block-level retained MAC ratio of the UNet architecture of all experts of APTP-Base applied to Stable Diffusion 2.1 with COCO as the target dataset. The groups of ResBlocks and the heads of Attention Blocks are pruned based on the outputs of the architecture predictor. The intensity of the color of each block represents the resource utilization of it. The number in each block indicates the precise ratio of retained MACs of the block. Conv\_in, Conv\_out, and skip connections between corresponding down and up blocks are omitted for brevity.

We also provide more samples from APTP-Base pruned on CC3M and COCO. Fig. 11 presents samples from the validation set of CC3M generated by each 16 experts of APTP-Base at 0.85 MACs budget. Fig. 12 shows samples from the validation set of COCO from each of the 8 experts of APTP-Base pruned to 0.77 MACs budget.





---

**CC3M Prompts**

---

Saw this beautiful sky on my way home.  
A silhouetted palm tree with boat tied to it rests on a beach that a man walks across during golden hour.  
Sketch of a retro photo camera drawn by hand on a white background.  
From left: person person, the dress on display.  
Never saw a doll like this before but she sure is sweet looking.  
The team on the summit.  
A water drop falls towards a splash already made by another water drop.  
Husky dog in a new year's interior.  
Old paper with a picture of flowers, ranked in a moist environment.  
People on new year's eve!  
I drive over stuff - a pretty cool jeep, 4x4, or truck t-shirt.  
The crowds arrive for day of festival.  
A scary abandoned house under a starry sky.  
Freehand fashion illustration with a lady with decorative hair.  
Introduce some new flavors to your favorite finger food with these inspired chicken wings.  
Gloomy face of a sad woman looking down, zoom in, gray background.

---

---

**COCO Prompts**

---

A white plate topped with a piece of chocolate covered cake.  
Decorated coffee cup and knife sitting on a patterned surface.  
A desk topped with a laptop computer and speakers.  
A man sitting on the beach behind his surfboard.  
A pizza type dish with vegetables and a lemon wedge.  
The browned cracked crust of a baked berry pie.  
A tennis player in an orange skirt walks off the court.  
The skier in the helmet moves through thick snow.  
A giraffe walks leisurely through the tall grass.  
Several brown horses are standing in a field.  
A red fire hydrant on a concrete block.  
A bus driving in a city area with traffic signs.  
There is a man on a surf board in the ocean.  
A boat parked on top of a beach in crystal blue water.  
A small kitchen with low a ceiling.  
A calico cat curls up inside a bowl to sleep.

---

Table 6: Prompts for Fig. 3




Figure 12: Samples of the APTP-Base experts after pruning the Stable Diffusion V2.1 using MS-COCO [37] as the *target* dataset. Each row corresponds to a unique expert. Please refer to Table 4 for the groups of prompts assigned to each expert.