

The hot gas mass fraction in halos. From Milky Way-like groups to massive clusters

P. Popesso^{1,2*}, A. Biviano^{3,4}, I. Marini¹, K. Dolag^{5,6,2}, S. Vladutescu-Zopp⁵, B. Csizi⁷, V. Biffi⁸, G. Lamer⁹, A. Robothan¹⁰, M. Bravo¹¹, L. Lovisari^{12,13}, S. Ettori¹⁴, M. Angelinelli¹⁴, S. Driver⁹, V. Toptun¹, A. Dev¹⁰, D. Mazengo¹, A. Merloni¹⁵, J. Comparat¹⁵, G. Ponti¹⁵, T. Mroczkowski¹, E. Bulbul¹⁵, S. Grandis⁷, and E. Bahar¹⁵

¹ European Southern Observatory, Karl Schwarzschildstrasse 2, 85748, Garching bei München, Germany e-mail: paola.popesso@eso.org

² Excellence Cluster ORIGINS, Boltzmannstr. 2, D-85748 Garching bei München, Germany

³ INAF – Osservatorio Astronomico di Trieste, Via Tiepolo 11, 34143 Trieste, Italy

⁴ IFPU – Institute for Fundamental Physics of the Universe, Via Beirut 2, I-34014 Trieste, Italy

⁵ Universitäts-Sternwarte, Fakultät für Physik, Ludwig-Maximilians-Universität München, Scheinerstr.1, 81679 München, Germany

⁶ Max-Planck-Institut für Astrophysik, Karl-Schwarzschildstr. 1, 85741 Garching bei München, Germany

⁷ Universität Innsbruck, Institut für Astro- und Teilchenphysik, Technikerstr. 25/8, 6020 Innsbruck, Austria

⁸ INAF – Osservatorio Astronomico di Trieste, Via Tiepolo 11, 34143 Trieste, Italy

⁹ Leibniz-Institut für Astrophysik Potsdam (AIP), An der Sternwarte 16, 14482 Potsdam, Germany

¹⁰ International Centre for Radio Astronomy Research, University of Western Australia, M468, 35 Stirling Highway, Perth, WA 6009, Australia

¹¹ McMaster University, 1280 Main Street West, Hamilton, Ontario, L8S 4L8, Canada

¹² INAF – Osservatorio Astronomico di Brera, Via E. Bianchi 46, 23807 Merate (LC), Italy

¹³ Center for Astrophysics | Harvard & Smithsonian, 60 Garden Street, Cambridge, MA 02138, USA

¹⁴ INAF – Osservatorio Astronomico di Bologna, Via Gobetti 93/3, 40129 Bologna, Italy

¹⁵ Max-Planck-Institut für Extraterrestrische Physik (MPE), Giessenbachstr. 1, D-85748 Garching bei München, Germany

Received September 15, 1996; accepted March 16, 1997

ABSTRACT

Aims. By using eROSITA data in the eFEDS area, we provide a measure of the $f_{gas} - M_{halo}$ relation over the largest halo mass range, from Milky Way sized halos to massive clusters, and to the largest radii (R_{200}) ever probed so far in local systems at $z < 0.2$.

Methods. To cope with incompleteness and selection biases of the X-ray selection, we apply the stacking technique in eROSITA data of a highly complete and tested sample of optically selected groups. The method has been extensively tested on mock observations.

Results. In massive clusters, the hot gas alone provides a baryon budget within R_{200} consistent with Ω_b/Ω_m , while at the group mass scale, it accounts only for 20-40% of the cosmic value. The $f_{gas} - M_{halo}$ relation is well fitted by a power law with a consistent shape (within 1σ) at R_{500} and R_{200} and a normalization varying nearly by a factor of 2. Such a relation is consistent with other works in the literature that consider X-ray survey data at the same depth as eFEDS, but it provides a lower average f_{gas} in the group regime in comparison to works based on X-ray bright group samples. The comparison of the observed relation with the predictions of several hydrodynamical simulations (BAHAMAS, FLAMINGO, SIMBA, Illustris, IllustrisTNG, MillenniumTNG and *Magneticum*) shows that all state-of-the-art simulations but *Magneticum* over-predict the gas fraction, with the largest discrepancy (up to a factor 3) in the $10^{13.5} M_\odot$ to $10^{14.5} M_\odot$ halo mass range.

Conclusions. We emphasize the need for mechanisms that can effectively expel gas to larger radii in galaxy groups without excessively quenching star formation in their member galaxies. Current hydrodynamical simulations face a significant challenge in balancing their subgrid physics: none can sufficiently evacuate gas from the halo virial region without negatively impacting the properties of the resident galaxy population.

Key words. galaxy groups – intra-group medium – AGN feedback – Baryonic processes

1. Introduction

In a purely gravitational framework, the temperature, density, and mass distribution of the hot gas in galaxy groups and clusters are expected to follow the halo's potential well and the dark matter distribution in a self-similar regime, as predicted by large-scale structure evolution models (see Peebles 1980). However, observations consistently show significant deviations from self-similar predictions in various scaling relations (Popesso et al.

2005; Rykoff et al. 2008; Vikhlinin et al. 2009; Pratt et al. 2009; Mantz et al. 2015; Planck Collaboration et al. 2016; Bulbul et al. 2019; Bahar et al. 2022; Zhang et al. 2024). Specifically, several studies indicate that the baryon fraction within the central region ($< R_{500}^1$) of massive halos increases with halo mass (Sun et al. 2009; Ettori 2015; Lovisari et al. 2015; Eckert et al. 2016; Nugent et al. 2020). The baryon content in galaxy groups is

¹ R_Δ represents the radius of a sphere centered on the group, with a mean density equal to Δ times the critical density of the Universe at the group's redshift.

* paola.popesso@eso.org

only about half of the expected value based on self-similar models, while for clusters it is much closer to the predicted value (see, e.g., the review by Eckert et al. 2021). This discrepancy is thought to be driven by non-gravitational processes that alter the thermodynamic properties of the hot gas and the overall baryon content in groups and clusters. Among these processes, feedback from the central supermassive black hole (hereafter BH) in the brightest cluster galaxy is a strong candidate due to the substantial energy involved (Sijacki et al. 2007; Puchwein et al. 2008; Fabjan et al. 2010; McCarthy et al. 2010; Le Brun et al. 2014; Biffi et al. 2018; Vallés-Pérez et al. 2020; Galárraga-Espinosa et al. 2021; Eckert et al. 2021; Oppenheimer et al. 2021). In high-mass clusters, BH feedback primarily impacts the central core, leading to elevated entropy levels (Le Brun et al. 2014). In contrast, in lower-mass groups, BH feedback may affect the gas out to 0.5-1 Mpc, potentially influencing the entire group volume (e.g., see Oppenheimer et al. 2021, for a comprehensive review).

Cosmological simulations show that different implementations of BH feedback result in varying predictions, particularly at the group mass scale. In single-mode feedback models, a fraction of the BH energy is deposited as a thermal boost into nearby cells (e.g., Schaye et al. 2015; McCarthy et al. 2017; Schaye et al. 2023). More sophisticated dual-mode implementations distinguish between thermal outflows or high-accretion (quasar) modes and kinetic energy transfer or bubble inflation at low accretion rates (radio mode), incorporating halo mass dependencies in models such as *IllustrisTNG* (Pillepich et al. 2019), *MillenniumTNG* (Pakmor et al. 2022), and *Magneticum* (Dolag et al. 2016). Constraining these theoretical predictions requires precise observational measurements of the hot gas content in galaxy groups and clusters to place upper limits on the energy injected via BH feedback.

Current observational studies of the gas mass fraction (f_{gas}) as a function of halo mass (M_{halo}) primarily focus on clusters. At lower masses, only a limited number of heterogeneously selected X-ray groups are available, sampled at varying depths and resolutions (Ponman et al. 1996; Mulchaey 2000; Osmond & Ponman 2004; Sun et al. 2009; Lovisari et al. 2015; Lovisari & Ettori 2021). Pointed observations with ROSAT, XMM-Newton, and Chandra have targeted only the brightest X-ray groups. If BH feedback can expel part of the intragroup medium, it would reduce gas density and potentially bias flux-limited X-ray surveys, leading to an overestimation of f_{gas} at the group scale. Therefore, an unbiased selection method is needed to accurately measure the hot gas content in galaxy groups. Indeed, recent analyses of eROSITA Science Verification data over the eROSITA Final Equatorial Depth Survey (eFEDS) area (Brunner et al. 2022) suggest that eROSITA's X-ray selection captures only a subset of galaxy groups, with many remaining undetected due to their lower X-ray surface brightness at a given halo mass (Popesso et al. 2024a, P24 hereafter).

An optical selection of galaxy groups offers a way to circumvent BH feedback biases since it is independent of a system's hot gas content. Large spectroscopic surveys like SDSS (Blanton et al. 2017) and GAMA (Driver et al. 2022) provide comprehensive catalogs of optically selected groups and clusters, down to halo masses of $10^{12} M_{\odot}$ at low to intermediate redshifts (e.g., Tempel et al. 2017; Robotham et al. 2011; Yang et al. 2007). Combining such optically selected samples with large X-ray surveys has proven effective in characterizing the average X-ray properties of the halo population down to group scales (Anderson et al. 2015; Rozo et al. 2009; Rykoff et al. 2008; Crossett et al. 2022; Giles et al. 2022). Stacking X-ray data at the positions of optically detected groups enables the measurement of

average X-ray scaling relations in the low-mass regime. In this paper, we perform a stacking analysis on eROSITA data of the GAMA galaxy group sample. The methodology and selection effects arising from the optical selection and the halo mass proxy used as a prior for the stacking have been thoroughly tested and evaluated in previous studies (Popesso et al. 2024c; Marini et al. 2024b). This study offers the most precise estimate of the gas mass fraction to date, covering the broadest halo mass range and the largest radius ever examined, while minimizing biases related to BH feedback, after extensive testing on mock dataset.

The paper is structured as follows. In Sect. 2 we describe optical and X-ray datasets used in the analysis. In Sect. 3 we describe how the gas mass is derived from the X-ray surface brightness distribution obtained through stacking in P24. Sect. 4 provides our results, while in Sect. 5 we draw our conclusions. Throughout the paper we assume a Flat Λ CDM cosmology with $H_0 = 67.74 \text{ km s}^{-1} \text{ Mpc}^{-1}$, $\Omega_m(z=0) = 0.3089$ (Planck Collaboration et al. 2016).

2. The dataset

In this section, we describe the data available over the 60 deg² of overlapping area between the eFEDS and the GAMA survey.

2.1. eROSITA eFEDS data and group sample

For this study, we used the public Early Data Release (EDR) eROSITA event file of the eFEDS field (Brunner et al. 2022). The field was observed with an unvignetted exposure of approximately 2.5 ks, slightly higher than the anticipated exposure for the future eRASS upon completion, which is about 1.6 ks unvignetted. The dataset contains roughly 11 million events (X-ray photons) detected by eROSITA across the 140 deg² area of the eFEDS Performance Verification survey. Each photon is assigned an exposure time based on the vignetting-corrected exposure map. Photons in proximity to detected sources from the source catalog are flagged. These sources are classified as point-like or extended according to their X-ray morphology (Brunner et al. 2022) and further categorized (e.g., galactic, active galactic nuclei, individual galaxies at redshift $z < 0.05$, galaxy groups, and clusters) using multi-wavelength information (Salvato et al. 2022; Vulic et al. 2022; Liu et al. 2022b,a; Bulbul et al. 2022).

The X-ray-selected groups and clusters in the eFEDS area are provided in the catalog of Liu et al. (2022a). This comprises more than 500 extended objects up to $z \sim 1$. According to Liu et al. (2022a) the catalog reaches a completeness of 40% down to a flux limit of $1.5 \times 10^{-14} \text{ erg s}^{-1} \text{ cm}^{-2}$. Each source is assigned a redshift according to the analysis reported in Klein et al. (2022), an estimate of the X-ray luminosity within different apertures (300 and 500 kpc and within R_{500}), and the surface brightness distribution within several radii. An estimate of M_{500}^2 is provided on the basis of the $L_X - M_{500}$ scaling relation of Lovisari et al. (2015).

Despite the smaller volume covered by eFEDS, its much greater depth and stable background make it preferable to the shallower observations from eRASS:1. Therefore, we use the results of Popesso et al. (2024b) on the average X-ray surface brightness profiles of galaxy groups to derive gas mass profiles from Milky Way-sized halos to massive clusters. These profiles, along with the stacking technique they are based on, have been

² $G M_{\Delta} = \Delta/2 H_z^2 R_{\Delta}^3$, where G is the gravitational constant and H_z the Hubble constant at the group redshift z .

rigorously validated by Popesso et al. (2024c) using mock optically selected catalogs and simulated eROSITA observations. This testing was done to assess the contamination and completeness of the input sample and to verify the reliability of the stacking analysis.

2.2. The GAMA optically selected group and cluster sample

The optically selected GAMA group sample (Robotham et al. 2011) comprises about 7500 galaxy groups and pairs identified in the spectroscopic sample of the GAMA spectroscopic survey (Driver et al. 2022), over the region of interest (G09 in the GAMA survey). This reaches a completeness of $\sim 95\%$ down to the magnitude limit of $r = 19.8$. The Friends-of-Friends algorithm described in (Robotham et al. 2011, hereafter R11) identifies the galaxy groups and pairs.

Once galaxy membership is identified, the mean group coordinates and redshift are iteratively estimated for each system. The total mass of the systems (M_{tot}) is then estimated from the group's velocity dispersion (σ_v) within a variable radius (see Robotham et al. 2011, for more details). However, Marini et al. (2024a), using a mock synthetic catalog based on the same selection algorithm of Robotham et al. (2011), show that the halo mass proxy based on velocity dispersion is not a reliable measure for groups with a low number of galaxy members. To address this, a richness cut is required to ensure a minimum number of galaxies to accurately estimate the dispersion, which introduces further selection effects during stacking.

Marini et al. (2024a) indicate that the total optical luminosity of the groups is the best mass proxy. The algorithm effectively retrieves group membership, ensuring that all bright members contributing most to the group's total luminosity are captured. This accuracy is consistent regardless of group richness, including the case of pairs. Therefore, the halo mass proxy based on total luminosity not only shows the best agreement with the true/input halo mass but also allows for the creation of a clean group sample without additional selection effects due to richness cuts.

Consequently, we use the galaxy membership provided in Robotham et al. (2011)'s catalog to estimate the total group optical luminosities in the r-band following the approach of Popesso et al. (2005), and the group masses M_{200} and virial radii R_{200} from the scaling relations with the optical luminosity provided in the same paper. Additionally, we derive estimates for M_{500} and R_{500} using the NFW mass distribution model of Navarro et al. (1997) and the concentration-mass relation of Dutton & Macciò (2014).

2.3. The average X-ray surface brightness profile of groups

To derive gas density profiles for galaxy groups, it is crucial to obtain accurate X-ray surface brightness profiles. For this purpose, we use the average surface brightness profiles from Popesso et al. (2024b), which have been rigorously validated using synthetic datasets that replicate the observed eROSITA X-ray and GAMA optical data, generated from the Magneticum simulations' lightcones. These profiles are based on stacking GAMA groups limited to $z < 0.2$ within the eFEDS area.

The redshift limit ensures high completeness for the GAMA group sample down to $M_{\text{halo}} \sim 10^{12.2} M_{\odot}$. The use of a halo mass proxy based on total group luminosity rather than velocity dispersion, makes the richness cut applied in Popesso et al. (2024a) unnecessary. As shown in Marini et al. (2024a), this luminosity-

based proxy offers more reliable halo mass estimates and extends the completeness down to lower masses. According to Marini et al. (2024a), the mock GAMA group sample retains over 90% completeness down to $\log(M_{200}/M_{\odot}) \sim 13.5$, decreasing to 80% at $\log(M_{200}/M_{\odot}) \sim 13$, and to 65% at $\log(M_{200}/M_{\odot}) \sim 12$. Contamination remains below 10% for $\log(M_{200}/M_{\odot}) \gtrsim 13$, increasing to 20% at lower masses.

In Popesso et al. (2024b) we apply the stacking procedure of P24 by using the GAMA sample as prior catalog for the stacking in the eFEDS data. We consider six halo mass bins from $M_{200} > 3 \times 10^{12} M_{\odot}$ to $10^{14} M_{\odot}$, from Milky Way like groups to poor clusters. All priors in the halo mass bins are considered without distinction between detected and undetected groups, to measure the average X-ray surface brightness profile of the underlying group population. Only groups with a companion or a point source within $2 R_{200}$ are discarded from the prior catalog because they would contaminate the background subtraction and the resulting average profile. Briefly, the stacking is done by averaging the background subtracted surface brightness profiles within the same annuli around the group center. The background is measured in a region between 2 to 3 Mpc from the group center. All events flagged as point sources in each annulus are excluded and the corresponding annulus area is corrected for the excluded point source area. All groups containing a point source or contaminated by close neighbors within $2 r_{200}$ are excluded from the prior sample for the stacking. The X-ray luminosity from the stacked signal is derived in the 0.5-2 keV band by selecting only events with a rest frame energy in the selected band at the median redshift of the prior sample. The spectroscopic information is retained and corrected for the effective area to ensure an accurate estimate of the X-ray luminosity. We refer to P24 and Popesso et al. (2024b) for a more detailed description of the procedure, including the AGN and XRB contamination based on the Magneticum model. The results of this analysis are shown in Fig. 2 of Popesso et al. (2024c), which presents the average X-ray surface brightness profiles obtained in this way.

Additionally, we include the average profile of detected clusters with $M_{200} > 10^{14} M_{\odot}$ at $z < 0.2$ from eFEDS, from Liu et al. (2022a). By cross-referencing the eROSITA eFEDS sample with optically selected groups, we identify an optical counterpart for each X-ray detection, except in two cases where associations were ambiguous. In one case, multiple lower-mass groups at the same redshift overlapped the region of the X-ray detection, and in the second case, the redshift provided by Klein et al. (2022) did not match that of the corresponding GAMA group. These two cases were excluded from our analysis. No optically selected groups remain undetected above $M_{200} > 10^{14} M_{\odot}$, confirming a consistent optical and X-ray selection of groups at high halo masses. As shown in P24, the stacked profiles of detected clusters are in agreement with the average profiles from Liu et al. (2022a), ensuring consistency throughout our study. The X-ray detected GAMA systems in eFEDS complement the stacked profiles in the $10^{14} < M_{200} < 10^{14.3} M_{\odot}$ range. For detected systems, we use the total optical luminosity as a mass proxy, maintaining the same selection function across the entire range analyzed. In Fig. 1 we show the surface brightness profiles for the groups in the seven halo mass bins, the first six obtained by stacking and the last one by averaging.

To complement our measure at higher halo masses, we use the average f_{gas} profile of the CHEX-MATE cluster sub-sample used for the stack of eROSITA data by Lyskova et al. (2023). The CHEX-MATE cluster sample (CHEX-MATE Collaboration et al. 2021) is an unbiased, signal-to-noise limited sample of 118 galaxy clusters detected by Planck via the Sunyaev-Zel'dovich





Fig. 1. Each panel in the upper two rows shows the X-ray surface brightness profile as estimated in Popesso et al. (2024b). The red solid line represents the stacked profile, while the pink shaded region indicates the uncertainty derived from bootstrapping. The panel in the last row displays the average X-ray surface brightness profile (red solid line) of the eFEDS detections with optical counterparts in the GAMA galaxy sample, corresponding to the specific halo mass bin, while the pink shaded region indicates the dispersion. The solid purple line in all panels shows the best-fit projected X-ray emissivity profile, represented by $n_e(r)^2 \Lambda(kT, Z)$.

Table 1. Best fit electron density model parameters of the Vikhlinin et al. (2006).

$\text{Log}(M_{200})$ M_{\odot}	R_{200} [Mpc]	n_0 [10^{-4}cm^{-3}]	r_c/R_{200}	r_s/R_{200}	α	β	ϵ
12.43±0.43	250±35	1.38±0.03	0.10±0.01	2.15±0.03	0.89±0.1	0.39±0.06	2.86
12.70±0.45	390±46	1.11±0.03	0.12±0.01	2.05±0.04	0.72±0.2	0.30±0.07	2.86
13.04±0.43	455±65	3.53±0.05	0.05±0.02	2.0±0.03	0.89±0.2	0.37±0.05	2.86
13.32±0.43	700±63	4.54±0.03	0.06±0.01	2.05±0.04	0.89±0.3	0.43±0.1	2.86
13.55±0.46	780±71	9.25±0.04	0.04±0.02	1.95±0.03	0.8±0.2	0.43±0.07	2.86
13.83±0.45	850±65	6.87±0.05	0.05±0.01	1.95±0.02	0.75±0.1	0.36±0.05	2.86
14.15±0.41	1997±41	1.17±0.01	0.042±0.005	1.7±0.01	1.07±0.03	0.40±0.03	8.96±0.13


Fig. 2. Electron density profiles of groups and clusters in the halo mass bins studied here. The profiles are color-coded as a function of M_{200} as shown in the color bar. The magenta profile is obtained from the stacking in eROSITA of the CHEXMATE clusters and it is taken from Lyskova et al. (2023).

effect. It is composed of clusters at $z < 0.2$ with masses $2 \times 10^{14} < M_{500}/M_{\odot} < 9 \times 10^{14}$ from the PSZ2 catalogue (Planck Collaboration et al. 2016). The CHEX-MATE subsample used for the stacking comprises 38 systems in regions with minimal background variations due to proximity to the Galactic plane and the Cygnus-X star formation region, and relatively far from the North Polar Spur. We derive the mean M_{200} and R_{200} from the average M_{500} and R_{500} estimates listed in Lyskova et al. (2023), by assuming a NFW profile with concentration of 6 (see also Dutton & Macciò 2014).

3. The gas mass estimate

We estimate the gas mass profile as described in Liu et al. (2022a). Specifically, we use a Vikhlinin et al. (2006) electron number density model

$$n_e^2(r) = n_0^2 \cdot \left(\frac{r}{r_c}\right)^{-\alpha} \cdot \left(1 + \left(\frac{r}{r_c}\right)^2\right)^{-3\beta + \alpha/2} \cdot \left(1 + \left(\frac{r}{r_s}\right)^3\right)^{-\epsilon/3}, \quad (1)$$

where n_0 is the normalization factor, r_c and r_s are the core and scale radii, β controls the overall slope of the density profile, α controls the slope in the core and at intermediate radii, and ϵ controls the change of slope at large radii. This is used to estimate and integrate along the line of sight the X-ray emissiv-

ity, $n_e(r)^2 \Lambda(kT, Z)$ profile, where $\Lambda(kT, Z)$ is the cooling function depending on the gas temperature and metallicity. The cooling function is derived by assuming a gas temperature from the $M - T_X$ relation of Lovisari et al. (2015) at the mean M_{500} of the halo mass bin. As in Liu et al. (2022a), we assumed a metallicity of the ICM of $0.3 Z_{\odot}$, adopting the solar abundance table of Asplund et al. (2009), that includes the He abundance. This assumption is consistent with the average metallicity estimated in poor cluster cores by Lovisari & Reiprich (2019) and with Magneticum predictions, although the observed scatter is large. The error due to these assumptions is estimated in (Popesso et al. 2024c, see also next session) based on the Magneticum mock observations. The effect on X-ray emissivity depends mainly on the systematics of the halo mass proxy. For the GAMA group sample, the use of the total luminosity proxy results in a scatter of 40% in the emissivity estimate at fixed metallicity. The assumption of a fixed metallicity of $0.3 Z_{\odot}$ leads to a variation in emissivity of 37%. Since these effects cannot be corrected, they are included in the error budget and summed in quadrature with the statistical errors.

The projected number density model is convolved with the eROSITA PSF and fitted to the data. Differently from Liu et al. (2022a) we leave all parameters free in the fit, but ϵ , which rules the change of slope at large radii. This is poorly constrained due to the relatively low SNR in the outskirts region. Thus, we fixed the value to the cluster value provided by Vikhlinin et al. (2006). Only for the average profile of the detected poor clusters at $14 < \log(M_{200}/M_{\odot}) < 14.3$, the SNR is high enough to constrain the change of slope at large radii. The best-fit line to the X-ray surface brightness profiles and the best-fit parameters are reported in Fig. 1. The electron density profiles obtained in this way are shown in Fig. 2. We include also the profiles of Lyskova et al. (2023) for the CHEX-MATE clusters.

We compute the ICM mass of a system within a given aperture, by using the best-fit model for the electron density profile,

$$M_{\text{ICM}} = 4\pi\mu_e m_p \int_0^R n_e(r) r^2 dr, \quad (2)$$

where the average nuclear charge and mass are $A \sim 1.4$ and $Z \sim 1.2$, and $\mu_e = A/Z \sim 1.17$.

3.1. Validation of the stacking procedure and gas mass estimate

The stacking procedure applied to eROSITA data in different mass bins, as validated by Popesso et al. (2024c), employs a mock dataset generated from the L30 lightcone of the Magneticum simulation. This dataset incorporates mock eROSITA observations down to the eRASS:4 depth (corresponding to two

years of observations) and a GAMA-like spectroscopic galaxy survey. A Friends-of-Friends (FoF) algorithm, as described by Robotham et al. (2011), is applied to the mock galaxy data to generate an optical group catalog resembling the GAMA-selected sample. The performance of this FoF algorithm, including completeness and contamination, is extensively analyzed in Marini et al. (2024a).

Popesso et al. (2024c) replicate the analysis framework of Popesso et al. (2024b) by using this mock dataset to test the reliability of the stacking method and gas mass estimations. Key elements of the mock analysis—halo mass limits, mass proxies, and bin sizes—are matched to those in the real dataset, ensuring a robust validation of the procedure.

The study addresses key systematic uncertainties, including selection biases in optical catalogs, mis-centering between optical and X-ray datasets, AGN and XRB contamination, and scatter in the halo mass proxy. Notably, completeness and contamination in optical catalogs were shown to be sufficient to avoid significant biases, while mis-centering is mitigated due to small positional offsets compared to the eROSITA PSF. AGN and XRB contamination, prominent in low-mass halos ($M_{200} < 10^{13} M_{\odot}$), are effectively modeled and subtracted, ensuring minimal impact on X-ray surface brightness estimates.

The stacking analysis demonstrates excellent agreement between the input and retrieved X-ray surface brightness profiles. Low-mass halos exhibit a maximum residual overestimation of 30%, attributable to contamination in the halo mass proxy bins. In higher mass halos, profiles are accurately reproduced. Across all mass bins, the stacking procedure proves robust, confirming no significant biases in the analyzed halo mass range, even when only 60% of the population is captured by the detection algorithm.

Regarding gas mass estimations, the study assesses the systematic impact of inferring gas temperatures from the T_X -mass scaling relation and assuming a fixed metallicity of $0.3Z_{\odot}$. For the R11 algorithm, the analysis shows a 40% scatter in the retrieved emissivity values. By incorporating uncertainties in gas temperature and metallicity into the error budget, the stacking method reliably reconstructs input electron density profiles, further validating its robustness (see Fig. 13 of Popesso et al. 2024c). This approach ensures that systematic uncertainties are accounted for when interpreting the results from real observations.

4. Results

4.1. The gas concentration

To quantify how the shape of the gas profiles varies with system mass, we estimate the gas concentration (c_{gas}) as the ratio of the gas mass within $0.1 R_{200}$ to that within R_{200} . Figure 3 shows the variation of gas concentration with halo mass. A clear trend is observed, with gas concentration increasing with mass; specifically, the CHEX-MATE clusters are approximately 2.5 times as concentrated as Milky Way-sized groups, following a dependence of $c_{gas} \propto M_{200}^{0.178 \pm 0.09}$. This factor is 3 times larger than errors deriving from observational error of the stacking, including the uncertainty due to the estimate of the gas emissivity by assuming the gas temperature and metallicity, as described in the previous section. Additionally, according to the standard hierarchical formation paradigm, dark matter concentration (c_{200}) decreases monotonically with mass (see also Dutton & Macciò 2014). The opposite trend observed for gas concentration sug-




Fig. 3. Relation between gas concentration, defined as the ratio of hot gas mass within $0.1 R_{200}$ to that within R_{200} , versus halo mass. The blue points represent results derived from the stacked data. The big purple point shows the result based on the electron density profile of the CHEX-MATE clusters stacked in eROSITA (Lyskova et al. 2023). The solid black line represents the best-fit relation based on the combined stacks of eFEDS and CHEX-MATE data. The small purple points indicate the mean relation predicted by the Magneticum simulation, with the shaded region illustrating the dispersion around this relation. The pink squares display the results obtained using the same stacking technique applied in this study to the X-ray surface brightness profiles derived from mock galaxy groups selected using the Robotham et al. (2011) algorithm on the mock eROSITA data from the L30 lightcone of Magneticum.

gests the influence of non-gravitational processes, most likely AGN feedback.

We propose that the observed increase in gas concentration from low-mass groups to massive clusters results from AGN feedback evacuating gas more effectively in low-mass halos due to their shallower potential wells compared to clusters. To explore this trend further, we examine the L30 lightcone of the Magneticum simulation, finding a positive correlation with a Spearman coefficient of 0.64 and a probability of no correlation of $\sim 10^{-5}$. However, Magneticum predicts a flatter dependence of $c_{gas} \propto M_{200}^{0.090 \pm 0.01}$.

Figure 3 also presents c_{gas} values obtained by applying the same analysis as in this study to the stacked surface brightness profiles of the mock dataset analogous to the one used here (Marini et al. 2024b; Popesso et al. 2024c). Figure 3 shows that our approach, including uncertainties and systematics of the group selection, halo mass proxy choice, and stacking technique, accurately reproduces the $c_{gas} - M_{200}$ relation predicted by Magneticum within 1σ . This consistency suggests that the results obtained from the observed stacked profiles are robust.

4.2. The observed $Y_{gas} - M_{halo}$ relation

We define the fraction of gas mass within a radius r as:

$$f_{gas}(< r) = M_{gas}(< r) / M_{tot}(< r) \quad (3)$$

where M_{gas} is estimated from eq. (3) and $M_{tot}(< r)$ is the total mass contained within the radius r . In this analysis, we study the gas fraction contained within R_{500} and R_{200} . We normalize f_{gas} to the universal baryon fraction ($\Omega_b / \Omega_m = 0.154$, Planck Collaboration et al. 2020) to obtain $Y_{gas}(< r)$.




Fig. 4. $Y_{\text{gas}}-M_{500}$ relation. The filled circles represent a compilation of literature data, color-coded as a function of the sample reference as shown in the picture. The blue squares indicate the Y_{gas} derived from the stacked groups of Popesso et al. (2024c). The purple square indicates the value derived from the CHEXMATE clusters stacked in eROSITA data by Lyskova et al. (2023). The solid black curve represents our best fit to stacked points including the CHEXMATE clusters. The dashed yellow and green curves represent the best fit of Pratt et al. (2009) and Eckert et al. (2016), respectively. The $Y_{\text{gas}} = 1$ corresponding to the Planck Collaboration et al. (2020) value is indicated by the black dashed line.




Fig. 5. $Y_{\text{gas}}-M_{200}$ relation. The blue squares indicate the Y_{gas} derived from the stacked groups of Popesso et al. (2024b). The purple square indicates the value derived from the CHEXMATE clusters stacked in eROSITA data by Lyskova et al. (2023). The solid black curve represents our best fit to stacked points including the CHEXMATE clusters. The red dashed line shows the best fit of the $Y_{\text{gas}} - M_{500}$ relation of Fig. 4.

Fig. 4 shows Y_{gas} estimated within R_{500} versus M_{500} . Y_{gas} varies by a factor of ~ 10 from $M_{500} \sim 5 \times 10^{12} M_{\odot}$, Milky Way-sized groups, to $M_{500} \sim 5 \times 10^{14} M_{\odot}$, the CHEXMATE clusters. The same is observed for the Y_{gas} estimated within R_{200} (see Fig. 5). The best-fit power-law relation to the data including the CHEXMATE stacked point is:

$$f_{\text{gas},500} = 2.23 \pm 0.18 \times 10^{-7} (M_{500}/M_{\odot})^{0.39 \pm 0.02} \quad (4)$$

Our best fit of eq. (4) is consistent within 1σ with the estimates of Pratt et al. (2009) and Eckert et al. (2016). Nevertheless, it has a similar slope but a lower normalization in comparison to the estimates of Sun et al. (2009), Lovisari et al. (2015), and Eckert et al. (2021). These estimates are based on ROSAT galaxy group samples, that include only the brightest groups of the local Universe due to the high RASS flux limit. The stacked data, instead, are representative of the bulk of the underlying halo mass population as tested in Popesso et al. (2024c) through the analysis of the analog mock dataset generated from Magneticum. Thus, they include also groups and poor clusters whose gas distribution might have been heavily affected by non-gravitational processes such as AGN feedback.

In addition to the combination of the eFEDS stacks and the CHEX-MATE stacked point, we also show in Fig. 4 a comprehensive compilation of literature data providing the same estimate for $z < 0.2$ systems. These are the cluster sample of Mulroy et al. (2019), Mahdavi et al. (2013), Eckert et al. (2019), the REXCESS sample of Pratt et al. (2009), the poor cluster and group sample of Arnaud et al. (2007), Vikhlinin et al. (2006), and Sun et al. (2009) used in Pratt et al. (2009) (APP05+V09+S09 in Fig. 4), the XMM-XXL sample of Eckert et al. (2016), the group samples of Gonzalez et al. (2013) and Lovisari et al. (2015), the poor cluster sample of Ragagnin et al. (2022), and the group sample of Rasmussen & Ponman (2009) and Pearson et al. (2017) (RP09+P17 in Fig. 4). We transformed all the values to our adopted cosmology. We compare the distribution of the literature compilation to our best fit. Given the very different selection functions of the collected data, it is not surprising that they scatter largely around our best fit. Nevertheless, we find consistency in the distribution of the observed systems and the best fit provided here and based on the stacked profiles. In particular, we point out that the XMM-XXL groups of Eckert et al. (2019), which are selected at a flux limit similar to eFEDS, exhibit f_{gas} values consistent with the mean values of the eFEDS detections and stacks at $M_{500} \sim 10^{13.5} - 10^{14} M_{\odot}$.

We also present here in Fig. 5, for the very first time, the f_{gas} versus halo mass relation, estimated within R_{200} . Until recently, measuring the f_{gas} beyond R_{500} was hampered by the lack of sensitivity of previous instruments. The stacking analysis can overcome this problem, as shown by P24 and Lyskova et al. (2023). The combination of eFEDS stacks and the CHEX-MATE stack allows us to determine f_{gas} over the largest halo mass range, and for the largest radius, ever probed so far in groups and clusters. The best-fit relation is:

$$f_{\text{gas},200} = 2.09 \pm 0.14 \times 10^{-6} (M_{200}/M_{\odot})^{0.33 \pm 0.02} \quad (5)$$

At the Milky Way-sized group scale, f_{gas} is $\sim 20\text{--}40\%$ of the cosmic value. It goes above 50% for massive groups and poor clusters and it reaches the cosmic value at the CHEX-MATE cluster mass scale. The slope of best fit of eqs. (4) and (5) are consistent within 2σ , but the fraction of gas nearly doubles from R_{500} to R_{200} .

4.3. Comparison with simulations

We compare the results of our analysis with the predictions of several hydrodynamical simulations, each implementing a different BH feedback model. We consider, in particular, the predictions of MillenniumTNG (Pakmor et al. 2022), FLAMINGO (Schaye et al. 2023), BAHAMAS (McCarthy et al. 2017), SIMBA (Davé et al. 2019), Illustris (Genel et al. 2014), IllustrisTNG (Pillepich et al. 2019) and *Magneticum* (Dolag et al. 2016).




Fig. 6. Comparison of the observed Y_{gas} versus mass relations within R_{500} with different hydrodynamical simulations. The color code for each dataset is indicated in each panel. The light orange squares show the stacked points of Fig. 4, while the black line shows our best-fit relation. The bottom subpanels show the residuals of each dataset to our best fit. These are expressed in dex ($\log(f_{\text{gas}}) - \log(\text{fit})$). *Top-left panel:* Comparison of $Y_{\text{gas}}-M_{500}$ relation with the predictions of the BAHAMAS (Salcido et al. 2023), and FLAMINGO (Schaye et al. 2023) simulations. The blue shaded region indicates the 1σ uncertainty of the relation in FLAMINGO as reported in the corresponding paper. These two simulations use similar galaxy evolution models and feedback implementations. *Top-right panel:* Comparison of $Y_{\text{gas}}-M_{500}$ relation with the predictions of the IllustrisTNG (Pillepich et al. 2019) and of MillenniumTNG (Pakmor et al. 2022) simulations. For IllustrisTNG we show the individual estimates (pink points) and the mean relation (purple squares). For MillenniumTNG we report the mean relation (green squares) retrieved in the corresponding paper. These two simulations use similar galaxy evolution models and feedback implementations. *Bottom-left panel:* Comparison of $Y_{\text{gas}}-M_{500}$ relation with the predictions of the *Magneticum* (Dolag et al. 2016). The pink points indicate the individual estimates, while the purple squares indicate the mean relation. *Bottom-right panel:* Comparison of $Y_{\text{gas}}-M_{500}$ relation with the predictions of the *Simba* (Davé et al. 2019) and *Illustris* (Genel et al. 2014).

For MillenniumTNG, FLAMINGO, BAHAMAS, Illustris, and SIMBA, the $f_{\text{gas}}-M_{500}$ relation is provided in the reference paper. We normalize such relation to the value of Ω_b/Ω_m according to the cosmology implemented in each simulation. Only for the IllustrisTNG and *Magneticum*, we derive the $f_{\text{gas}} - M_{\text{halo}}$ relation ourselves. For IllustrisTNG, we select halos in TNG-300, corresponding to the largest cosmological box available, including 75000^3 particles in a $300 \text{ h}^{-1} \text{ cMpc}^3$ volume. The dark matter (initial gas) particles have mass $5.9 \times 10^7 \text{ h}^{-1} M_\odot$ ($1.1 \times 10^7 \text{ h}^{-1} M_\odot$) and Plummer equivalent softening 0.74 kpc (0.19 ckpc). Details on the simulation and the astrophysical subgrid models implemented can be found in Pillepich et al. (2019). We select halos at redshift $z = 0$ since we find no evolution of the $Y_{\text{gas}} - M_{\text{halo}}$ relation in the redshift range $z = 0-0.2$ (i.e., the redshift range of the surveys considered here). As for *Magneticum*, halos are drawn from *Box2b/hr* which includes a to-

tal of 2×2880^3 particles in a volume of $(640 \text{ h}^{-1} \text{ cMpc})^3$. The dark matter (initial gas) particles have mass $6.9 \times 10^8 \text{ h}^{-1} M_\odot$ ($1.4 \times 10^8 \text{ h}^{-1} M_\odot$) and Plummer equivalent softening $3.75 \text{ h}^{-1} \text{ kpc}$ ($3.75 \text{ h}^{-1} \text{ kpc}$). We select halos in the last snapshot available at redshift $z = 0.25$. To further prove the consistency of our investigation, we repeat the analysis with *Box2/hr* - 2×1584^3 particles in a $(352 \text{ h}^{-1} \text{ cMpc})^3$ volume - both at $z = 0$ and $z = 0.3$ to rule out possible intrinsic redshift evolution of such relation. More details on the simulations and the astrophysical subgrid models implemented can be found in Dolag et al. (2016). In both simulations, we gather a representative sample of clusters and group-size halos by randomly selecting 10^4 halos with $\log M_{500}/M_\odot \geq 12.2$ in each simulation. For each of them, we compute the baryon fraction Y_{gas} within R_{500} and R_{200} considering all the hot gas particles (i.e., $T > 10^6 \text{ K}$).

The result of the comparison is shown in Fig. 6. Compared to our observational results, Y_{gas} is over-predicted at given M_{halo} by MillenniumTNG and IllustrisTNG, which apply the same galaxy physical model (see also Pop et al. 2022, for an alternative estimate in IllustrisTNG300). FLAMINGO, and BAHAMAS, which have similar approaches for the BH feedback implementation, are closer to our observed relation, although they do not follow the observed power law, in particular in the M_{halo} range $10^{13.5-14.5} M_{\odot}$ (see also Salcido et al. 2023). The *Magneticum* simulation reproduces the observed relation reasonably well, with a slightly higher normalization that remains consistent within 1σ of the observations (see also Angelinelli et al. 2022). SIMBA also shows agreement within 1σ , albeit with slightly lower concordance. In contrast, Illustris exhibits an overly efficient evacuation of gas from halos across all masses. It is important to note that Genel et al. (2014) provides the gas fraction relation for all phases of gas rather than exclusively the hot phase. Consequently, the relation depicted in the bottom-right panel of Fig. 4.3 represents an upper limit to the hot gas-only relation.

The mass range of $10^{13.5} - 10^{14} M_{\odot}$, where most predictions deviate most significantly from the observed relation, warrants further investigation. To this end, we compare the electron density profiles derived from our stacking analysis to predictions from simulations. For *Magneticum*, the electron density profile is obtained directly from simulation data, while other profiles are taken from the review by Oppenheimer et al. (2021). As shown in Fig. 7, the profiles from *Magneticum* and SIMBA align most closely with the observations. In contrast, the normalizations of the EAGLE (Schaye et al. 2015) and IllustrisTNG simulations exceed observational results by a factor of approximately three. These results are more consistent with those from studies of bright X-ray groups, which naturally contain a higher gas fraction (e.g., Lovisari et al. 2015; Sun et al. 2009).

The discrepancies among simulations are largely attributable to differences in the treatment of galaxy formation physics and the associated timing and effects of black hole feedback on the intracluster medium (ICM). These variations make it challenging to isolate specific drivers of the observed differences, as they likely arise from a combination of factors. For example, Kauffmann et al. (2019) provide a compelling illustration of this complexity through a trace particle analysis comparing Illustris (Nelson et al. 2015) and IllustrisTNG. Their study demonstrates that Illustris evacuates hot gas from galaxy groups more effectively than IllustrisTNG (see also Hadzhiyska et al. 2024). The findings by Kauffmann et al. (2019) attribute these differences to the sub-grid models of feedback, which affect the timing of gas displacement, cooling, and collapse during galaxy evolution. However, the observed differences in the dependence on group or cluster mass suggest that an important factor may be the inclusion (or lack thereof) of halo mass-dependent feedback parameters. For instance, kinetic feedback models vary across simulations and are absent in *Magneticum*, which could play a critical role in shaping the observed trends.

4.4. Comparison with eRASS:1 data

To further validate our findings, we compare them with a subsample of groups and clusters selected from eRASS:1 observations as presented by Bulbul et al. (2024). This subsample, illustrated in Fig. 8, comprises all clusters and groups at $z < 0.05$ with a well-defined optical counterpart in the matched catalog provided in the eRASS:1 data release, as described by Bulbul et al. (2024). These systems include only those with more than five spectroscopic members. A flux cut of $10^{-13.5} \text{ erg s}^{-1} \text{ cm}^{-2}$




Fig. 7. Electron density profile for groups at $10^{13} M_{\odot} < M_{200} < 10^{14} M_{\odot}$ from this work (blue dashed-dotted curve), Lovisari et al. (2015) (black dashed curve) and Sun et al. (2009) (grey dotted curve), compared with the predictions of the hydrodynamical simulations in the same M_{200} mass bin: *Magneticum* (pink curve), IllustrisTNG100 (red curve), EAGLE (orange curve) and Simba (green curve). With the exclusion of the *Magneticum* data provided by Popesso et al. (2024c), the profiles of the simulations are taken from the review of Oppenheimer et al. (2021).




Fig. 8. *Upper panel:* Comparison of the observed Y_{gas} versus mass relations within R_{500} with the f_{gas} values within the same radius as given by Bulbul et al. (2024) for the eRASS:1 extended objects at $z < 0.05$ and with an optical counterpart. *Lower panel:* residuals of the eRASS:1 data from the best fit of Fig. 4 expressed in dex ($\log(f_{\text{gas}}) - \log(\text{fit})$).

was applied to ensure a 50% complete sample for systems with $M_{500} > 6 \times 10^{13} M_{\odot}$, following the completeness criteria outlined by Bulbul et al. (2024). Additionally, Fig. 8 includes systems with masses below this completeness limit.

The gas masses reported by Bulbul et al. (2024) were estimated using the methodology described in Liu et al. (2022a), which was previously applied to eFEDS-detected systems. Total masses were derived using scaling relations calibrated with weak lensing mass estimates (see Bulbul et al. 2024, for further details). In these analyses, eROSITA data were simultaneously fitted to extract M_{500} and temperature, iteratively refining the aperture size to define R_{500} such that the data aligned with

the observed $L_X - M_{500}$ scaling relation. As a result, all derived measurements are inherently correlated.

Despite these correlations, we find excellent agreement between our best-fit $f_{gas} - M_{halo}$ relation and the independent estimates from Bulbul et al. (2024). This consistency further underscores the robustness of our results and strengthens confidence in the methodologies employed.

5. Discussion & Conclusions

Using the stacking results from optically selected groups in eFEDS and the eROSITA stacked surface brightness profile of the CHEX-MATE clusters, we provide a comprehensive measurement of the $f_{gas} - M_{halo}$ relation over the largest halo mass range and to the largest radii ever probed for galaxy systems at $z < 0.2$. Extensive tests conducted on an analogous mock dataset ensure that our results are robust against selection biases. We find that the $f_{gas} - M_{halo}$ relation is well-described by a power law with a consistent shape (within $1 - 2\sigma$) when estimated within both R_{500} and R_{200} radii. This relation is in agreement with other studies that utilize X-ray survey data of similar depth, such as eFEDS and XMM-XXL (see e.g., Eckert et al. 2016). However, our results indicate a lower f_{gas} in the group regime compared to studies based on X-ray bright groups (e.g., Sun et al. 2009; Lovisari et al. 2015; Eckert et al. 2021). We interpret this discrepancy as a selection effect, with X-ray brightest nearby groups occupying the upper envelope of the $f_{gas} - M_{halo}$ relation at fixed halo mass.

Comparing our observed $f_{gas} - M_{halo}$ relation with predictions from various hydrodynamical simulations reveals that most current state-of-the-art models tend to over-predict the gas fraction across different halo mass ranges. Only *Magneticum* and, to a lesser extent, SIMBA align with the observed relation. Interestingly, the most significant discrepancies are not evident at the Milky Way group mass scale, where simulations generally perform well, but rather at the scale of massive groups and poor clusters ($13.5 < \log(M_{500}/M_\odot) < 14.3$). These discrepancies are unlikely to arise from systematic biases in our f_{gas} measurements, as our best-fit relation aligns well with literature data compilations (Fig. 4). Instead, while *Magneticum* and SIMBA accurately reproduce the electron density profiles derived from the data, EAGLE and IllustrisTNG overestimate the normalization of these profiles, leading to an overprediction of gas mass fractions.

The low f_{gas} values observed at the group mass scale, approximately 20–40% of the cosmic baryon fraction, suggest that a significant portion of the hot gas may reside beyond the virial region or exist in non-X-ray-emitting phases. Simulations predominantly support the first scenario, where feedback mechanisms expel gas to regions far beyond the virial radius, particularly in lower-mass halos. Studies such as Angelinelli et al. (2022) and Ayromlou et al. (2023) demonstrate that in both *Magneticum* and IllustrisTNG, most baryons in the form of hot gas are displaced well beyond the virial radius in Milky Way-sized halos and massive groups. This displacement implies that the halo closure radius—where baryon content aligns with the cosmic value—extends significantly beyond R_{200} for most group-sized systems. However, in IllustrisTNG, this gas expulsion is insufficient at the massive group and poor cluster scales, where our observations reveal discrepancies in f_{gas} of up to a factor of three. This may indicate that the moderated or halo-mass-dependent feedback in IllustrisTNG, introduced to better match galaxy properties (Pillepich et al. 2019), does not expel gas as efficiently as the original Illustris model (Nelson et al. 2015).

This discrepancy is further highlighted in Hadzhiyska et al. (2024), which reports kinematic Sunyaev-Zeldovich (kSZ) effect measurements from the Atacama Cosmology Telescope (ACT), stacked on the luminous red galaxy (LRG) sample of the Dark Energy Spectroscopic Instrument (DESI). These observations detect gas extending well beyond the virial radius at high significance ($> 40\sigma$), showing better agreement with Illustris predictions than with IllustrisTNG (see also Amodeo et al. 2021). It is worth noting that the feedback adjustments in IllustrisTNG improve predicted galaxy properties, such as color and star formation rates, compared to Illustris (Sparre et al. 2015; Donnari et al. 2021). However, these adjustments appear to compromise the accuracy of gas distribution predictions within halos. Similarly, while *Magneticum* performs well in reproducing halo gas properties (see also Popesso et al. 2024c,b), it overquenches local galaxy populations (Mazengo et al., in prep.), as does SIMBA (Davé et al. 2019).

Other simulations, such as BAHAMAS and FLAMINGO, exhibit less extreme behavior compared to IllustrisTNG. While they do not perfectly reproduce the $f_{gas} - M_{halo}$ relation, the maximum disagreement is limited to a factor of two at $M_{500} \sim 10^{14} M_\odot$. Additionally, their galaxy populations do not suffer from the strong overquenching of star formation observed in *Magneticum*, or SIMBA, although their lower resolution poses limitations compared to these simulations (Schaye et al. 2023; McCarthy et al. 2017).

We conclude that current hydrodynamical simulations face a critical challenge in balancing subgrid physics. While strong feedback mechanisms effectively expel gas from halos, they often suppress star formation too aggressively, leading to inconsistencies in modeling galaxy populations. The critical challenge lies not only in determining the magnitude of energy feedback required to deplete or prevent gas cooling and inflow but also in understanding when and where these processes occur. Addressing this requires robust observational constraints on halo gas and galaxy properties across cosmic time and varying environments, which remain largely lacking.

In conclusion, our estimates of f_{gas} over a wide range of halo masses, from Milky Way-sized groups to clusters, and out to R_{200} distances, set severe constraints to theoretical models that investigate the co-evolution of the hot intra-group medium in the presence of the central galaxy BH feedback, and highlights the importance of avoiding selection biases when deriving halo properties that can depend on the halo selection process itself.

Acknowledgements

PP acknowledges financial support from the European Research Council (ERC) under the European Union’s Horizon Europe research and innovation programme ERC CoG CLEVeR (Grant agreement No. 101045437). AB acknowledges the financial contribution from the INAF mini-grant 1.05.12.04.01 “*The dynamics of clusters of galaxies from the projected phase-space distribution of cluster galaxies*”. KD acknowledges support by the COMPLEX project from the European Research Council (ERC) under the European Union’s Horizon 2020 research and innovation program grant agreement ERC-2019-AdG 882679. The calculations for the *Magneticum* simulations were carried out at the Leibniz Supercomputer Center (LRZ) under the project pr83li. GP acknowledges financial support from the European Research Council (ERC) under the European Union’s Horizon 2020 research and innovation program Hot-Milk (grant agreement No 865637), support from Bando per il Finanziamento della Ricerca Fondamentale 2022 dell’Istituto Nazionale di As-

trofisica (INAF): GO Large program and from the Framework per l'Attrazione e il Rafforzamento delle Eccellenze (FARE) per la ricerca in Italia (R20L5S39T9). SVZ and VB acknowledge support by the *Deutsche Forschungsgemeinschaft*, DFG project nr. 415510302

This work is based on data from eROSITA, the soft X-ray instrument aboard SRG, a joint Russian-German science mission supported by the Russian Space Agency (Roskosmos), in the interests of the Russian Academy of Sciences represented by its Space Research Institute (IKI), and the Deutsches Zentrum für Luft- und Raumfahrt (DLR). The SRG spacecraft was built by Lavochkin Association (NPOL) and its subcontractors and is operated by NPOL with support from the Max Planck Institute for Extraterrestrial Physics (MPE).

The development and construction of the eROSITA X-ray instrument was led by MPE, with contributions from the Dr. Karl Remeis Observatory Bamberg & ECAP (FAU Erlangen-Nuernberg), the University of Hamburg Observatory, the Leibniz Institute for Astrophysics Potsdam (AIP), and the Institute for Astronomy and Astrophysics of the University of Tübingen, with the support of DLR and the Max Planck Society. The Argelander Institute for Astronomy of the University of Bonn and the Ludwig Maximilians Universität Munich also participated in the science preparation for eROSITA.

The eROSITA data shown here were processed using the eSASS software system developed by the German eROSITA consortium.

GAMA is a joint European-Australasian project based around a spectroscopic campaign using the Anglo-Australian Telescope. The GAMA input catalogue is based on data taken from the Sloan Digital Sky Survey and the UKIRT Infrared Deep Sky Survey. Complementary imaging of the GAMA regions is being obtained by a number of independent survey programmes including GALEX MIS, VST KiDS, VISTA VIKING, WISE, Herschel-ATLAS, GMRT and ASKAP providing UV to radio coverage. GAMA is funded by the STFC (UK), the ARC (Australia), the AAO, and the participating institutions. The GAMA website is <https://www.gama-survey.org/>.

References

- Amodeo, S., Battaglia, N., Schaan, E., et al. 2021, *Phys. Rev. D*, 103, 063514
- Anderson, M. E., Gaspari, M., White, S. D. M., Wang, W., & Dai, X. 2015, *MNRAS*, 449, 3806
- Angelinelli, M., Ettori, S., Dolag, K., Vazza, F., & Ragagnin, A. 2022, *A&A*, 663, L6
- Arnaud, M., Pointecouteau, E., & Pratt, G. W. 2007, *A&A*, 474, L37
- Asplund, M., Grevesse, N., Sauval, A. J., & Scott, P. 2009, *ARA&A*, 47, 481
- Ayromlou, M., Nelson, D., & Pillepich, A. 2023, *MNRAS*, 524, 5391
- Bahar, Y. E., Bulbul, E., Clerc, N., et al. 2022, *A&A*, 661, A7
- Biffi, V., Dolag, K., & Merloni, A. 2018, *MNRAS*, 481, 2213
- Blanton, M. R., Bershady, M. A., Abolfathi, B., et al. 2017, *AJ*, 154, 28
- Brunner, H., Liu, T., Lamer, G., et al. 2022, *A&A*, 661, A1
- Bulbul, E., Chiu, I. N., Mohr, J. J., et al. 2019, *ApJ*, 871, 50
- Bulbul, E., Liu, A., Kluge, M., et al. 2024, arXiv e-prints, arXiv:2402.08452
- Bulbul, E., Liu, A., Pasini, T., et al. 2022, *A&A*, 661, A10
- CHEX-MATE Collaboration, Arnaud, M., Ettori, S., et al. 2021, *A&A*, 650, A104
- Crossett, J. P., McGee, S. L., Ponman, T. J., et al. 2022, arXiv e-prints, arXiv:2203.14200
- Davé, R., Anglés-Alcázar, D., Narayanan, D., et al. 2019, *MNRAS*, 486, 2827
- Dolag, K., Komatsu, E., & Sunyaev, R. 2016, *MNRAS*, 463, 1797
- Donnari, M., Pillepich, A., Nelson, D., et al. 2021, *MNRAS*, 506, 4760
- Driver, S. P., Bellstedt, S., Robotham, A. S. G., et al. 2022, *MNRAS*, 513, 439
- Dutton, A. A. & Macciò, A. V. 2014, *MNRAS*, 441, 3359
- Eckert, D., Ettori, S., Coupon, J., et al. 2016, *A&A*, 592, A12
- Eckert, D., Gaspari, M., Gastaldello, F., Le Brun, A. M. C., & O'Sullivan, E. 2021, *Universe*, 7, 142
- Eckert, D., Ghirardini, V., Ettori, S., et al. 2019, *A&A*, 621, A40
- Ettori, S. 2015, *MNRAS*, 446, 2629
- Fabjan, D., Borgani, S., Tornatore, L., et al. 2010, *MNRAS*, 401, 1670
- Galárraga-Espinosa, D., Langer, M., & Aghanim, N. 2021, arXiv e-prints, arXiv:2109.06198
- Genel, S., Vogelsberger, M., Springel, V., et al. 2014, *MNRAS*, 445, 175
- Giles, P. A., Robotham, A., Ramos-Ceja, M. E., et al. 2022, *MNRAS*, 511, 1227
- Gonzalez, A. H., Sivanandam, S., Zabludoff, A. I., & Zaritsky, D. 2013, *ApJ*, 778, 14
- Hadzhiyska, B., Ferraro, S., Ried Guachalla, B., et al. 2024, arXiv e-prints, arXiv:2407.07152
- Kauffmann, G., Nelson, D., Borthakur, S., et al. 2019, *MNRAS*, 486, 4686
- Klein, M., Oguri, M., Mohr, J. J., et al. 2022, *A&A*, 661, A4
- Le Brun, A. M. C., McCarthy, I. G., Schaye, J., & Ponman, T. J. 2014, *MNRAS*, 441, 1270
- Liu, A., Bulbul, E., Ghirardini, V., et al. 2022a, *A&A*, 661, A2
- Liu, T., Buchner, J., Nandra, K., et al. 2022b, *A&A*, 661, A5
- Lovisari, L. & Ettori, S. 2021, *Universe*, 7, 254
- Lovisari, L. & Reiprich, T. H. 2019, *MNRAS*, 483, 540
- Lovisari, L., Reiprich, T. H., & Schellenberger, G. 2015, *A&A*, 573, A118
- Lyskova, N., Churazov, E., Khabibullin, I. I., et al. 2023, arXiv e-prints, arXiv:2305.07080
- Mahdavi, A., Hoekstra, H., Babul, A., et al. 2013, *ApJ*, 767, 116
- Mantz, A. B., von der Linden, A., Allen, S. W., et al. 2015, *MNRAS*, 446, 2205
- Marini, I., Popesso, P., Lamer, G., et al. 2024a, *A&A* submitted, arXiv:2411.16455
- Marini, I., Popesso, P., Lamer, G., et al. 2024b, *A&A*, 689, A7
- McCarthy, I. G., Schaye, J., Bird, S., & Le Brun, A. M. C. 2017, *MNRAS*, 465, 2936
- McCarthy, I. G., Schaye, J., Ponman, T. J., et al. 2010, *MNRAS*, 406, 822
- Mulchaey, J. S. 2000, *ARA&A*, 38, 289
- Mulroy, S. L., Farahi, A., Evrard, A. E., et al. 2019, *MNRAS*, 484, 60
- Navarro, J. F., Frenk, C. S., & White, S. D. M. 1997, *ApJ*, 490, 493
- Nelson, D., Pillepich, A., Genel, S., et al. 2015, *Astronomy and Computing*, 13, 12
- Nugent, J. M., Dai, X., & Sun, M. 2020, *ApJ*, 899, 160
- Oppenheimer, B. D., Babul, A., Bahé, Y., Butsky, I. S., & McCarthy, I. G. 2021, *Universe*, 7, 209
- Osmond, J. P. F. & Ponman, T. J. 2004, *MNRAS*, 350, 1511
- Pakmor, R., Springel, V., Coles, J. P., et al. 2022, arXiv e-prints, arXiv:2210.10060
- Pearson, R. J., Ponman, T. J., Norberg, P., et al. 2017, *MNRAS*, 469, 3489
- Peebles, P. J. E. 1980, *The large-scale structure of the universe*
- Pillepich, A., Nelson, D., Springel, V., et al. 2019, *MNRAS*, 490, 3196
- Planck Collaboration, Ade, P. A. R., Aghanim, N., et al. 2016, *A&A*, 594, A13
- Planck Collaboration, Aghanim, N., Akrami, Y., et al. 2020, *A&A*, 641, A6
- Ponman, T. J., Bourner, P. D. J., & Ebeling, H. 1996, in *Roentgenstrahlung from the Universe*, ed. H. U. Zimmermann, J. Trümper, & H. Yorke, 357–360
- Pop, A.-R., Hernquist, L., Nagai, D., et al. 2022, arXiv e-prints, arXiv:2205.11528
- Popesso, P., Biviano, A., Böhringer, H., Romaniello, M., & Voges, W. 2005, *A&A*, 433, 431
- Popesso, P., Biviano, A., Bulbul, E., et al. 2024a, *MNRAS*, 527, 895
- Popesso, P., Marini, I., & Dolag, K. 2024b, *A&A* submitted, arXiv:2411.17120
- Popesso, P., Marini, I., & Dolag, K. 2024c, *A&A* submitted, arXiv:2411.16546
- Pratt, G. W., Croston, J. H., Arnaud, M., & Böhringer, H. 2009, *A&A*, 498, 361
- Puchwein, E., Sijacki, D., & Springel, V. 2008, *ApJ*, 687, L53
- Ragagnin, A., Andreon, S., & Puddu, E. 2022, *A&A*, 666, A22
- Rasmussen, J. & Ponman, T. J. 2009, *MNRAS*, 399, 239
- Robotham, A. S. G., Norberg, P., Driver, S. P., et al. 2011, *MNRAS*, 416, 2640
- Rozo, E., Rykoff, E. S., Evrard, A., et al. 2009, *ApJ*, 699, 768
- Rykoff, E. S., McKay, T. A., Becker, M. R., et al. 2008, *ApJ*, 675, 1106
- Salcido, J., McCarthy, I. G., Kwan, J., Upadhye, A., & Font, A. S. 2023, *MNRAS*, 523, 2247
- Salvato, M., Wolf, J., Dwelly, T., et al. 2022, *A&A*, 661, A3
- Schaye, J., Crain, R. A., Bower, R. G., et al. 2015, *MNRAS*, 446, 521
- Schaye, J., Kugel, R., Schaller, M., et al. 2023, arXiv e-prints, arXiv:2306.04024
- Sijacki, D., Springel, V., Di Matteo, T., & Hernquist, L. 2007, *MNRAS*, 380, 877
- Sparre, M., Hayward, C. C., Springel, V., et al. 2015, *MNRAS*, 447, 3548
- Sun, M., Voit, G. M., Donahue, M., et al. 2009, *ApJ*, 693, 1142
- Tempel, E., Tuvikene, T., Kipper, R., & Libeskind, N. I. 2017, *A&A*, 602, A100
- Vallés-Pérez, D., Planelles, S., & Quilis, V. 2020, *MNRAS*, 499, 2303
- Vikhlinin, A., Kravtsov, A., Forman, W., et al. 2006, *ApJ*, 640, 691
- Vikhlinin, A., Kravtsov, A. V., Burenin, R. A., et al. 2009, *ApJ*, 692, 1060
- Vulic, N., Hornschemeier, A. E., Haberl, F., et al. 2022, *A&A*, 661, A16
- Yang, X., Mo, H. J., van den Bosch, F. C., et al. 2007, *The Astrophysical Journal*, 671, 153
- Zhang, Y., Comparat, J., Ponti, G., et al. 2024, arXiv e-prints, arXiv:2401.17309